

A1 EROSION SEDIMENT CONTROL PLAN - AREA 4
SCALE 1" = 50'


GENERAL NOTES

1. ALL ELEVATIONS ARE IN FEET.
2. CONTOUR INTERVALS ARE 1.0'.
3. REFER TO G-100 FOR LAYDOWN AND HAUL ROUTE.
4. INSTALL EROSION CONTROL MEASURE AS INDICATED ON THE PLANS AND AS FIELD CONDITIONS WARRANT PRIOR TO COMMENCING AND CONSTRUCTION ACTIVITIES. REPAIRS OR MODIFICATIONS TO THE MEASURES SHOULD BE MADE IF CONTROL MEASURES PROVE INEFFECTIVE OR IF ADDITIONAL CONTROL MEASURES ARE NECESSARY.


KEYNOTES

1. CONSTRUCT SILT FENCE PER DETAIL B5/CE501
2. CONSTRUCT ROCK CHECK DAM PER DETAIL A5/CE501
3. CONSTRUCT STORM DRAIN CULVERT SEE CG SERIES
4. CONSTRUCT TEMPORARY STABILIZED CONSTRUCTION ENTRANCE PER DETAIL B1/CE501

LEGEND



RIP RAP/ROCK CHECK DAM
PER DETAIL A5/CE501



TEMPORARY STABILIZED
CONSTRUCTION ENTRANCE



PROPERTY BOUNDARY



SILT FENCE



PROPOSED CONTOUR LINE




EXISTING CONTOUR LINE



SWALE

KEY PLAN



777 Main Street
Fort Worth, TX 76102
Earth Systems Engineering
License Exp. Date: 12/31/2024

REVISION		DATE	BY	APPROVED	DR	DCG	JPB	CHK
100% ISSUED FOR CONSTRUCTION - DEVELOPMENT		2024-07-19	DS	TM				
100% ISSUED FOR REVIEW - DEVELOPMENT		2024-07-01	DS	TM				
NO.		DATE	BY	APPROVED	DR	DCG	JPB	CHK

Site Development
Camden OSD
Camden, Arkansas
Aerjet Rocketdyne

EROSION SEDIMENT CONTROL -
AREA 4

SHEET NO
CE104

SCALE AS SHOWN
DATE 07/01/2024
PROJ D3547405
DWG CE104.dwg
SHEET 14 of 99

PLOT DATE/TIME: 7/23/2024 12:34 PM