

Notes:

Volts: 480V
Phases: 3
Wires: 3

A.I.C. Rating: 35K
Mains Type: MLO
Mains Rating: 1000 A
MCB Rating: 0 A

Total Conn. Load:	596928 VA
Total Amps:	718 A

Legend:

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
LTG	3543 VA	100.00%	3543 VA		
MOT	592385 VA	100.00%	592385 VA	Total Conn. Load:	596928 VA
REC	1000 VA	100.00%	1000 VA	Total Est. Demand:	596928 VA
				Total Conn. Current:	718 A
				Total Est. Demand Current:	718 A

Notes:

NOTES:

Volts: 120/208V
Phases: 3
Wires: 4

A.I.C. Rating: 10K
Mains Type: MCB
Mains Rating: 225 A
MCB Rating: 150 A

Total Load:	2197 VA	2631 VA	1603 VA
Total Amps:	19 A	23 A	13 A

Legend:

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
LTG	3543 VA	100.00%	3543 VA		
MOT	1888 VA	100.00%	1888 VA	Total Conn. Load:	6431 VA
REC	1000 VA	100.00%	1000 VA	Total Est. Demand:	6431 VA
				Total Conn. Current:	18 A
				Total Est. Demand Current:	18 A

Jacobs
1999 Bryan Street Suite 3500 Dallas, TX 75201
Tel: 214/636-0445 Fax: 214/638-0447
Entirety Jacobs Engineering Group Inc.
License Type: Engineering
License No.: 1717
Exp. Date: 12/31/2024



Conditioning-Boxes
Camden OSD
Calhoun County, Arkansas
Aerojet Rocketdyne

Jacobs **NABHOLZ**

ELECTRICAL PANEL SCHEDULES

SHEET NO.

E-710

SCALE

DATE _____

PROJ

DWG

CMON-OSD_Conditioning-Boxes_E-710

PLOT DATE/TIME: 9/16/2024 9:04:29 AM