CONCRETE STEM WALL SCHEDULE

WALL TYPE	THICKNESS	VERT REINF	HORZ REINF
ST1	1' - 2"	#4@12"OC EF	#4@12"OC EACH FACE

CONCRETE WALL SCHEDULE

WALL TYPE	THICKNESS	VERT REINF	HORZ REINF
W12	1' - 0"	#6@12" OC EF VERT	#4@12" OC EF HORIZ
W24	2' - 0"	#8@12" OC EF VERT	#6@12 OC EF HORIZ

CONCRETE WALL FOOTING SCHEDULE

MARK	WIDTH	THICKNESS	LONGITUDINAL REINF T&B	TRANSVERSE REINF BOT	TRANSVERSE REINF TOP
WF4	4' - 0"	1' - 6"	#5@12"OC BOTTOM ONLY	#4 @ 12" O.C.	NO REINFORCEMENT
WF7	7' - 0"	1' - 6"	#5@12" OC	#4 @ 12" O.C.	#4 @ 12" o.c.
WF12	12' - 0"	2' - 0"	# 5@ 12" O.C. BOTTOM& # 4 @ 12" O.C. TOP	#7 @ 12" O.C.	#4 @ 12" o.c.
WF14	14' - 0"	2' - 0"	# 5@ 12" O.C. BOTTOM& # 4 @ 12" O.C. TOP	#7 @ 12" O.C.	#4 @ 12" o.c.

CONCRETE PEDESTAL SCHEDULE

Type	WIDTH	LENGTH	VERTICAL REINF	TIES	REMARKS
P24x33	2'-0"	2'-9"	8 - #7	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P24x36	2'-0"	3'-0"	8 - #7	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P24x45	2'-6"	3'-2"	8 - #8	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P24x48	2'-0"	4'-0"	12 - #7	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P28x33	2'-4"	2'-9"	8 - #7	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P28x36	2'-4"	3'-0"	8 - #8	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P28x45	2'-6"	3'-2"	8 - #8	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P28x48	2'-4"	4'-0"	12 - #7	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P36x36	3'-0"	3'-0"	12 - #7	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)
P36x72	3'-0"	6'-0"	18- # 8	#4@6"OC	TOP # TIES @ 2" O.C. (SEE A4/S-502 FOR MORE DETAILS)

CONCRETE FOOTING SCHEDULE

MARK	SIZE			BOTTOM REINF	TOP REINF
	LENGTH	WIDTH	THICK		
F6	6' - 0"	6' - 0"	<varies>	(8) #5 BARS EW	<varies>
F7	7' - 0"	7' - 0"	1' - 6"	(9) #5 BARS EW	#4@9" OC EW
F9	9' - 0"	9' - 0"	1' - 6"	#5@9" OC EW	#4@9" OC EW
F14x7	14' - 0"	7' - 0"	1' - 6"	#5@9" OC EW	#4@9" OC EW
F24x48	48' - 0"	24' - 0"	3' - 0"	#8@12" OC	#8@12" OC
F31x31	31' - 0"	31' - 0"	2' - 0"	#7@9" OC EW	#4@9" OC EW

MECHANICAL PAD SCHEDULE

MARK	THICKNESS (in.)	WIDTH (ft.)	LENGTH (ft)	LONG REINF.	TRAVERSE REINF.	NOTES
P1	8	10	48	#4 @ 12" O.C. TOP	#4 @ 12" O.C. TOP	SEE DETAIL C1/S-501 FOR MORE INFORMATION
P2	8	10	32	#4 @ 12" O.C. TOP	#4 @ 12" O.C. TOP	
P3	8	7	26	#4 @ 12" O.C. TOP	#4 @ 12" O.C. TOP	
P4	8'-0"	16'-0"	26'-0"	#4 @ 12" O.C. TOP	#4 @ 12" O.C. TOP	RAISE TOP OF PAD 6" MIN ABOVE FINISHED GRADE
P5	3'-0"	30'-0"	42'-0"	#8 @ 12" O.C. TOP & BOTTOM	#8 @ 12" O.C. TOP & BOTTOM	RAISE TOP OF PAD 6" MIN ABOVE FINISHED GRADE
P6	3'-0"	34'-0"	40'-0"	#8 @ 12" O.C. TOP & BOTTOM	#8 @ 12" O.C. TOP & BOTTOM	RAISE TOP OF PAD 6" MIN ABOVE FINISHED GRADE

NABHOLZ

STATE OF ARKANSAS
LICENSED PROFESSIONAL ENGINEER
No. 22954
DUSTIN C. LORANCE
09/18/2024

Jacobs
1999 Bryan Street Suite 2000
Dallas, TX 75201
Tel +1 214 638 0145
Fax +1 214 638 0447
Entity: Jacobs Engineering Group Inc.
License Type: Engineering
License #: 178
License Exp Date: 12/31/2024

NO.	DATE	REVISION	CHK	APV'D	BY	APV'D	TM
0	09/18/2024	100% ISSUED FOR CONSTRUCTION	HB	JAX	KFM	TM	

DSGN KFM
DR
CHK
APV'D

GMLRS
Camden OSD
Calhoun County, Arkansas
Aerojet Rocketdyne

STRUCTURAL SCHEDULES

SHEET NO
S-701

SCALE	3/4" = 1'-0"
DATE	09/18/2024
PROJ	D3754502
DWG	CMDN-OSD_GMLRS_S-701

© Jacobs Solutions 2023. ALL RIGHTS RESERVED.
REUSE OF DOCUMENTS: THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF JACOBS AND SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF JACOBS.