FINISH LEGEND

ITEM CODE	DESCRIPTION	MANUFACTURER	MODEL	COLOR	SIZE	NOTES
FLOORING						
EPX-3	EPOXY FLOORING - HIGH STRENGTH, CONDUCTIVE HEAVY DUTY	SIKA FLOOR	SIKAFLOOR 200 ESD	DARK GREY	-	
SC-1	SEALED AND HARDENED CONCRETE	TENNENT	ECO HARD N SEAL	CLEAR	-	
SDT-1	STATIC DISSIPATIVE TILE	ARMSTRONG FLOOR	EXCELON SDT	FOSSIL GRAY	12" X 12"	
WM-1	WALK-OFF MAT, SURFACE MOUNTED	MILLIKEN	OBEX BAR CUTX - SURFACE MOUNT	DARK GREY	10.87" X 39.37" PLANK	
BASE						
EPB-3	INTEGTRAL EPOXY BASE, CONDUCTIVE	SIKA FLOOR	SIKAFLOOR 200 ESD	DARK GREY	6" HIGH WITH COVE	
RB-1	RUBBER BASE	TARKETT	ROLLED GOODS	28 MEDIUM GREY	4" HIGH WITH COVE	
WALLS						
PEMP-1	PRE-ENGINEERED METAL LINEAR PANEL	TBD	TBD	TBD - PT-1 TO MATCH	TBD	
PT-1	FIELD PAINT	SHERWIN WILLIAMS	PROMAR 200, EGGSHELL	SW7035 AESTHETIC WHITE	-	
PT-2	ACCENT PAINT	SHERWIN WILLIAMS	PROMAR 200	SW7602 INDIGO BATIK	-	USED FOR DOORS, DOOR FRAMES, AND SIGNAGE COLOR; WILL MATCH EXTERIOR TRIM
CEILINGS						
ACT-1	ACOUSTICAL CEILING TILE	ARMSTRONG CEILING	OPTIMA TEGULAR LAY-IN	WHITE	24" X 24"	
OTS-1	OPEN TO STRUCTURE, PAINTED	SHERWIN WILLIAMS	PROMAR 200, EPOXY	SW7006 EXTRA WHITE	-	
MISCELLANEOUS						
CG-1	HEAVY DUTY RUBBER CORNER GUARD	INPRO	HEAVY DUTY RUBBER CORNER GUARD	BLACK	3" WING	

ROOM FINISH SCHEDULE

ROOM	NAME	FLOOR FINISH	BASE FINISH	WALL FINISH				CEILING FINISH
				NORTH	EAST	SOUTH	WEST	
100	VEST.	WM-1	RB-1	PT-1	PT-1	PT-1	PT-1	ACT-1
101	DRIVE THRU	EPX-3	EPB-3	PEMP-1	PEMP-1	PEMP-1	PEMP-1	OTS-1
102	GRINDER ROOM	EPX-3	EPB-3	PEMP-1	PEMP-1	PEMP-1	PEMP-1	OTS-1
103	UTILITY ROOM	SC-1	RB-1	PT-1	PT-1	PT-1	PEMP-1	OTS-1
104	IT CLOSET							
104	TELECOM IT CL.	SDT-1	RB-1	PT-1	PT-1	PT-1	PT-1	OTS-1
105	MECHANICAL YARD	NA	NA	NA	NA	NA	NA	NA

GENERAL SHEET NOTES

A. MANUFACTURER AND COLOR LISTED ARE INTENDED TO ESTABLISH LEVEL OF QUALITY, COLOR & FINISH, AND ARE NOT INTENDED TO LIMIT THE SELECTION OF OTHER MANUFACTURERS FOR EQUAL PRODUCTS.

B. ALL FINISHES ARE TO BE INSTALLED / APPLIED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.

C. FIELD VERIFY ALL DIMENSIONS PRIOR TO ORDERING FINISH MATERIALS.

D. ALL FLOORING TRANSITIONS ARE TO OCCUR AT THE CENTERLINE OF THE DOOR, DOORWAY, OR CEILING, UON.

E. GYPSUM BOARD WALLS ARE TO HAVE AN EGGSHELL FINISH, UON.

F. PAINTED GYPSUM BOARD CEILINGS ARE TO HAVE A FLAT FINISH, UON

G. DOORS AND FRAMES SCHEDULED TO BE PAINTED MUST HAVE A SEMI GLOSS FINISH, UON.

H. REFER TO ARCHITECTURE FOR EXTERIOR FINISHES

NO.	DATE	REVISION	BY	APV'D
0	09/18/2024	100% ISSUED FOR CONSTRUCTION - EXPANSION	IE	TM

DSGN	DR	CHK	APV'D
LTV	JMW	KC	TM

© Jacobs Solutions 2023. ALL RIGHTS RESERVED.

Jacobs
1999 Bryan Street Suite 3500 Dallas, TX 75201
Tel: 214.583.8500 Fax: 214.583.8640
Entity: Jacobs Consultants Inc.
License Type: Architecture
License: 0179
Exp. Date: 01/31/2025

REGISTERED ARCHITECT CHRIS ALFSTAD 12327 STATE OF ARKANSAS
09/18/2024
SEAL

REUSE OF DOCUMENTS: THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF JACOBS AND SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF JACOBS.

Grinder
Camden OSD
Calhoun County, Arkansas
Aerojet Rocketdyne

Jacobs NABHOLZ

INTERIOR
FINISH MATERIAL LEGEND AND SCHEDULE

SHEET NO
I-601

SCALE	12" = 1'-0"
DATE	09/18/2024
PROJ	D3754502
DWG	CMDN-OSD_Grinder_I-601

PLOT DATE/TIME: 9/18/2024 9:13:05 AM

9/18/2024 9:13:05 AM I-601
Autodesk Docs://US_D3754500_FED_Aerojet Rocketdyne/D3754500_CMDN_OSD_Grinder_ARCH-INT.rvt