



LOCATIONS OF ALL CEILING FANS (CF) SHALL BE COORDINATED SUCH THAT THE HUBS (CENTER OF FANS) ARE CENTRALLY LOCATED BETWEEN FOUR (4) SPRINKLER HEADS AND SUPPORTED BETWEEN TWO (2) JOISTS. SUPPORT FAN BETWEEN TWO (2) JOISTS PER MANUFACTURE INSTALLATION REQUIREMENTS AND DETAILS. PROVIDE ALL MOUNTING HARDWARE. INSTALLATION REQUIREMENTS DETAILS IN SUBMITTALS. THIS INCLUDES INSTALLING SAFETY CABLES ON ALL FANS PER MANUFACTURES REQUIREMENTS. FANS SHALL NOT BE OPERATED WITHOUT PROPERLY INSTALLED SAFETY CABLE. FAN SHALL ALSO BE INSTALLED AT AN ELEVATION TO ENSURE THE FAN BLADES HAVE A VERTICAL MINIMUM CLEARANCE OF 30" FROM ALL SPRINKLER DEFLECTORS (INSTALL AS HIGH AS POSSIBLE AFTER MEETING THIS REQUIREMENT WITH MAINTAINING TENANTS CLEAR HEIGHTS).

ADDITIONALLY THE FAN SHALL BE COORDINATED WITH TENANT TO ENSURE:

- FANS SHALL BE INSTALLED A MINIMUM OF 50" (75" PREFERRED) AWAY FROM RTU SUPPLY DROP BOXES.
- FANS SHALL BE INSTALLED A MINIMUM OF 7" (10" PREFERRED) FROM ANY AREA THAT COULD BE USED FOR STORAGE RACK PRODUCT PICKING.
- FANS SHALL ALSO BE INSTALLED A MINIMUM OF 3' FROM RIGID AND 10' FROM NON-RIGID SUPPORT (SIGNAGE).

FAN DISCONNECT/CONTROLLERS SHALL BE WALL OR COLUMN MOUNTED WITH BOTTOM OF DEVICE AT 6'-0" (72") AFF. COORDINATE INTERFACE OF FANS WITH FIRE ALARM TO DEACTIVATE UPON FIRE ALARM PER NFPA 72. HVLS FANS INSTALLATION SHALL COMPLY WITH CURRENT ADOPTED NFPA 13 SECTION 11.1.7.

PARTIAL WAREHOUSE HVAC PLAN

0' 1' 2' 3'
SCALE: 1/16" = 1'-0"

M201	M202	M203	M204
M205	M206	M207	M208

KEY PLAN

APPROVAL STAMP:

HAMILTON DEVELOPMENT
ONE MUSIC SQUARE SOUTH, SUITE 110 NASHVILLE, TN 37203

SMD
SM DESIGN & CONSULTING, PC
855 Bloomfield Avenue, Suite 220
Glen Ridge, NJ 07028
Telephone: 973-259-9500
www.smdpc.com

CONSULTANT
SHIRK & O'DONOVAN
CONSULTING ENGINEERS
SHIRK & O'DONOVAN CONSULTING ENGINEERS, INC.
370 EAST WILSON BRIDGE ROAD
WORTHINGTON, OH 43085
PH: 614.436.6465

MEP CONSULTANTS
KRAEMER CONSULTING ENG PLLC
2050 W. WHISPERING WIND DR. STE 158
PHOENIX, AZ 85085
PH: 602.285.1669

harrington
FIRE PROTECTION CONSULTANTS
HARRINGTON GROUP, INC.
3237 SATELLITE BOULEVARD, SUITE 525
DULUTH, GA 30096
PH: 770.564.3505

HARGIS
TELECOMMUNICATIONS CONSULTANTS
HARGIS ENGINEERS, INC.
1201 THIRD AVENUE, SUITE 600
SEATTLE, WA 98101
PH: 206.448.3376

IN COORDINATION WITH DEVELOPERS CONSULTANT WORKING IN PARALLEL:

Pickering
Pickering Firm, Inc.
Engineering
Planning - Surveying

SITE CIVIL
PICKERING FIRM, INC.
1700 KIRK RD. SUITE 120
LITTLE ROCK, AR 72223
PH: 501.246.3578

SEAL
KCE JOB #24-240
03.26.25
Professional Engineer

END USER
amazon

PROJECT DESCRIPTION
AMAZON LIT3
2026 IUX GENSHM
CROSS-DOCK WAREHOUSE FACILITY
(RECEIPT & REDISTRIBUTION)

PROJECT LOCATION
Port of Little Rock
(INDUSTRIAL PARK)
LITTLE ROCK, ARKANSAS 72206
(UNINCORPORATED PARCELS) PULASKI COUNTY

SHEET TITLE
PARTIAL WAREHOUSE
HVAC PLAN

SHEET MANAGEMENT
PROJECT NO.:
DATE ISSUED:
DRAWN BY: VARIOUS
REVIEWED BY: MK
ISSUANCE / REVISION SCHEDULE
DATE DESCRIPTION
02/20/2025 REVIEW SET - 10% PERMIT
03/20/2025 100% CD - FOR PERMIT

SHEET NUMBER
M-208