



AIA® Document G709™ – 2018

Proposal Request

PROJECT: *(name and address)*
AWSOM
Bentonville, Arkansas

CONTRACT INFORMATION:
Contract For: General Construction
Date: 11.29.2021

Architect’s Project Number: 993A
Proposal Request Number: 089
Proposal Request Date: 12.12.2024

OWNER: *(name and address)*
AWSOM Lands, LLC
PO Box 2030
Bentonville, AR 72712

ARCHITECT: *(name and address)*
Polk Stanley Wilcox
509 W. Spring St., Ste 150
Fayetteville, AR 72701

CONTRACTOR: *(name and address)*
Crossland Construction Company
1800 S. 52nd Street, Suite 410
Rogers, AR 72758

The Owner requests an itemized proposal for changes to the Contract Sum and Contract Time for proposed modifications to the Contract Documents described herein. The Contractor shall submit this proposal within five (5) days or notify the Architect in writing of the anticipated date of submission.

(Insert a detailed description of the proposed modifications to the Contract Documents and, if applicable, attach or reference specific exhibits.)

Refer to the attached Proposal Request 089 Narrative listing revised drawings with brief description of changes.

THIS IS NOT A CHANGE ORDER, A CONSTRUCTION CHANGE DIRECTIVE, OR A DIRECTION TO PROCEED WITH THE WORK DESCRIBED IN THE PROPOSED MODIFICATIONS.

REQUESTED BY THE ARCHITECT:

Mark Herrmann, AIA

PRINTED NAME AND TITLE

PROPOSAL REQUEST 089

Green Roof Devices and High Roof Security Cameras

ISSUED: December 12, 2024

PROJECT: AWSOM
BENTONVILLE, AR

FROM ARCHITECT: POLK STANLEY WILCOX ARCHITECTS
801 SOUTH SPRING ST.
LITTLE ROCK AR 72201

TO CONTRACTOR: CROSSLAND CONSTRUCTION COMPANY, INC

PROPOSAL REQUEST 89 BRIEF

Revised and new drawings in PR 089 update devices located on the Green Roof and add security cameras to the high roof per request for updated lighting layout, green roof security cameras, and wireless access points.

REVISED DRAWING SHEETS AND SPECIFICATIONS

1) LANDSCAPE ARCHITECTURAL

- a) Refer to Revised Sheet **L000B**, with original issue date 10.21.2024 and revised date 12.12.2024.
 - Updated sheet issuance for PR 089.
- b) Refer to Revised Sheet **L224**, with original issue date 03.13.2023 and revised date 12.12.2024.
 - Revised Holiday Controlled Receptacle locations.
 - Revised Charging Pedestal locations.
 - Added Strobe on Post locations.
 - Added Exit Sign on Post locations.
 - Added Light and Strobe on 16' Tall Pole locations.
 - Added Light, Exit Sign, and Strobe on 16' Tall Pole locations.
 - Updated Legend
- c) Refer to Revised Sheet **L225**, with original issue date 03.13.2023 and revised date 12.12.2024.
 - Revised Holiday Controlled Receptacle locations.
 - Revised Charging Pedestal locations.
 - Added Strobe on Post locations.
 - Added Exit Sign on Post locations.
 - Added Light and Strobe on 16' Tall Pole locations.
 - Added Light, Exit Sign, and Strobe on 16' Tall Pole locations.
 - Updated Legend.

2) ARCHITECTURAL

- a) Refer to New Sheet **A940**, with original issue date 12.12.2024.
 - Legend added elevating rooftop devices.

3) ELECTRICAL

- a) General clarification: For all charging pedestals and precise dimensions for locations of devices, refer to landscape plans. The revisions indicated below are intended to identify significant location changes.
- b) Revised Sheet **E100.2**, Detail 1, with original issue date 02.24.2023 and revised date 12.12.2024.
 - To align with landscape coordination:
 - (1) Adjust location of two type SB4 light fixtures.
 - (2) Adjust location of one XWB2 fixture.
 - (3) Adjust location of one type H holiday receptacle pedestal.
- c) Revised Sheet **E100.2**, Detail 2, with original issue date 02.24.2023 and revised date 12.12.2024.
 - To align with landscape coordination and RFI 525:
 - (1) Remove exit sign on level 3 plaza.
 - (2) Adjust location of fixture SB4.

4) FIRE PROTECTION

- a) Revised Sheet **FP105A**, Detail 1, with original issue date 02.24.2023 and revised date 12.12.2024.
 - To align with landscape coordination:
 - (1) Adjust location of 15 fire alarm appliances.
 - (2) Remove 1 fire alarm appliance.

5) TELECOM

- a) Revised Sheet **TN000** with original issue date 02.24.2023 and revised date 12.12.2024.
 - Added note for wireless access points to legend.
- b) Added Sheet **TN100.2** with issue date 12.12.2024.
 - Added 5 wireless access point bollards to green roof.
 - Added conduit, pull box, and cabling for wireless access points.
- c) Revised Sheet **TN500** with original issue date 02.24.2023 and revised date 12.12.2024.
 - Added Exterior Wireless Access Point in Bollard detail.

6) SECURITY

- a) Added Sheet **TY105A** with issue date 12.12.2024.
 - Added three cameras to Roof Plan – Section A for surveilling Green Roof, Area B, of Roof Plan. Revised mounting location of Northeast Rooftop Camera.
- b) Revised Sheet **TY500** with original issue date 02.24.2023 and revised date 12.12.2024.
 - Revised sheet to include Details for Parapet mounting guidelines for Rooftop Cameras.

7) REVISED SPECIFICATION

- a) Revised Specification Section **271500 Communications Horizontal Cabling**
 - Added section 2.05 Wireless Access Point Bollard

End of PR 089

PART 1 - GENERAL REQUIREMENTS

1.01 SUMMARY

- A. Provide a complete Category 6A horizontal (work area) telecommunications cabling system as shown on the TN sheets and in accordance with these Contract Documents.
- B. This section specifies the following:
 - 1. Horizontal Copper Cable
 - 2. Copper Connectivity
 - a) Faceplates
 - b) Surface Box
 - c) Jacks/plugs/inserts
 - 3. Power Over Ethernet Extenders

1.02 RELATED SECTIONS INCLUDE THE FOLLOWING

- A. Except as modified by governing codes and by the Contract Documents, comply with the applicable provisions, requirements, and recommendations in Division 27 Section “General Communications Requirements”
- B. Refer to Division 27 Section “Common Work Results for Communications” for general pathway, firestopping, access panel, identification, and other requirements.
- C. Refer to Division 27 Section “Structured Cabling System” for Advanced System Warranty information and other requirements.
- D. Refer to Division 27 Section “Telecommunications Equipment Room Fittings” for telecommunications equipment racks, patch panels, wall-blocks, surge suppressors, and other equipment room requirements.
- E. Category 6 and fiber cabling and connectivity for Audio Video Systems (as required by the TA drawings) are specified in Division 27 Section “Telecommunications Requirements for Audio Video Systems”.

1.03 CODES, STANDARDS, AND GUIDELINES

- A. In addition to all applicable codes, standards, and guidelines listed in Division 27 Sections “General Communications Requirements” and “Structured Cabling System”, follow the most recent editions of the following:
 - 1. NFPA 70 (NEC) – “National Electrical Code” (NEC)
 - 2. IEEE NESC - “National Electrical Safety Code”

3. ANSI/BICSI 005 – “Electronic Safety and Security System Design and Implementation Best Practices”
4. ANSI/NECA/BICSI-607 – “Standard for Telecommunications Bonding and Grounding Planning and Installation methods for Commercial Buildings”
5. ANSI/TIA-568 – “Commercial Building Telecommunications Cabling Standard Set”
6. ANSI/TIA-569 – “Commercial Building Standard for Telecommunications Pathways and Spaces”
7. ANSI/TIA-607 – “Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises”
8. ANSI/TIA-606 – “Administration Standard for Commercial Telecommunications Infrastructure”
9. BICSI – “Telecommunications Distribution Methods Manual”
10. BICSI – “Information Technology Systems Installation Methods Manual”
11. IEEE 142 – “Recommended Practice for Grounding of Industrial and Commercial Power Systems” (Green Book)
12. IEEE 1100 – “Recommended Practice for Powering and Grounding Electronic Equipment” (Emerald Book)
1. TIA-526 – “Standard Test Procedures for Fiber Optic Systems”
 13. TIA-TSB-140 – “Additional Guidelines for Field-Testing Length, Loss and Polarity of Optical Fiber Cabling Systems”

1.04 DEFINITIONS

- A. Advanced System Warranty – refer to Division 27 Section “Structured Cabling System”.
- B. Communications Equipment Room - This CSI MasterFormat term shall apply to spaces specifically designed to maintain communications equipment. This definition shall encompass ANSI/TIA-569 terms for Entrance Room, Common Equipment Room (CER), and Common Telecommunications Room (CTR). This definition also shall encompass BICSI Telecommunications Distribution Methods Manual terms for Telecommunications Room (TR), Telecommunications Enclosure (TE), Equipment Room (ER), and Entrance Facility (EF).
- C. Direct Attach Method – as defined in ANSI/BICSI 005-2013, the horizontal cabling on the remote device end directly attaching (or connecting) to the device through a connectorized cable or hard-wired termination, eliminating the workstation outlet, jack and equipment cord.
- D. Horizontal Cabling
 1. Horizontal cable and its connecting hardware provide the means of transporting signals between the telecommunications outlet/connector and the horizontal cross-connect located in the communications equipment room. This cabling and its connecting hardware are called "permanent link," a term that is used in the testing protocols.

- a) Horizontal cabling shall contain no more than one transition point or consolidation point between the horizontal cross-connect and the telecommunications outlet/connector
 - b) Bridged taps and splices shall not be installed in the horizontal cabling
 - c) Splitters shall not be installed as part of the optical fiber cabling
2. A work area is approximately 100 sqft (9.3 sqm), and includes the components that extend from the telecommunications outlet/connectors to the station equipment.
 3. The maximum allowable horizontal cable length for Category copper cable is 295 feet (90 meter). This maximum allowable length does not include an allowance for the length of 16 feet (4.88 meter) to the workstation equipment. The maximum allowable length does not include an allowance for the length of 16 feet (4.88 meter) in the horizontal cross-connect.
 4. Horizontal cables longer than 295 feet shall be hybrid optical fiber and power conductor cable with a Power Over Ethernet Extender transmitter/receiver on each end.
- E. Structured Cabling / Telecommunications System – a fully-functional passive telecommunications system (infrastructure), that includes permanently installed copper Category and fiber optic cable terminated onto a patch panel or outlet.

1.05 QUALITY ASSURANCE

- A. As a minimum, the person(s) conducting the testing for all Telecommunications cabling shall be a current BICSI Certified Level II Commercial Installer or higher.
- B. All testing equipment used shall have the latest version of software and/or firmware installed prior to testing any cabling. Testing equipment shall also undergo all manufacturers' required and recommended routine maintenance.

1.06 SUBMITTALS

- A. Follow the requirements for submittals in Division 27 Section "General Communications Requirements"
- B. Pre-bid submittal
 1. For all products for which a substitute is to be considered as an approved equivalent or acceptable substitution provide submittals with sufficient detail for review by the Engineer. Submittals shall at a minimum provide detailed information substantiating all performance requirements as well as all necessary code compliance and NRTL listing information.
- C. Pre-construction submittal

1. Provide a typed list indicating part name, manufacturer, part number, and color (if applicable) for products specifically identified herein by the exact and complete part number (no wild-card characters)
2. Submit manufacturers' cut sheets or catalog cut sheets for:
 - a) Each of the cables specified. Cut sheets shall include the following information at a minimum:
 - 1) Manufacturers name and logo
 - 2) Cable outside diameter
 - 3) Number of conductors/strands in each cable and binder group
 - 4) Gauge or strand thickness
 - 5) Minimum transmission performance rating
 - 6) Cable jacket material and rating
 - 7) Maximum pulling tension
 - 8) Jacket/Sheath color
 - 9) Individual conductor or strand insulation colors
 - 10) Minimum bend radius
 - a) During installation and post installation.
 - b) As well as any additional information required by individual sections of this Division.
 - b) Faceplates and modules. Cut sheets shall include the following information at a minimum:
 - 1) Manufacturers name and logo
 - 2) Material type
 - 3) Performance rating
 - 4) Physical Dimensions
 - 5) Color
 - c) Product information of test equipment to be used for the testing of cabling.
 - d) Provide documentation indicating manufacturer required and recommended maintenance and calibration services and intervals at which these services shall be performed.
 - 1) Provide documentation indicating the dates at which all testing units have undergone these services. For services required on a daily or pre-test basis provide documentation on the procedures the contractor will undergo for performing such services.
3. Shop Drawings
 - a) Submit for review scaled layout drawings showing the routing of all cabling, and the locations where terminal blocks, patch panels, Telecommunications outlets, cable types, cable jacket listing information, firestop locations (with quantity and NRTL system

- number identified), furniture feed points, and fiber optic termination panels are to be installed.
 - b) Shall show the number of horizontal cables served by each room and the number of patch panels and termination blocks to be installed (including those to accommodate 25% growth).
 - c) Each individual outlet on the drawings shall have proposed outlet identification indicated.
 - d) Unless otherwise required by these specifications, it is permissible to show different cabling systems (voice, data, CATV, A/V) on the same shop drawing.
 - 4. Testing
 - a) Qualifications: Identity and qualifications of the personnel who will perform the testing as required above in the Quality Assurance paragraph.
 - b) Submit all physical characteristics needed for appropriate testing setup and verification. I.e. Nominal velocity of propagation (NVP) for each and every cable type. This parameter shall be identified and submitted for review. Such submittals for all parameters shall be from printed manufacturers' cut-sheets or other manufacturers' printed material.
 - c) Submit the proposed schedule for performing testing at least 2 weeks prior to the start of testing.
 - 5. Sample warranty information as indicated herein and elsewhere in this Division.
- D. Project completion submittal
 - 1. As-built Drawings
 - a) Submit scaled layout drawings showing the routing of all cabling, and the locations where terminal blocks, patch panels, Telecommunications outlets, cable types, cable jacket listing information, firestop locations (with quantity and NRTL system number identified), furniture feed points, and fiber optic termination panels have been installed.
 - b) Shall show the number of horizontal cables served by each room and the number of patch panels and termination blocks installed (including those to accommodate 25% growth).
 - c) Unless otherwise required by these specifications, it is permissible to show different cabling systems (voice, data, CATV, A/V) on the same As-built drawing.
 - 2. After approval by the Owner, submit the test results in computer readable copy in CD, DVD or mutually acceptable format by the Contractor and Owner.
 - 3. Advanced Structured Cabling System Warranty Certificate

1.07 WARRANTIES

- A. Provide manufacturer warranties as required in Division 27 Section “Structured Cabling System”.

PART 2 - PRODUCTS AND MATERIALS

2.01 HORIZONTAL (WORK AREA) COPPER CABLE

- A. Horizontal cables for dry environments
 - 1. Requirements
 - a) Unshielded Twisted Pair (UTP)
 - b) Minimum performance specifications: Cable shall meet requirements for Augmented Category 6 of ANSI/TIA-568.
 - c) Four pairs of 22-24 AWG solid copper conductors
 - d) Cable jacket color(s) shall be
 - 1) Blue for general data cabling
 - 2) Yellow for security cabling
 - 3) White for wireless access point cabling
 - e) Cable jacket marking: Shall be legible and shall contain the following information:
 - 1) Manufacturer’s name
 - 2) Copper Conductor Gauge
 - 3) Pair Count
 - 4) UL and CSA listing
 - 5) Manufacturer’s trade mark
 - 6) Category rating
 - 7) Sequential distance markings, in one foot increments
 - f) Individually insulated conductors under a common sheath
 - g) Plenum (CMP or MPP) rated.
 - 2. Manufacturer shall be:
 - a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)
- B. Horizontal cables for Wet Locations (as defined in Division 27 Section “Structured Cable System”)
 - 1. Requirements
 - a) Suitable to be in contact with standing water
 - b) Cable construction shall be consistent with manufacturer’s requirements to be covered under warranty specified in Division 27 Section “General Communications Requirements”.

- c) Minimum performance specifications: Cable shall meet requirements for Augmented Category 6 of ANSI/TIA-568.
 - d) Cable jacket marking: Shall be legible and shall contain the following information:
 - 1) Manufacturer's name
 - 2) Copper Conductor Gauge
 - 3) Pair Count
 - 4) UL and CSA listing
 - 5) Manufacturer's trade mark
 - 6) Category rating
 - 7) Sequential distance markings, in one foot increments
2. Product shall be:
- a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)

2.02 FACEPLATES FOR COPPER CONNECTIVITY

A. Single-gang faceplate:

1. Requirements

- a) High impact nylon with number of ports to allow all modular jacks to be installed as required, and as indicated on the drawings.
- b) Color shall match electrical, U.O.N. by owner
- c) Single gang, U.O.N

2. Product shall be

- a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)

B. Double-gang faceplate:

1. Requirements

- a) High impact nylon with number of ports to allow all jacks to be installed as required, and as indicated on the drawings.
- b) Color shall match electrical, U.O.N. by owner
- c) Double gang, U.O.N

2. Product shall be

- a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)

C. Weatherproof faceplate:

1. Requirements

- a) Water resistant faceplate (to IP56 rating, or equivalent) with number of ports to allow all jacks to be installed as required, and as indicated on the drawings.
 - b) With in-use cover
2. Product shall be:
- a) Panduit Mini-Com Water Resistant Faceplate with integral cover.
 - b) Hubbell RW57300 (Or Approved Equivalent) with decora-insert and jacks from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements).

D. Surface mount box

- 1. Requirements
 - a) With number of ports to allow all jacks to be installed as required, and as indicated on the drawings.
 - b) Mount into backbox, U.O.N
- 2. Product shall be
 - a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)

2.03 COPPER CONNECTIVITY

A. Modular jacks

- 1. Requirements
 - a) Outlets shall meet requirements for Augmented Category 6 of ANSI/TIA-568.
 - b) All 8-position modular jacks are to be wired according to the TIA T568B pin/pair assignments.
 - c) Outlet hardware shall be UL listed.
 - d) One port
 - e) Color shall match electrical, U.O.N. by owner
- 2. Product shall be
 - a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)

B. Field termination plugs

- 1. Requirements
 - a) Outlets shall meet requirements for Augmented Category 6 of ANSI/TIA-568.
 - b) All 8-position modular jacks are to be wired according to the TIA T568B pin/pair assignments.
 - c) UL Listed: UL 2043 (plenum)

2. Product shall be
 - a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)

C. Blank inserts

1. Requirements
 - a) Provide blank modules to fill any unused openings in faceplates
 - b) Color shall match other jack colors
2. Product shall be
 - a) Submit product data from Conditionally Approved manufacturer listed above (subject to Advanced System Warranty requirements)

2.04 POWER OVER ETHERNET EXTENDER

A. General:

1. Shall be utilized where noted on drawings and for any work area outlets that requires a Category 6 connection, where the cable distance exceeds 295 feet.
2. The Power over Ethernet (PoE) extender system shall provide the capability to upgrade a channel of a standard Ethernet switch to deliver PoE (IEEE 802.3af), PoE+ (IEEE 802.3at), or HPoE (non-standard) over a composite fiber/power cable.
3. The system shall utilize an external power injector at the source end.
4. The system shall provide power that is compliant with the requirements of a Class 2 Power Source per NFPA 70 or CSA C22.1 and be listed as such.
5. The system shall be comprised of a power injector and converter that generates and injects DC power and converts electrical signals to optical signals in the head end room, a receiver that converts the optical signals back to electrical signals and acts as a power supply for Power Over Ethernet at the work area outlets, and a composite cable for both fiber optic and copper power elements.

B. Media Converters - Power Source Devices

1. Shall be capable of being mounted on a horizontal or vertical surface or rack-mount bracket or chassis. Chassis modules shall take power from a common power supply.
2. The operating temperature range shall be 0°C to 40°C (32°F to 104°F).
3. The Power over Ethernet capabilities shall be:
 - a) Input voltage range 100 – 240 VAC.
 - b) Complies with the universal IEEE 802.3at PoE endpoint standard, supplying PoE to class 0, 1, 2 and 3 devices or PoE+ to class 0, 1, 2, 3 and 4 devices.
4. Product shall be

- a) Berk-Tek One Reach
 - b) Commscope Powered Fiber
- C. Media Converters – Work Area Outlet Devices
 - 1. Shall accept power from power source equipment at head end.
 - 2. Shall be available in 1 and 2 port modules.
 - 3. Remotes shall be placed in enclosures/boxes suitable for the environment such as NEMA Type 1 (indoors, typical) or NEMA Type 3R (outdoors, typical).
 - 4. The operating temperature shall be -40°C to 50°C (-40°F to 122°F).
 - 5. Product shall be
 - a) Berk-Tek One Reach
 - b) Commscope Powered Fiber
- D. Hybrid Optical Fiber/Copper Cable
 - 1. The cable shall be a composite, containing single-mode fibers and solid copper conductors of size 12 AWG.
 - 2. Outdoor rated.
 - 3. Product shall be
 - a) Berk-Tek One Reach
 - b) Commscope Powered Fiber

2.05 WIRELESS ACCESS POINT BOLLARD

- A. General:
 - 1. Cylindrical polyethylene plastic Wi-Fi bollard. Shall protect APs and antennas in outdoor public spaces. Designed for permanent or temporary low voltage installations.
 - 2. Shall protect equipment from tampering, spilling liquids and weather. Shall be NEMA 3R performance-rated for indoor/ outdoor environments.
 - 3. Shall anchor to pre-installed concrete pedestal or anchor with ground or asphalt screws.
 - 4. The operating temperature shall be -40°F (-40°C) to +140°F (+60°C)
- B. Bollard
 - 1. Confirm color and height with architect.
 - 2. Product shall be:
 - a) Oberon Model 3032-00-XX

PART 3 - EXECUTION

3.01 INSTALLATION, GENERAL

- A. Install in accordance with manufacturer's instructions.

3.02 CABLE INSTALLATION

A. General

1. Place all horizontal cabling in accordance with these specifications, on the Drawings, and as indicated on any cable schedules
2. Install each cable as an uninterrupted conductor section between the designated termination points, unless otherwise directed by the cable installation specifications.
 - a) There shall be no splices or mechanical couplers installed between the cable points of origin and termination except as shown on the Drawings and/or specified herein.
 - b) There shall be no Bridged taps (multiple appearances of the same cable pairs at several distribution points) installed.
 - 1) Horizontal cabling shall be terminated in a Telecommunications room that is on the same floor as the area (outlet) being served in accordance with ANSI/TIA-568.
 - 2) No horizontal Category cables shall exceed the allowed maximum distance of 295 feet (90 meters) by ANSI/TIA-568.
 - 3) Horizontal cables longer than 295 feet shall be hybrid optical fiber and power conductor cable with a Power Over Ethernet Extender transmitter/receiver on each end.
3. Unless otherwise noted, all cables shall be routed through the building cable tray/conduit/surface-mounted raceway system. Refer to the electrical drawings for the layout of the conduits. Refer to the Telecommunications drawings for layout of cable tray.
 - a) All horizontal cables shall be plenum (CMP, MPP, OFNP, or OFCP) rated. UON
 - b) Horizontal cables installed in “wet” locations as defined by the NEC or in these construction documents (such as conduits embedded or routed below a ground floor slab) shall be suitable for installation in such environments and follow the installation requirements for outside plant cables as specified herein.
4. Cables shall remain unattached to pathways or other cables and shall simply lay at rest on the supports provided by its pathway (including cable trays, wire basket, j-hooks, conduit, etc.). Wire ties, velcro straps, electrical tape or any other method shall not be used to attach cables to cable supports or to create cable bundles.
 - a) Except when supported by ladder racking within each Telecommunications room, UON.
5. At the same time horizontal cables are pulled into a conduit also install a pull cord to facilitate future cable pulls along those. Use polypropylene or

monofilament plastic line with not less than 200 lb (90.72 kg) tensile strength. Leave at least 12 inches (304.8 mm) of slack at each end of pull cord.

6. Do not install kinked, scored, deformed, or abraded cable. Remove and discard cable if damaged during installation and replace it with new cable
7. Comply with all referenced standards and guidelines.
8. Cables shall be masked, covered, or otherwise protected from being painted or coming in contact with any other substance that may degrade the performance or physical characteristics of the cable jacket or insulation over time.
9. Where distance allows all horizontal cables shall be provided with slack/service loops at each end of the cable, one at the work area outlet and one at the Telecommunications room/enclosure. Each slack/service loop shall be:
 - a) A minimum of 8 feet (2.44 meter) in length, UNO
 - b) Configured in a loosely formed figure eight configuration (i.e. not coiled)
10. Prior to using any cable pulling lubricants provide the Engineer with written documentation from the cable manufacturer supporting the cable manufacturers' acceptance of its use in compliance with all required warranties as part of these contract documents. The use of non-water based lubricants shall be provided when pulling PVC jacketed and all cables not suitable for contact with water.

B. Outside plant cable installation: for cables placed in "wet locations" or as required by these construction documents. (I.e. all cables which extend beyond the footprint/envelope of the building or pathways leading to floor-boxes embedded in a ground floor slab)

1. Unlisted cables shall transition to an indoor rated cable within 50 feet (15.24 meter) of the entrance point as required the NEC.
 - a) This 50 feet (15.24 meter) allowed by code is only to allow termination as close as practicable to the entrance point. Terminate all outdoor only (unlisted) cables at the closest point of entrance and transition to an indoor rated cable to extend to additional Telecommunications rooms (spaces)
2. No portion of outdoor only (unlisted) cables may be installed with the cable jacket exposed in any plenum or other air handling space nor shall they be allowed to transition between different levels of the building.
3. Where specifically allowed by these construction documents cable jackets rated for dual use by a NRTL, such as an indoor/outdoor rated cable may be used.
 - a) These cables may be installed in locations within the building in which the cable jacket is appropriately rated to meet all applicable building codes.

4. Rigid metallic conduit shall be used to route outdoor (unlisted) cabling to within 50 feet (15.24 meter) of the transition point to indoor rated cabling in accordance with the NEC.
5. All cables which extend beyond the envelope/footprint of the building shall be installed with entrance protectors in accordance with Division 27 Section “Communications Equipment Room Fittings”

C. Horizontal (work area) Cables:

1. From the appropriate Telecommunications room, provide each work area outlet, the types and quantities of horizontal cables as described in the applicable system specification sections. Cables will leave the Telecommunications room via cable tray, conduit/sleeve or floor duct. Each cable will be terminated except for pay phone and elevator machine room junction box locations.
2. Install all horizontal cables in accordance with Division 27 Section “Common Work Results for Communications” and as indicated on the drawings.

3.03 CABLE & WIRE INSTALLATION

A. General:

1. Place all station cabling in accordance with these specifications, and as indicated on the cable schedules and the Drawings.

B. Station Cables:

1. Install station cabling, outlets and jacks as detailed in the horizontal cable placement schedules and the Drawings. The typical configuration for outlets shall be two unshielded twisted pair (UTP) cables of 4-pairs each, unless otherwise noted on the drawings or the Horizontal Cable Placement Schedules.

C. Cables located in “wet” locations

1. Provide all required entrance protection in accordance with Division 27 “Communications Equipment Room Fittings”.
2. Follow the requirements for installing outside plant rated cable as specified in Division 27 Section “Communications Horizontal Cabling”
3. All cables routed to floor boxes in the slab shall route to a transition box within 50 feet (15.24 meter) of where the conduit emerges from the slab. Provide connecting hardware within an appropriately rated enclosure to allow a transition from outside plant cable to indoor rated cable. Indoor rated cable shall be rated as required by building code and as specified herein. Route indoor cables as indicated for horizontal cable distribution. Transition hardware shall meet or exceed the category performance of the highest rated cable being terminated.

- a) Cables from multiple different floor boxes may be routed to a single, appropriately sized, transition enclosure.

D. Elevator Phone Cables:

1. Install elevator phone cables to support communications to each individual elevator cab. These cables will be run from each elevator's respective elevator equipment room to the nearest Telecommunications room as shown on the Drawings. Leave 15 feet (4.47 m) of coiled slack in the elevator equipment room junction box for eventual termination by the elevator contractor.

3.04 CONNECTOR INSTALLATION

A. Furnish and install all cable connectors as shown on the Drawings.

B. Provide number of connectors as required by the Drawings and as required by these documents, where the number of connectors required does not fill the entire faceplate provide blank inserts so that no opening is left.

C. The provision and termination of connectors from each cable shall be done as follows:

1. Where connector types are identified on the applicable drawings or in the specifications, furnish and install the specified connectors on the specified cables. Installation of the connectors shall be in accordance with the manufacturer's printed instructions.
2. All installed connectors, regardless of type, method of procurement or permanency, shall be adequately protected during and after installation.

D. Copper Connector Installation

1. Terminate all four pairs of each cable on one outlet jack.
2. Furnish and install all cable connectors as shown on the Drawings or as indicated herein, unless otherwise noted.
3. The provision and termination of connectors for each cable shall be done as follows:
 - a) Where connector types are identified on the applicable drawings or in the specifications, Furnish and install the specified connectors on the specified cables. Installation of the connectors shall be in accordance with the manufacturer's printed instructions.
 - b) All installed connectors, regardless of type, method of procurement or permanency, shall be adequately protected during and after installation.

3.05 FLOORBOX LOCATIONS

- A. Refer to Division 27 "Common Work Results for Communications" for size, type, and specifications.

1. Provide appropriate mounting brackets (as required), faceplates, modular jacks, inserts, mounting frames and cabling required to fully populate and provide a fully functional system.
- B. For slab-on-grade floorbox locations, coordinate with the Common Work contractor to extend underground or in-slab conduit all of the way to the serving Telecommunications Room. If that is not practical, coordinate with Common Work contractor on stub-up location and overhead enclosure size/location to transition OSP (wet-rated) cable to plenum-rated cable.
 1. Note underground conduit routing and overhead transition point locations on pre-construction shop drawings and Record Drawings.

3.06 FACEPLATE INSTALLATION

- A. Furnish and install all faceplates in locations as shown on the Drawings.

3.07 CABLE IDENTIFICATION

- A. Label all horizontal cabling with machine-printed labels according to the labeling scheme identified on the drawings. Where the drawings are silent, submit RFI through appropriate channels requesting labeling scheme.
 1. Shop drawings shall include floor plan that indicates proposed cable/outlet identification for each outlet.
- B. Cables shall be labeled within 6” at each end.
- C. All cable labels shall be thermal-transfer type and utilize self-adhesive labels. The following are approved manufacturers:
 1. Brady, IDXPRT
 2. Hellermann Tyton, Spirit 2100
 3. Panduit LS9
 4. Or equivalent

3.08 CABLE TERMINATIONS

- A. Terminate all horizontal cables in accordance with Division 27 Section “Communications Equipment Room Fittings”. No cables shall contain unterminated elements UON.

3.09 CABLE TESTING

- A. Refer to Division 27 Section “Structured Cabling System” for testing requirements.

3.010 ACCEPTANCE

- A. The Owner and Design Consultant reserves the right to observe the conduct of any or all portions of the testing process.

- B. All cables that fail testing are to be corrected prior to substantial completion and acceptance by owner. Replace entire cable if bad pair or conductor is found.

END OF SECTION

General

L000	Drawing list, symbols + Abbreviations
L000A	Drawing List Continued
L000B	Drawing List Continued
L001	Symbols, Abbreviations, Legends

Reference Plan

L010	Reference Plan
L011	LSD Site Plan

Site Preparation

LSP-0	Site Preparation - Key Plan, Legend and Notes
LSP-1	Site Preparation Plan 1/3
LSP-2	Site Preparation Plan 2/3
LSP-3	Site Preparation Plan 3/3

Materials

L100	Materials - Key Plan, Legend and Notes
L101	Materials Plan - Ground Floor 1/3
L102	Materials Plan - Ground Floor 2/3
L103	Materials Plan - Ground Floor 3/3
L104	Materials Plan - Roof 1/2
L105	Materials Plan - Roof 2/2
L106	Materials Plan - Roof Level 3

Layout - Hardscape

L200A	Layout - Hardscape - Key Plan, Legend and Notes
L200B	Layout - Hardscape - Data Chart
L201	Layout - Hardscape - Groundfloor 1/3
L202	Layout - Hardscape - Groundfloor 2/3
L203	Layout - Hardscape - Groundfloor 3/3
L204	Layout - Hardscape - Roof 1/2
L205	Layout - Hardscape - Roof 2/2

Layout - Furnishings

L210	Layout - Furnishings - Key Plan, Legend and Notes
L211	Layout - Furnishings - Ground Floor 1/3
L212	Layout - Furnishings - Ground Floor 2/3
L213	Layout - Furnishings - Ground Floor 3/3
L214	Layout - Furnishings - Roof 1/2
L215	Layout - Furnishings - Roof 2/2

Layout - Lighting

L220A	Layout - Lighting - Key Plan, Legend and Notes
L221	Layout - Lighting - Ground Floor 1/3
L222	Layout - Lighting - Ground Floor 2/3
L223	Layout - Lighting - Ground Floor 3/3
L224	Layout - Lighting - Roof 1/2
L225	Layout - Lighting - Roof 2/2

Layout - Wayfinding

L231	Layout - Wayfinding - Ground Floor 1/3
L232	Layout - Wayfinding - Ground Floor 2/3
L233	Layout - Wayfinding - Ground Floor 3/3
L234	Layout - Wayfinding - Roof 1/2
L235	Layout - Wayfinding - Roof 2/2

Grading

L300	Grading Plan - Key Plan, Legend and Notes
L301	Grading Plan - Ground Floor 1/3
L302	Grading Plan - Ground Floor 2/3
L303	Grading Plan - Ground Floor 3/3
L304	Grading Plan - Roof 1/2
L305	Grading Plan - Roof 2/2
L306	Grading Plan - Roof - Level 3

Planting Soils

L400	Planting Soils - Key Plan, Legend and Notes
L401	Planting Soils - Ground Floor 1/3
L402	Planting Soils - Ground Floor 2/3
L403	Planting Soils - Ground Floor 3/3
L404	Planting Soils - Roof 1/2
L405	Planting Soils - Roof 2/2

Planting

L500A	Planting - Key Plan, Legend and Notes
L500B	Planting Schedule 1/4
L500C	Planting Schedule 2/4
L500D	Planting Schedule 3/4
L500E	Planting Schedule 4/4
L501	Planting Plan - Ground Floor 1/3
L502	Planting Plan - Ground Floor 2/3
L503	Planting Plan - Ground Floor 3/3
L504	Planting Plan - Roof 1/2
L505	Planting Plan - Roof 2/2
L506	Tree Planting Plan - Ground Floor 1/3
L507	Tree Planting Plan - Ground Floor 2/3
L508	Tree Planting Plan - Ground Floor 3/3
L509	Tree Planting Plan - Roof 1/2
L510	Tree Planting Plan - Roof 2/2
L511	Shrub Planting Plan - Ground Floor 1/3
L512	Shrub Planting Plan - Ground Floor 2/3
L513	Shrub Planting Plan - Ground Floor 3/3
L514	Shrub Planting Plan - Roof 1/2
L515	Shrub Planting Plan - Roof 2/2

4 Drawing List (Continued)
Scale: N/A

Issuance
ASL 02B
10.21.2024
12.12.2024

Sections

L600	1 - Parking + Swale
	2 - Pond + Wetland Terrace
L610	1 - Tail + Grotto
	2 - Steep Roof Cross Section
L611	1 - L4 Terrace Section

Basin & Runnel Enlargements - Plans

L700A	Enlargements Key Plan - Woodland Amphitheater and Welcome Plaza
L700B	Enlargements Key Plan - Stone Paving and Benches
L701	Woodland Amphitheater Enlargement 1 - Materials
L702	Woodland Amphitheater Enlargement 2 - Materials
L703	Welcome Plaza Enlargement - Materials
L704	Amphitheater Enlargement 1 - Layout
L705	Amphitheater Enlargement 2 - Layout
L706A	Welcome Plaza Enlargement 1 - Layout - Hardscape
L706B	Welcome Plaza Enlargement 1 - Layout - Lighting
L707	Amphitheater Enlargement 1 - Grading
L708	Amphitheater Enlargement 2 - Grading
L709	Welcome Plaza Enlargement 1 - Grading
L710	Woodland Amphitheater Section
L711	Amphitheater Seat Wall Sections and Schedule
L712	Woodland Amphitheater Stone Stair Schedule
L720	Basin 1 and Runnel Plans
L720A	Cascade Falls Details
L721	Basin 2 Plans
L722	Basin 3 Plans
L723	Basin Sections
L724	Basin Sections
L725	Basin Sections
L730	Runnel - 3d Views
L731	Runnel and Basin Section Elevation
L732	Runnel Stone Schedule
L733	Runnel Stone Schedule
L734	Runnel Stone Schedule
L735	Runnel Stone Schedule
L750	Roof Tail Flake Stone Enlargement
L751	Cafe Plaza Stone Enlargement
L752	Prospect Bluff Stone Enlargement
L753	Healing Garden Stone Enlargement
L754	Winter Terrace Stone Enlargement
L755	Stone Schedules
L761	Teaching Garden Enlargement - Layout
L762	Teaching Garden Enlargement - Grading
L790	Water Feature - Details
L791	Water Feature - Details

Details

L901	Details - Paving
L902	Details - Paving
L903	Details - Paving, Walls, Curbs
L904	Details - Furnishing
L905	Details - Furnishing
L906	Details - Stairs, Drains, Handrails
L907	Details - Fencing
L908	Details - Lighting
L909	Details - Boardwalk
L910	Details - Boardwalk
L911	Details - Planting
L912	Details - Soils
L913	Details - Roof Drain Access
L914	Details - Teaching Garden
L915	Details - Teaching Garden
L916	Details

Irrigation Drawings

I101	Ground Floor Irrigation Plan 1
I102	Ground Floor Irrigation Plan 2
I103	Ground Floor Irrigation Plan 3
I104	Irrigation Roof Plan
I105	Irrigation Details
I106	Irrigation Details

Water Feature Drawings

WF101	Water Feature Site Plan
WF102	Water Feature Piping Plan
WF201	Runnel Hydraulic Schematic
WF202	Basins 2 & 3 Hydraulic Schematic
WF301	Water Feature Equipment
WF302	Water Feature Equipment
WF401	Water Feature Section and Details
WF501	Water Feature Fabrication and General Details
WF601	Water Feature Electrical Plan
WF602	Water Feature Electrical Details

Issuance
ASL 02B
10.21.2024

801 South Spring Street
Little Rock, AR 72201
501.378.0878 office
509 W. Spring St | Suite 150
Fayetteville, AR 72701
479.644.0033 office
polkstanleywilcox.com

CIVIL
McClendon Consulting Engineers, Inc.
1580 E STEARNS ST
FAYETTEVILLE, AR 72703
P: 479.443.2377

LANDSCAPE
OSD
115 ST. JOHNS PLACE
BROOKLYN, NY 11217
P: 917.553.5586

STRUCTURAL
Martin/Martin Consulting Engineers
8005 SOUTH WALTON BLVD, STE 212
BENTONVILLE, AR 72712
P: 479.407.0545

MERF - LOW VOLTAGE
Henderson Engineers
6346 LENEKA DRIVE, STE 300
LENEKA, MS 38614
P: 662.660.6167

SUSTAINABILITY
SOM
224 SOUTH MICHIGAN AVENUE
CHICAGO, IL 60604
P: 312.360.4121


SIGNAGE - WAYFINDING
TWO TWELVE
238 W. 27th ST., SUITE 602
NEW YORK, NY 10001
P: 212.254.6870

FOOD SERVICE
JMG HOSPITALITY
6926 SW FINLEY DR., SUITE 8210
THE WOODLANDS, TX 77380
P: 609.841.2222

WATER FEATURES
OTL
2150 S. TOWNE CENTER, SUITE 100
ANAHIM, CA 92906
P: 714.637.4747

IRRIGATION
WC3 DESIGN
11A ROBINSON MANOR BLVD
MOORESBURG, PA 14108
P: 844.231.7042

PSW Job Number:
933A



AWSOM
Bentonville, AR

Issue Date:
10.21.2024

REVISIONS			
NUMBER	DATE	DESCRIPTION	BY
1	10.13.2024	ADD SHEET	PR 089
2	10.12.2024	PR 089	

Contents:
Drawing List, Symbols and Abbreviations

Lighting Layout Legend

- Light on 16' Tall Pole
- Light and Strobe on 16' Tall Pole
- Light, Exit Sign, and Strobe on 16' Tall Pole
- Lit Bollard
- Wireless Access Point Inside Bollard Shroud
- Strobe on Post
- Exit Sign on Post
- Exit Sign and Strobe on Post
- Charging Pedestal
- Holiday Controlled, Receptacle Pedestals

General Legend

- Property Line
- Limit of Work
- Right of Way
- Building Entry
- Landscape Area Drain Inlet, See Civil Drawings
- Trench Drain
- Slot Drain
- Roof Drain, See Architecture Drawings

PSW Job Number:
933A




AWSOM
Bentonville, AR

Issue Date:
03.13.2023

REVISIONS

NUMBER	DATE	DESCRIPTION
1	03.13.2023	PROVISION
2	06.09.2023	ADDITIONAL P
3	08.09.2024	PROVIDE
4	11.21.2024	PROVIDE
5	12.12.2024	PROVIDE

Contents:
Layout - Lighting - Roof 1/2



1 Layout Plan - Lighting - Roof 1
Scale: 1/8"=1'-0"




REVISIONS		
NUMBER	DATE	DESCRIPTION
1	03.13.2023	ISSUED FOR PERMIT
2	06.06.2023	ADDITIONAL 2
3	06.06.2024	PERMITS
4	09.26.2024	ASB DES
5	12.12.2024	PERMITS

Lighting Layout Legend


- Light on 16' Tall Pole
- ⊗ Light and Strobe on 16' Tall Pole
- Light, Exit Sign, and Strobe on 16' Tall Pole
- ⊕ Lit Bollard
- ⊖ Wireless Access Point Inside Bollard Shroud
- ⊞ Strobe on Post
- ⊟ Exit Sign on Post
- ⊠ Exit Sign and Strobe on Post
- ⊡ Charging Pedestal
- ⊢ Holiday Controlled Receptacle Pedestals

General Legend

- Property Line
- L.O.W. Limit of Work
- R.O.W. Right of Way
- ▲ Building Entry
- ⊕ Landscape Area Drain Inlet, See Civil Drawings
- TD 9 1.005 Trench Drain
- SD 2 1.006 Slot Drain
- ⊞ Roof Drain, See Architecture Drawings



MATCHLINE, SEE L224



- ELECTRICAL PLAN NOTES:**
- L14 LIGHT FIXTURE SHALL BE UTILIZED FOR EMERGENCY EGRESS AND POWERED THROUGH REMOTE BATTERY INVERTER. FIXTURE SHALL BE NORMALLY CONTROLLED WITH CONTROL ZONE INDICATED.
 - L20 PROVIDE UNCONTROLLED HOT TO ALL EXTERIOR EMERGENCY LIGHTING FIXTURES.
 - L34 FIXTURE PROVIDE WITH INTEGRAL EMERGENCY BATTERY AND SHALL BE PROVIDED WITH UNCONTROLLED HOT FOR CIRCUIT SENSING.

CIVIL
McClain Consulting Engineers, Inc.
 1380 E STEARNS ST
 FAYETTEVILLE, AR 72703
 P: 479.443.2377

LANDSCAPE
OSD
 115 ST. JOHNS PLACE
 BROOKLYN, NY 11217
 P: 917.553.5886

STRUCTURAL
Martin Consulting Engineers
 506 SOUTH WALTON BLVD., STE 107
 BENTONVILLE, AR 72712
 P: 479.493.9345

MEPF - LOW VOLTAGE
Henderson Engineers
 834 LENEZA DRIVE, STE 300
 LENOXA, MS 39214
 P: 913.660.8197


SUSTAINABILITY
SOM
 224 SOUTH MICHIGAN AVENUE
 CHICAGO, IL 60604
 P: 312.362.4121

SIGNAGE - WAYFINDING
TWO TWELVE
 236 W. 23RD ST., SUITE 802
 NEW YORK, NY 10001
 P: 212.254.9870


FOOD SERVICE
JMC HOSPITALITY
 856 SIX PINES DR., SUITE 8210
 THE WOODLANDS, TX 77380
 P: 684.41.2222

WATER FEATURES
OTL
 2150 S. TOWNE CENTER, SUITE 100
 ANAHEIM, CA 92806
 P: 714.637.4747

IRRIGATION
WC3 DESIGN
 11A ROBINSON MANOR BLVD.
 ROCKESBURG, PA 16155
 P: 844.231.7042




2 ELECTRICAL SITE - ROOF COURTYARD
 1/8" = 1'-0"



1 ELECTRICAL SITE PLAN - ROOF
 1/16" = 1'-0"

PSW Job Number:
993A
 Henderson Job Number:
2150002607



AWSOM
 Bentonville, AR

Issue Date:
02.24.2023

REVISIONS

NUMBER	DATE	DESCRIPTION
1	03/13/23	ADDENDUM 1
2	06/23/23	ADDENDUM 2
3	12/18/23	REV 004
4	06/24/24	REV 051
5	06/24/24	REV 048
6	08/24/24	REV 073
7	08/24/24	ADD 055
8	10/12/24	REV 089
9	11/28/24	REV 0782

Contents:
ELECTRICAL SITE PLAN - ROOF

FIRE ALARM SCOPE OF WORK NOTES:

1. FIRE ALARM SCOPE OF WORK IS TO PROVIDE A COMPLETE, IN-BUILDING MASS NOTIFICATION FIRE ALARM SYSTEM.
2. ALL CEILING MOUNTED FIRE ALARM APPLIANCES AND DEVICES SHALL BE INSTALLED IN A SYMMETRICAL PATTERN AND ALIGNED WITH LIGHTS AND OTHER CEILING EQUIPMENT WHERE CODE PERMITS.
3. WHERE CEILING MOUNTED FIRE ALARM EQUIPMENT ARE SHOWN IN WOOD CEILINGS, CONTRACTOR SHALL COORDINATE FINAL LOCATIONS AND APPLIANCE COLOR WITH ARCHITECT.
4. WHERE CEILING MOUNTED SPEAKERS ARE SHOWN IN AREAS OPEN TO STRUCTURE, SPEAKERS SHALL BE LOCATED 18" ABOVE THE NEAREST CEILING ELEVATION.

FIRE SPRINKLER SCOPE OF WORK NOTES:


1. FIRE SPRINKLER SCOPE OF WORK IS TO PROVIDE A COMPLETE, AUTOMATIC SPRINKLER SYSTEM THROUGHOUT THE BUILDING.
2. SPRINKLER PROTECTION WITH FREEZE PROTECTION SHALL BE PROVIDED FOR ALL EXTERIOR BUILDING PROJECTIONS AND EXTERIOR OCCUPIED BALCONIES OR DECKS.
3. SPRINKLER SYSTEM CONTAINS A COMBINATION OF WET, DRY, AND PREACTION SPRINKLER SYSTEMS. ANTIFREEZE SOLUTION PROVIDED IN SELECT WET SYSTEMS.
4. ALL DRY-PIPE AND PREACTION SPRINKLER SYSTEMS SHALL BE FILLED WITH NITROGEN.
5. HEAT TRACE IS TO BE PROVIDED ON ANY WET DISTRIBUTION MAINS ROUTED THROUGH UNHEATED SPACES.

FIRE SPRINKLER SCOPE OF WORK NOTES:

6. FIRE SPRINKLER SYSTEM DESIGN AND INSTALLATION SHALL BE IN ACCORDANCE WITH NFPA 13 2019 EDITION WITH THE EXCEPTION OF THE GARAGE SPRINKLER SYSTEM DESIGN CRITERIA, REFER TO FP100.2 FOR ADDITIONAL INFORMATION.
7. WHERE ANTIFREEZE SYSTEMS ARE PROVIDED, SYSTEM SHALL BE CALCULATED AS A DRY-PIPE SPRINKLER SYSTEM WHERE NEEDED TO ACHIEVE LARGER SYSTEM SIZES PER MANUFACTURER'S DATA.
8. FIRE SPRINKLER PIPE SHALL NOT BE ROUTED THROUGH ELECTRICAL ROOMS, IT DATA ROOMS, ANY ROOMS OR SIMILAR PIPING SHALL BE LIMITED TO BRANCHLINES SERVING SPRINKLERS WITHIN THOSE ROOMS.

FIRE PROTECTION PLAN NOTES:

- F33 PROVIDE HYPERSPIKE TCPA-10 MODEL 00215A-801-01-L FIRE ALARM LOUDSPEAKER PROVIDE 70V 12W OUTPUT.
- F38 LOUDSPEAKERS SHALL BE POLE MOUNTED BEHIND THE PARAPET. SPEAKERS SHALL BE INSTALLED SUCH THAT THE ENTIRE SPEAKER IS ABOVE THE PARAPET AND CAN BE ANGLED TOWARD THE OPPOSITE SIDE OF THE OCCUPIED GREEN ROOF BELOW.
- F98 FREESTANDING ROOF LEVEL STANDPIPE WITH TWO 2-1/2" HOSE VALVES, CAP AND CHAIN. PROVIDE SHUT-OFF VALVE WITH TAMPER SWITCH AND BALL DRIP WITHIN STAIRWAY.



① FIRE PROTECTION PLAN - ROOF - AREA A
1/8" = 1'-0"
SCALE: 1/8"=1'-0"

PSW Job Number:
993A
Henderson Job Number:
2150002607




AWSOM
Bentonville, AR

Issue Date:
02.24.2023


REVISIONS		
NUMBER	DATE	DESCRIPTION
1	03.10.23	Addendum
2	12.18.23	PR-024
3	06.15.24	PR-083
4	12.12.24	PR-089

Consents:
FIRE PROTECTION - ROOF PLAN - AREA A

TECHNOLOGY PLAN NOTES:
T106 PROVIDE (1) 2" CONDUIT FOR DATA FROM DATA ROOM #3504 TO WIRELESS ACCESS POINT IN BOLLARD. SEE DIVISION 27 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
T108 PROVIDE (1) 2" CONDUIT FOR DATA FROM WIRELESS ACCESS POINT IN BOLLARD TO WIRELESS ACCESS POINT IN BOLLARD. SEE DIVISION 27 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
T109 PROVIDE FILL BOX. SEE DIVISION 27 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
T120 APPROXIMATE LOCATION OF DATA ROOM #3504 ON LEVEL 3.
T122 PROVIDE (1) CAT6A FROM DATA ROOM #3504 TO WIRELESS ACCESS POINT IN BOLLARD.



PSW Job Number:
993A
Henderson Job Number:
2150002607




AWSOM
Bentonville, AR


Issue Date:
12.12.2024

NUMBER	DATE	DESCRIPTION


Consents:
TELECOM SITE PLAN - ROOF

① TELECOM SITE PLAN - ROOF
1/16" = 1'-0"







1 SINGLE GANG COMM OUTLET
NTS




2 FIBER PANEL
NTS




3 WALL PHONE OUTLET
NTS




4 COMM OUTLET FOR ELEVATOR - LAND LINE
NTS




5 POKE THROUGH
NTS




6 FLOOR BOX
NTS




7 LABELING OF HORIZONTAL CABLE
NTS





8 TYPICAL PATCH PANEL LABELING DETAIL
NTS




9 CABLE ROUTING FOR POKE THROUGH AND FLOOR BOXES
NTS




10 DAS INSTALLATION
NTS



11 CEILING COMM OUTLET
NTS




12 COMMUNICATIONS OUTLET MOUNTING
NTS



13 EXTERIOR WIRELESS ACCESS POINT IN BOLLARD
NTS


SECURITY PLAN NOTES:

TY4 ALL CAMERAS SHALL HAVE CATEGORY CABLING
TERMINATED BACK TO 4TH FLOOR IDF. DATA 4104, WITH POE
INJECTORS SUPPLIED AS REQUIRED TO MEET
MULTI-SCRIPT VOLTAGE REQUIREMENTS. EACH POE
INJECTOR SHALL REQUIRE A 100V CONNECTION
CONTRACTOR SHALL UTILIZE DUPLEXES IN DATA RACKS
FOR POWER REQUIREMENTS
REFER TO TN SERIES PLANS FOR SERVING ZONE INFORMATION



PSW Job Number:
993A

Henderson Job Number:
2150002607





AWSOM
Bentonville, AR

Issue Date:
12.12.2024


REVISIONS		
NUMBER	DATE	DESCRIPTION

Contents:
**SECURITY -
LEVEL 5 PLAN -
ROOF AREA A**







7 EXTERIOR ROOF MOUNTED CAMERA - PARAPET
12" = 1'-0"




4 EXTERIOR POLE MOUNTED CAMERA NTS
12" = 1'-0"




3 TYPICAL CAMERA INSTALLATION DETAIL - INTERIOR WALL MOUNT
12" = 1'-0"




1 TYPICAL ACCESS CONTROL PATHWAY ROUTING
12" = 1'-0"



2 TYPICAL CAMERA INSTALLATION DETAIL - INTERIOR CEILING MOUNT RECESSED
12" = 1'-0"



6 AXIS FA SERIES CAMERA MAIN UNIT RISER
12" = 1'-0"



5 EXTERIOR POLE MOUNTED CAMERA
12" = 1'-0"

REVISIONS		
NUMBER	DATE	DESCRIPTION
1	03.10.23	ADDENDUM 1
2	06.09.23	ADDENDUM 2
3	12.13.24	PROJ.08