

STOCKPILE PROTECTION INSTALLATION NOTES

1. SEE PLAN FOR:
-LOCATION OF STOCKPILES
-TYPE OF STOCKPILE PROTECTION
2. INSTALL PERIMETER CONTROLS IN ACCORDANCE WITH THEIR RESPECTIVE DESIGN DETAILS. SILT SOCK IS SHOWN IN THE STOCKPILE PROTECTION DETAILS; HOWEVER, OTHER TYPES OF PERIMETER CONTROLS INCLUDING SEDIMENTS CONTROL LOGS OR ROCK SOCKS MAY BE SUITABLE IN SOME CIRCUMSTANCES. CONSIDERATIONS FOR DETERMINING THE APPROPRIATE TYPE OF PERIMETER CONTROL FOR A STOCKPILE INCLUDE WHETHER THE STOCKPILE IS LOCATED ON A PEROUS OR IMPEROUS SURFACE, THE RELATIVE HEIGHTS OF THE PERIMETER CONTROL AND STOCKPILE, THE ABILITY OF THE PERIMETER CONTROL TO CONTAIN THE STOCKPILE WITHOUT FAILING IN THE EVENT THAT MATERIAL FROM THE STOCKPILE SHIFTS OR SLUMPS AGAINST THE PERIMETER, AND OTHER FACTORS.
3. STABILIZE THE STOCKPILE SURFACE WITH SURFACE ROUGHENING, TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS, OR SOIL BINDERS. SOILS STOCKPILED FOR AN EXTENDED PERIOD (TYPICALLY FOR MORE THAN 60 DAYS) SHOULD BE SEEDED AND MULCHED WITH A TEMPORARY GRASS COVER ONCE THE STOCKPILE IS PLACED (TYPICALLY WITHIN 14 DAYS). USE OF MULCH ONLY OR A SOIL BINDER IS ACCEPTABLE IF THE STOCKPILE WILL BE IN PLACE FOR A MORE LIMITED TIME PERIOD (TYPICALLY 30-60 DAYS).
4. FOR TEMPORARY STOCKPILES ON THE INTERIOR PORTION OF A CONSTRUCTION SITE, WHERE OTHER DOWNGRADIENT CONTROLS, INCLUDING PERIMETER CONTROL, ARE IN PLACE, STOCKPILE PERIMETER CONTROLS MAY NOT BE REQUIRED.

STOCKPILE PROTECTION MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
4. IF PERIMETER PROTECTION MUST BE MOVED TO ACCESS SOIL STOCKPILE, REPLACE PERIMETER CONTROL BY THE END OF THE WORKDAY.
5. STOCKPILE PERIMETER CONTROLS CAN BE REMOVED ONCE ALL THE MATERIAL FROM THE STOCKPILE HAS BEEN USED.


NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SEQUENCE OF CONSTRUCTION

1. INSTALL STABILIZED CONSTRUCTION ENTRANCES.
2. CONSTRUCT COMPOST FILTER SOCK/SILT FENCES ON THE SITE.
3. INSTALL INLET PROTECTION DEVICES ON EXISTING INLETS.
4. PREPARE TEMPORARY PARKING AND STORAGE AREA.
5. HALT UNTIL SITE BMP'S HAVE BEEN INSPECTED AND APPROVED. ONCE APPROVED, CLEAR AND GRUB THE SITE.
6. BEGIN GRADING THE SITE.
7. START CONSTRUCTION OF BUILDING PAD AND OTHER STRUCTURES.
8. TEMPORARILY SEED DENUDEED AREAS.
9. INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS AND CURB & GUTTERS.
10. INSTALL INLET PROTECTION DEVICES.
11. PREPARE SITE FOR PAVING.
12. PAVE SITE.
13. COMPLETE GRADING AND INSTALL PERMANENT SEEDING AND PLANTING.
14. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (ONLY IF SITE IS STABILIZED)

NOTES:

1. INSTALL AS SOON AS POSSIBLE BEFORE START OF GRADING
2. PLACE FILTER FABRIC UNDER STONE
3. USE 3"-6" CLEAN CRUSHED LIMESTONE
4. REPLACE AS NEEDED TO MAINTAIN 6" DEPTH






GRAVEL CONSTRUCTION ENTRANCE / EXIT
NOT TO SCALE

ScourStop®
Installation Recommendations



1. ScourStop mats must be installed over a soil cover: sod, seeded turf reinforcement mat (TRM), geotextile, or a combination thereof.
2. For steep slopes (>10%) or higher velocities (>10 ft/sec), sod is the recommended soil cover.
3. Follow manufacturer's ScourStop Installation Guidelines to ensure proper installation.
4. Install ScourStop mats at maximum 1'-2" below flowline of culvert or culvert apron. (No waterfall impacts onto ScourStop mats.)
5. Performance of protected area assumes stable downstream conditions.




ANCHOR PATTERN
Abut transition mats to end of culvert or culvert apron.
Adjacent mats abut together laterally and longitudinally.
Minimum 8 anchors per mat.
Extra anchors as needed for loose or wet soils.
Extra anchors as needed for uneven soil surface.




A LEADER in the GEOSYNTHETIC and EROSION CONTROL industries
Learn more about our products at: HanesGeo.com | 888.239.4539


©2014 Leggett & Platt, Incorporated | 16959_1114



STOCKPILE PROTECTION PLAN



SECTION A



TREE PROTECTION DETAIL
NOT TO SCALE

TREE PRESERVATION NOTES

1. GRADING AROUND TREES TO BE LIMITED TO OUTSIDE THE DRIPLINE UNLESS OTHERWISE NOTED ON THESE PLANS.
2. THERE SHALL BE NO GRADING OR FILLING WITHIN THE PROTECTED CRITICAL ROOT ZONES OF PROTECTED TREES UNLESS OTHERWISE NOTED ON THESE PLANS.
3. NO VEHICLES OR EQUIPMENT SHALL BE DRIVEN OR PARKED UNDER THE DRIPLINE OF PROTECTED TREES. NO MATERIALS SHALL BE STORED UNDER THE DRIPLINE OF PROTECTED TREES.
4. TREE FENCE, COMPOST FILTER SOCK AND SILT FENCE FOR ALL PROTECTED TREES MUST BE PROPERLY MAINTAINED THROUGHOUT CONSTRUCTION.
5. ALL REQUIRED TREE, SILT FENCING AND COMPOST FILTER SOCK SHALL REMAIN IN PLACE UNTIL ALL GRADING AND LANDSCAPING ACTIVITIES HAVE CEASED AND SHALL ONLY BE REMOVED UPON THE REVIEW AND APPROVAL BY THE LANDSCAPE ARCHITECT.
6. ATTACHMENTS (WIRES, FENCES, ETC.) OTHER THAN THOSE APPROVED FOR GUYING, BRACING OR WRAPPING MUST NOT BE ATTACHED TO PROTECTED TREES.



3537 N. Steele Boulevard
Suite 310
Fayetteville, AR 72703
olsson.com
TEL 479.443.3404
FAX 479.443.4340
Olsson - Engineering
Arkansas COA #1010

A NEW BUILDING FOR THE

ROGERS FACILITIES DEPARTMENT


2295 N. ARKANSAS ST, ROGERS, ARKANSAS, 72756

© 2025 DEMX ARCHITECTURE

EROSION CONTROL
DETAILS

65.2

BID SET
05/04/2026 025-04961



DEMX
ARCHITECTURE
104 N EAST AVENUE
FAYETTEVILLE, ARKANSAS 72701 | 479.965.4571