



- NOTES:
- 1) METERS WILL BE INCLUDED WITH THE INSTALLATION TO ENSURE PROPER FIT.
 - 2) ALL BOLTS TO BE STAINLESS STEEL.
 - 3) SLOPE FLOOR TO DRAIN.
 - 4) IF POSSIBLE, PROVIDE 4" PVC DRAIN TO DAYLIGHT OR STORM SEWER. PROVIDE PVC CHECK IN DRAIN PIPE. THE AGGREGATE SUMP IS NOT REQUIRED IN THIS CASE.
 - 5) CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI.
 - 6) CONTRACTOR SHALL VERIFY ALL PART DIMENSIONS
 - 7) ALL MATERIAL AND LABOR FOR 4" METER VAULT (INCLUDING METER) SHALL BE PROVIDED BY THE CONTRACTOR.

WD-2
9
REV. 08/2023

WD-2
10

REVISION DATE	SHEET NO.
9/20/2022	WD-2