

**CDI BID PROPOSAL FORM**  
**AMP NORTH ADDITION**  
**5079 W Northgate Rd**  
**Rogers, AR 72758**

**BF-5.0 STRUCTURAL STEEL**

**Submitted by:** \_\_\_\_\_  
Name / Company / Date

The following Documents constitute the basis for the work:

- **Plans** as prepared by Drawing Dept Architecture & Design, and their consultants dated June 19, 2026.
- **Geotechnical Report** as prepared by GTS, Inc. dated May 22, 2026.
- **Addendum No. 1** – Dated July 16, 2026
  - **Structural Drawings** as prepared by dated April 13, 2026.
  - **Civil Drawings** as prepared by Crafton Tull dated July 1, 2026.

**The scope of work for this proposal shall be in strict compliance with the plans, specifications, any addenda/revisions listed above, and the items listed below, including but not limited to:**

**INCLUDING BUT NOT LIMITED TO:**

1. Include all submittals, shop drawings, product data, concrete mix designs, samples, mock-ups, certificates, and warranties as required by the Contract Documents.
2. Subcontractor is responsible for all testing, lab reports, and material certifications required by the Contract Documents.
3. Subcontractor is responsible for including all sales tax (city, county, and state) required per local code.
4. Subcontractor is responsible for procuring and maintaining licenses to work within the project's jurisdiction.
5. Subcontractor shall be responsible for all notes and details pertaining to their scope of work, regardless of what area of the plans the notes are included.
6. Each prime contractor will require its Superintendent and Sub-Tier Superintendents to provide and use an iPad for CDI's Document Management Software CMiC on site (for daily use to facilitate drawing review, inspections, work completion, punch list items, etc.).
7. This Subcontractor, by submitting a bid, is acknowledging that they have read and, if they are successful bidder, agree to enter into a contract with CDI Contractors, LLC according to the terms and conditions of the CDI Contractors, LLC Subcontract Agreement, complete with its insurance and safety requirements.
8. If any Bidder wishes to substitute equipment or materials, which is believed to be equal to those specified, the Bidder shall make a request in writing to CDI for approval of such substitute equipment or materials at least seven (7) calendar days prior to the bid date. In proposing items for consideration, Bidder assumes all risk, costs, coordination with other trades, cost associated with other trades if substitution impacts their scope of work, and responsibility for item's final acceptance, compliance with the Bidding Documents and Contract Documents, integration into the Work, and performance.
9. Compute Request for Changes in work by the additions or deductions as follows:  
For work performed by Subcontractors:  
Net Cost of Materials a

|                                      |                |
|--------------------------------------|----------------|
| State Sales Tax                      | b              |
| Net Placing Cost                     | c              |
| W.C. Insurance Premium and FICA Tax  | d              |
| <u>Subtotal</u>                      | <u>a+b+c+d</u> |
| Overhead and Profit, 12% x (a+b+c+d) | e              |

10. The Contractor and the Contractor's Subcontractors shall not discriminate against any employee or applicant for employment because of race, religion, color, sex, or national origin. The Contractor shall take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, religion, color, sex, or national origin. Such actions shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices setting forth the policies of nondiscrimination.
11. The Contractor and the Contractor's Subcontractors shall, in all solicitations or advertisements for employees placed by them or on their behalf; state that all qualified applicants will receive consideration for employment without regard to race, color, sex or national origin.

### **STRUCTURAL STEEL SCOPE OF WORK**

This scope includes, but is not limited to, providing all labor, materials, tools, equipment, and supervision to complete the scope of work listed below:

1. Provide all structural and miscellaneous steel work complete including engineering, detailing, fabrication, delivery, unloading, hoisting, and erection as shown in the Contract Documents, except as specifically excluded below.
2. The work under this Subcontract includes but is not limited to furnishing and installing the following items.
  - a. Structural steel columns, girders, and beams.
  - b. Base plates
  - c. Anchor bolts.
  - d. Column & beam connections
  - e. Gussets.
  - f. Shear studs.
  - g. Bolts
  - h. Embedded plates and angles.
  - i. Anchor bolts, connection bolts and hardware as required for installation of all materials under this scope
  - j. HSS girts, sag rods, connections, hardware, etc.
  - k. Moment welds
  - l. Backing plates as required for moment connections
  - m. All steel components, including angles, bent plates, deformed bar anchors.
  - n. Edge angles and bent plate pour stops, including fasteners, elevated slab locations
  - o. Roof anchors with stiffener plates, HSS bracing, engineering, testing, and certification.
  - p. All members that do not receive fireproofing shall be shop primed
  - q. Provide and install 3x3x 1/4" angles punched to receive safety barrier cable as needed where there is no column
3. At L3 X 3 X 1/4 frames, delete clip angles, cope vertical leg and extend horizontal leg over framing - weld all around. For roof openings over 6" to 12" wide (i.e.: over-sized opening for roof drains), provide L2 X 2 X 1/4 frame around opening and extend to joists- weld all around.
4. Furnish and install all anchor bolts, erection bolts, setting plates, lifting/erection devices, temporary seats, bearing plates, adjustable erection bolt connects, and etc. as indicated, including layout drawings for coordination.
5. Furnish, install, and maintain while mobilized temporary fall protection within OSHA requirements at building perimeter (steel area only), floor openings, etc.

6. Connection engineering
7. Engineered shoring plan for beam splices.
8. Provide temporary hoist beam above existing slab. Removal after elevator installation.
9. Existing beam in elevator hoist to be modified. Coordinate alterations with shoring/support of materials to remain in place for duration of construction.
10. Installation of embedded miscellaneous metals will be provided by Others. This Subcontractor will be responsible for furnishing these materials unless specifically excluded herein. Embeds shall be delivered in a timely fashion so as not to delay the concrete schedule.
11. Grouting of base plates will be by Others.
12. Provide galvanized steel where required by the Contract Documents.
13. Welding equipment shall be diesel or gas generator driven and kept outside the buildings when directed by the Construction Manager.
14. Provide hoisting as required for unloading and shaking out of materials.
15. Furnish and install all metal stairs and stair railings including stringer mounted and wall mounted railings. Subcontractor shall coordinate in wall blocking requirements for wall mounted railings with the Construction Manager and Drywall Subcontractor.
16. Provide material and touch-up of steel primers and galvanizing.
17. Provide cable fall protection around perimeter of building.
18. Furnish install, and maintain all back rails, guardrails, and horizontal opening protection as necessary to comply with OSHA requirements, Owner requirements, and the requirements of the Construction Manager's safety program. This protection shall be maintained by the Subcontractor until the area is turned over to the construction manager for use by trades. Upon turnover to the construction manager, the protection will be maintained and removed by the Others.
19. Protect structures, utilities, sidewalks and other facilities from this Subcontractor's operations.
20. Subcontractor is responsible for all task lighting necessary to perform their work.
21. Replace / repair any areas damaged during this Subcontractor's scope of work.
22. Restore to existing conditions all areas disturbed by this Subcontractor.
23. Phasing as required.
24. Comply with OSHA Standards for Steel Erection Subpart R.
25. Complete fall protection adhering to CDI's safety requirements outlined in the Subcontract Agreement. Submission of a formal fall protection plan is required prior to proceeding with your work.
26. All temporary seats shown and/or required for steel erection.
27. Furnish, install, and remove OSHA approved safety cable system prior to slab decking for building perimeter and slab openings of the steel structure as required for safe steel erection, including provisions for attachment of cables. Cable connections and "nuts" to coordinate with the Steel Fabricator.
28. Furnish, install, and remove all temporary shoring, bracing and framing as required to install the steel structure covered under this scope. Coordination with other trades will be required so as not to impede their work.
29. Provide a Hot Work Permit, fire watch and incorporate the use of fire blankets during all cutting and/or welding operations.
30. Touch up primer, paint, galvanization, etc. as required on structural and miscellaneous steel due to chipping damage or field welding during erection.
31. Provide welding certifications for all personnel intended to perform field welding operations at the commencement of the project.
32. All vertical and horizontal layout associated with this work, working from benchmarks and control points established by others.
33. Steel frame is non-self-supporting and column anchor rods are designed for a completed condition only. Metal roof deck, elevated slabs, steel moment frames, braced frames and masonry shear walls are required to provide lateral stability for the frame and resistance to wind and seismic forces. Contractor shall provide all temporary bracing required to maintain stability of structural system.

## **SAFETY & SITE LOGISTICS**

1. This Subcontractor will provide sufficient manpower to meet the project schedule, including any overtime required to maintain the project schedule, at no additional charge unless the necessity for overtime is caused by others failing to maintain their project schedule through no fault of this Subcontractor or circumstances beyond control (such as "acts of God").
2. Use of personal vehicles on the project site is prohibited. Company vehicles only.
3. Coordinate on-site employee parking with CDI's Superintendent. Refer to Section 04 of the Bidder's Instructions Manual for location of available parking for the Construction Team.
4. Furnish, install, remove, relocate, and reinstall fencing or barricades as necessary to access Subcontractor's work areas. Initial fence installation by the Construction Manager.
5. Subcontractor is responsible for all damage(s) to existing asphalt and curb by this sub and any third-party sub/suppliers.
6. Replace / repair any areas damaged during this Subcontractor's scope of work that are outside the construction limits established by CDI.
7. Restore to existing conditions all areas disturbed by this Subcontractor.
8. CDI will facilitate the installation of silt fencing by others. In the event damage by this subcontractor occurs to the silt fencing in place, CDI will install new at the expense of this subcontractor through back-charge.
9. Provide flagging and traffic control as required for these operations as needed.
10. Subcontractors are responsible for unloading their own materials and deliveries. All materials are to be delivered F.O.B. jobsite to each location as scheduled.
11. Loading, staging and stocking of materials shall be coordinated with the Construction Manager's Superintendent. Deliveries must be scheduled to coincide with the installation of the work. No long-term on-site storage is provided.
  - a. Subcontractor will coordinate and plan material/product delivery to coincide with the schedule and workflow. Materials on hand will be limited to 3-5 days of work.
  - b. Materials shall be staged /bundled/organized off-site to the greatest extent possible to be delivered and staged into the current work areas. Appropriate "buffers" of material will be managed to ensure workflow is not interrupted.
  - c. Subcontractor will coordinate its work and obtain Contractor's Superintendent's prior approval of subcontractor's schedule for delivery, installation and/or placement of its materials, equipment, and crew shacks at the jobsite.
12. All truck and equipment traffic will be restricted to the immediate construction area.
13. Keep the roadway clear of dirt and debris from Subcontractor's own activities. This includes washing of tires as needed and directed.
14. Subcontractor is responsible for daily cleanup. Daily cleanup is defined as leaving work area neat and orderly and broom swept at the end of each shift. Subcontractor shall remove from the jobsite and properly dispose of any hazardous materials generated by this Subcontractor's operations.
15. Temporary power will be available for small tools but will not support electric welders or heaters. All welding and heating shall be done using fuel-powered equipment provided by this Subcontractor. OSHA guidelines shall be followed by this Subcontractor while using fuel-powered equipment.
16. It is this subcontractor's requirement to call one-call for all utility location within your scope of work.
17. During excavation operations, all slopes will be maintained in accordance with OSHA regulations in a continuous manner until completion of this Subcontractor's scope of work. (Trench safety 29 CFR 1926 subpart P).
18. Subcontractor shall require their employees to attend CDI Contractors Jobsite Safety Orientation prior to working on site.

19. Perform, review, and document Job Hazard Analysis (JHA's) for all work and with all employees prior to the start of work. JHA must be submitted to CDI for review and approval prior to commencement of work.
20. Subcontractor must fill out and submit daily reports to CDI's superintendent. The reports must include company name, Supervisor's name, manpower, daily work hours, summary of the day's work, and any delays found (if any). Submit reports daily.
21. Subcontractors must review one toolbox safety talk each week with the crew onsite. Signed documentation is to be submitted weekly.
22. Subcontractor's supervisor must attend CDI's subcontractor's meeting which occurs once a week. CDI's Superintendent will determine date and time.
23. Subcontractor's supervisor must attend a daily huddle before starting the daily shift.
24. Provide 100% fall protection for all work over six feet. This includes working on scissor lifts.
25. Subcontractor must attend a CDI pre-mobilization and pre-installation meetings prior to the start of any portion of the Work.
26. Furnish, install and maintain all safety measures necessary to comply with OSHA requirements, Owner requirements, and the requirements of the Construction Manager's safety program. This protection shall be maintained by the Subcontractor until the area is turned over to the construction manager for use by trades.
27. Subcontractor is responsible for protection of their open trenches, holes, etc. to maintain a safe operation. At the end of each shift, hole or trench protection shall consist of either covers secured in place or fence panels protecting all sides of open trenches. In roadways and drives, open trenches shall be covered with road plates secured in place.
28. Compliance with all rules, regulations, and requirements of local, state, and federal authorities.
29. Subcontractor shall coordinate this scope of work with local utility company.
30. Phasing as required.

### **EXCLUSIONS**

- 1.

### **BASE BID**

All prices quoted represent the entire cost of the project in accordance with the bidding documents, and bidder acknowledges that no subsequent claim will be recognized for any increase in wage scales, material prices, cost or any other rates affecting the construction industry and/or this project.

### **PRICING BREAKDOWN**

|                                 |          |
|---------------------------------|----------|
| 1. STRUCTURAL STEEL FABRICATION | \$ _____ |
| 2. STRUCTURAL STEEL ERECTION    | \$ _____ |
| 3.                              | \$ _____ |
| 4.                              | \$ _____ |

---

**BASE BID (Including Applicable Taxes)**

**\$ \_\_\_\_\_**

---

(Write Base Bid Amount in Words Above)

### **ALTERNATE PRICES**

1. (2) ton at a minimum cost of \$10,000/ ton of miscellaneous steel beams, channels and angles in addition to the framing shown on the plans and details. \$ \_\_\_\_\_
2. Erection, fabrication, design and detailing costs for the additional framing mentioned above. \$ \_\_\_\_\_

Voluntary Alternates in addition to those listed above are welcome and may be used in assessing the low qualified bidder. Detailed submittal information and compliance with Division 00 and 01 Alternates specifications must be issued along with the Bid Form for any alternates to be considered.

1. Bidder Defined: \_\_\_\_\_ \$ \_\_\_\_\_
2. Bidder Defined: \_\_\_\_\_ \$ \_\_\_\_\_
3. Bidder Defined: \_\_\_\_\_ \$ \_\_\_\_\_
4. Bidder Defined: \_\_\_\_\_ \$ \_\_\_\_\_

### **UNIT PRICES**

Provide the following unit prices on the Bid Form. This subcontract will be a fixed lump sum subcontract agreement. For revisions to the scope of the project and/or revisions to the contract documents, the lump sum subcontract amount would be adjusted by change order at the unit prices issued below:

1. Mobilization Fee \$/EA
2. \$/EA
3. \$/EA

### **ADDENDA ACKNOWLEDGEMENT**

The bidder acknowledges receipt and incorporation of the following addenda into this Proposal's BASE BID. List addendum number(s) & date(s): \_\_\_\_\_

---

### **DISADVANTAGED BUSINESS DESIGNATION**

Please check the applicable box:

MBE ☐ SDV ☐ DBE ☐ SBA ☐ WBE ☐

### **CONFIRM THE FOLLOWING:**

Check boxes to confirm each.

1. ☐ Bidder has filled out all items on this CDI Bid Proposal Form

2. ☐ Bidder has reviewed and will meet requirements of "CDI's Project Schedule". (*Located in Section 02 of the CDI Bid Manual.*)
3. ☐ Bidder has reviewed and will meet requirements of "CDI's Site Logistics and Safety Plan" (*Located in Section 03 of the CDI Bid Manual.*)
4. ☐ Bidder has completed & attached CDI's Subcontractor Prequalification Form. (*Located in Section 04 of the CDI Bid Manual.*)
5. ☐ Bidder has reviewed and will meet requirements of "CDI's Sample Subcontractor Agreement" (*Located in Section 05 of the CDI Bid Manual.*)
6. ☐ Bidder has reviewed and will meet requirements of CDI's "Attachment I, Exhibits to the Subcontractor Agreement" (*Located in Section 06 of the CDI Bid Manual.*)
7. ☐ Bidder has completed and attached all applicable "Misc. Forms" located in Section 12 of the CDI Bid Manual.

**MATERIALS LEAD TIMES OVER 2 WEEKS**

If any materials in this bidder's scope of work have lead times greater than 2 weeks, list the material and current lead time as of bid day. (Include shop drawing, delegated design, and fabrication lead times / durations if applicable)

1. \_\_\_\_\_
2. \_\_\_\_\_
3. \_\_\_\_\_
4. \_\_\_\_\_
5. \_\_\_\_\_

**ADMINISTRATION OF CONTRACTS**

The undersigned, in submitting this document, agrees that if he is the successful Bidder, he or she will enter into a contract with CDI Contractors, LLC according to the terms and conditions of the standard CDI Contractors, LLC. Subcontract Agreement. In addition, the undersigned agrees that this bid may not be withdrawn for a period of ninety (90) days after the bid issuance.

Respectfully submitted:

\_\_\_\_\_  
Firm

\_\_\_\_\_  
Bidder Contact Name & Title (printed)

\_\_\_\_\_  
Bidder Contact Signature

\_\_\_\_\_  
Mailing Address

\_\_\_\_\_  
Street Address

\_\_\_\_\_  
Telephone

\_\_\_\_\_  
Fax No.

---

Bidder Contact e-mail

Texas Contractor's License No. \_\_\_\_\_

Federal I.D. No. or SS # \_\_\_\_\_ – \_\_\_\_\_

Date and Time of Bid \_\_\_\_\_