



**POND**  
 Architects • Engineers • Planners  
 3500 Parkway Lane  
 Suite 600  
 Fort Smith, AR 72430  
 Phone: 479-336-7744  
 Fax: 479-336-7744  
 Web: www.pondco.com

Copyright 2008 by Pond & Company. All rights reserved. This document is the property of Pond & Company. It is to be used only for the specific project identified or referred to herein and is not to be used, in whole or in part, except by the express agreement of Pond & Company.

**188th Fighter Wing**

Mark	Description	Date
0	ISSUED FOR CONSTRUCTION	4/11/08
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		

Designed by:	SMS
Drawn by:	CSH
Checked by:	SR
Reviewed by:	KCS
Date:	4-11-08

COMPOSITE A-10 AIRCRAFT MAINTENANCE FACILITY  
 FT. SMITH, ARKANSAS  
**REFLECTED CEILING PLAN**

Sheet reference number:  
**A-103**  
 Sheet 18 of 69

**GENERAL NOTES:**

- ALL MATERIAL EXPOSED WITHIN THE CEILING PLENUMS SHALL BE NON-COMBUSTIBLE OR SHALL BE LIMITED IN COMBUSTIBILITY AND HAVE A FLAME SPREAD INDEX OF 25, MIN. AND A SMOKE-DEVELOPMENT INDEX OF 50, MIN., PER ASTM E84.
- THE SUSPENDED ACOUSTICAL AND GYPSUM WALLBOARD CEILING SYSTEMS SHALL BE INSTALLED AT A HEIGHT OF 8'-9", U.N.O.
- SPRINKLER HEADS TO BE CENTERED IN ACOUSTICAL CEILING PANELS WHERE THEY OCCUR- COORDINATE THE LOCATION OF THE SPRINKLER HEADS WITH OTHER CEILING FIXTURES AND EQUIPMENT.

- HIGH INTENSITY DOWNLIGHTING
- ⊖ STANDARD 1X4 STRIP LIGHTING
- ⊖ EMERGENCY 1X4 STRIP LIGHTING
- ⊖ 2X4 LIGHTING
- PS PROJECTION SCREEN

- WALL OR CEILING MOUNTED EXIT SIGN
- ⊖ METAL SOFFIT BY M.B. MANUFACTURER
- ⊖ SLOPED STEEL DECK ON FRAMING
- ⊖ INSTALL 5/8" WATER-RESISTANT GYPSUM BOARD AT THE CEILING OF RESTROOMS, SHOWERS, AND LOCKER ROOMS- INSTALL STANDARD GWB AT REMAINING LOCATIONS TO RECEIVE DRYWALL
- ⊖ 2'-0" x 2'-0" ACOUSTICAL CEILING SYSTEM WITH 3-1/2" ACOUSTICAL BATT CONTINUOUS ABOVE

- 1 HR. FIRE-RATED PARTITION
- 2' x 4' FLUORESCENT LIGHT FIXTURE
- 1' x 4' FLUORESCENT LIGHT FIXTURE
- 2' x 4' EMERGENCY FLOOR LIGHT FIXTURES
- 1' x 4' EMERGENCY FLOOR LIGHT FIXTURE
- 24" x 24" MECH. DIFFUSERS
- 24" x 24" MECH. RETURN AIR GRILLES
- 2'-0" x 2'-0" ACOUSTICAL CEILING SYSTEM



SCALE: 1/8" = 1'-0"

REFLECTED CEILING PLAN  
 SCALE: 1/8"=1'-0"

