



LINTEL SCHEDULE					
TYPE WALL	WALL THICKNESS	OPENING WIDTH FROM UP TO	LINTEL SIZE	REMARKS	SHAPE
FACE BRICK	4"	0'-0" - 3'-4"	3 1/2" x 3 1/2" x 1/4" STL. Z	LOOSE	3/4"
CLAY TILE	4"	3'-5" - 8'-0"	3 1/2" x 4" x 5/8" STL. Z	LOOSE	3/4"
CONG. BLOCK OR L.W.C.M.U.	4"	0'-0" - 3'-4"	3" x 1 1/2" PL. W/ 8" x 1/4" TEE	WELD PL. & TEE	1 1/2"
CLAY TILE	4"	3'-5" - 8'-0"	3" x 1 1/2" PL. W/ 7" x 3/8" TEE	WELD PL. & TEE	1 1/2"
CLAY TILE OR BRICK	8"	0'-0" - 3'-4"	5" x 1 1/2" PL. W/ 8" x 1/4" TEE	WELD PL. & TEE	1 1/2"
CONG. BLOCK OR L.W.C.M.U.	8"	3'-5" - 8'-0"	5" x 1 1/2" PL. W/ 7" x 3/8" TEE	WELD PL. & TEE	1 1/2"
CONG. BLOCK OR L.W.C.M.U.	8"	0'-0" - 3'-4"	7" x 1 1/2" PL. W/ 8" x 1/4" TEE	WELD PL. & TEE	1 1/2"
CONG. BLOCK OR L.W.C.M.U.	8"	3'-5" - 8'-0"	7" x 1 1/2" PL. W/ 7" x 3/8" TEE	WELD PL. & TEE	1 1/2"
CONG. BLOCK OR L.W.C.M.U.	12"	0'-0" - 8'-0"	18" LONG LINTEL BLOCK - 4 NO. 4 2 BARS TOP & 2 BOTT.		3/4"
CONG. BLOCK OR L.W.C.M.U.	12"	8'-1" - 12'-0"	18" LONG LINTEL BLOCK - 4 NO. 4 2 BARS TOP & 2 BOTT.		3/4"
CONG. BLOCK OR L.W.C.M.U.	12"	0'-0" - 8'-0"	18" LONG LINTEL BLOCK - 4 NO. 5 2 BARS TOP & 2 BOTT.		3/4"
CONG. BLOCK OR L.W.C.M.U.	12"	8'-1" - 12'-0"	18" LONG LINTEL BLOCK - 4 NO. 5 2 BARS TOP & 2 BOTT.		3/4"

NOTES:
 1- PROVIDE LINTELS FOR ALL OPENINGS IN MASONRY WALLS FOR ALL TRADES INCLUDING MECH. & ELECT. IF NOT SHOWN OTHERWISE LINTELS SHALL BE AS SCHEDULED ABOVE.
 2- USE COMBINATION OF 4" FACE BRICK & 8" BACK-UP LINTELS FOR 12" EXTERIOR WALLS.
 3- ALL STEEL LINTELS TO LAP OVER EDGE OF OPENING A MIN. OF 6".
 4- FILL ALL CONG. & L.W.C.M.U. LINTEL BLOCK VOIDS W/ CONCRETE.
 5- L.W.C.M.U. = LIGHT WEIGHT CONCRETE MASONRY UNIT.