



GENERAL NOTES

- WHERE WALLS AND THEIR ASSOCIATED OPENINGS ARE TO BE DEMOLISHED, REMOVE EXISTING WALL CONSTRUCTION IN ITS ENTIRETY FROM FLOOR TO STRUCTURE ABOVE INCLUDING DOORS, DOOR FRAMES, VISION PANELS, BASE, ASSOCIATED ELEC./MECH. WORK ETC. (EXTENT SHOWN BY BROKEN LINES). PATCH EXISTING ADJACENT AREAS, AS REQUIRED, THAT HAVE BEEN DISTURBED BY DEMOLITION AND PREPARE SURFACES TO RECEIVE NEW FINISHES.
- WHERE OPENINGS ARE TO BE REMOVED IN WALLS THAT ARE EXISTING TO REMAIN, REMOVE EXISTING DOOR OR VISION PANEL, GLAZING AND FRAME ASSEMBLY. CLOSE EXISTING OPENING TO MATCH ADJACENT CONSTRUCTION. ALIGN NEW WORK FLUSH WITH EXISTING ADJACENT PARTITION. PREPARE SURFACE AS REQUIRED TO RECEIVE NEW SCHEDULED FINISH.
- WHERE NEW OPENINGS ARE SHOWN IN WALLS THAT ARE EXISTING TO REMAIN, PROVIDE OPENING IN EXISTING PARTITION AS REQUIRED TO RECEIVE NEW DOOR FRAME OR VISION PANEL AS SHOWN. PATCH AND PREPARE ADJACENT SURFACES AS REQUIRED TO RECEIVE NEW SCHEDULED FINISH.

DEMOLITION LEGEND

- EXISTING PARTITIONS TO BE DEMOLISHED
- EXISTING ELEMENTS TO BE DEMOLISHED
- EXISTING ELEMENTS TO REMAIN
- EXISTING DOORS TO REMAIN
- EXISTING DOORS TO BE DEMOLISHED
- EXISTING GLAZING TO BE DEMOLISHED
- PROVIDE OPENING IN EXISTING PARTITION

SHEET KEYNOTES

- REMOVE FENCE, PREPARE FOR NEW UTILITY ENCLOSURE
- REMOVE CONCRETE CURB AND PATCH CONCRETE SLAB TO MATCH EXISTING
- EXISTING FIRE EXTINGUISHER CABINET TO REMAIN
- EXISTING DRINKING FOUNTAIN TO REMAIN
- REMOVE EQUIPMENT CURB, PREPARE SUBFLOOR FOR NEW FINISH
- REMOVE MEZZANINE ABOVE



US Army Corps of Engineers®

MARK	DESCRIPTION	DATE

DESIGNED BY: D. REMY	ISSUE DATE: JUNE 2024
DRAWN BY: M. DAVIS	SOLICITATION NO.:
CHECKED BY: S. BLAIR	CONTRACT NO.:
SUBMITTED BY: C. SEGHI	
SIZE: ANSI D	

US ARMY CORPS OF ENGINEERS
FORT WORTH DISTRICT
819 TAYLOR ST., FORT WORTH, TX 76102

BLAIRREMY
ARCHITECTS

SEGHRICK
CORPORATION

FORT SMITH, ARKANSAS
EBBING ANG RENOVATION OF 5 FACILITIES
A-2020-S
DEMOLITION PLAN
BUILDING 201

SHEET ID
AD101

Plot Date: 6/26/2024 4:58:26 PM File Path: \\usace-ebbing\EBBING\AFC\03\RF\RF BUILDING 201_A224.rvt

A1 DEMOLITION PLAN
3/16" = 1'-0"

PLAN NORTH



GENERAL NOTES

1 REFER TO 01 10 00, ATTACHMENT C FOR SCOPE OF FINISHES

PROGRAMMING LEGEND

- BULK SPARES
- CIRCULATION
- COMPACT STORAGE SYSTEM
- RACKED STORAGE AREA
- RESTROOMS
- SEMI BULKY STORAGE AREA
- SPARES TRANSIT AREA
- UTILITY SPACES

FLOOR PLAN LEGEND

- EXISTING PARTITIONS TO REMAIN
- NEW MASONRY PARTITIONS
- NEW METAL STUD PARTITIONS
- EXISTING DOORS TO REMAIN
- NEW DOORS
- UTILITY ENCLOSURE (ABOVE)

SHEET KEYNOTES

- 1 CHAIN LINK ENCLOSURE OVER UTILITY YARD (ABOVE)
- 2 EXISTING COVERED ENTRY TO REMAIN (ABOVE)
- 3 FLOOR-MOUNTED SERVICE SINK
- 4 EXISTING DRINKING FOUNTAIN TO REMAIN
- 5 EXISTING FIRE EXTINGUISHER CABINET TO REMAIN
- 6 WALL-MOUNTED LAVATORY
- 7 WATER CLOSET
- 8 METAL PANEL UTILITY ENCLOSURE



US Army Corps of Engineers®

MARK	DESCRIPTION	DATE

DESIGNED BY: D. REMY	ISSUE DATE: JUNE 2024
DRAWN BY: M. DAVIS	SOLICITATION NO.:
CHECKED BY: S. BLAIR	CONTRACT NO.:
SUBMITTED BY: C. SEGHI	
SIZE: ANSI D	

US ARMY CORPS OF ENGINEERS
FORT WORTH DISTRICT
819 TAYLOR ST., FORT WORTH, TX 76102

BLAIR SEGHI
ARCHITECTS

MERRICK
ARCHITECTS

FORT SMITH, ARKANSAS
EBBING ANG RENOVATION OF 5 FACILITIES
A-2020-S
CONCEPT PLAN
BUILDING 201

SHEET ID
A-002

A1 CONCEPT PLAN
3/16" = 1'-0"

PLAN NORTH

Plot Date: 6/26/2024 4:58:25 PM File Path: \\adobe01\csc\ebbing\ANG_EB_RFP\5\Renovation\EBBING_403_03_RFP_BUILDING_201_A22.rvt

