

## **DEMOLITION NOTES**

- DRAWINGS OF EXISTING CONDITIONS HAVE BEEN COMPILED FROM EXISTING DATA SUPPLIED TO THE A/E. THE ARCHITECT A/E MAKES NO WARRANTY, EITHER EXPRESSED OR IMPLIED, FOR THE ACCURACY OR COMPLETENESS OF THE EXISTING INFORMATION RECORDED. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AND NOTIFY THE C.O. IMMEDIATELY OF ANY DISCREPANCIES OR CONFLICTS THAT MIGHT ARISE IN THE COURSE OF DEMOLITION WORK.
- VERIFY LOCATIONS OF EXISTING MECHANICAL, PLUMBING AND ELECTRICAL UTILITIES. LOCATE AND PROTECT UTILITIES TO REMAIN. DISCONNECT, REMOVE BACK TO THE NEAREST JUNCTION BOX OR PANEL AS REQUIRED AND CAP DESIGNED UTILITIES WITHIN THE DEMOLITION AREA. REFER TO THE MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFO.
- THE DEMOLITIONS ARE DIAGRAMMATIC AND GENERAL IN NATURE. THE INTENT IS TO ILLUSTRATE DEMOLITION REQUIRED IN THE SPACES UNLESS NOTED OTHERWISE. FIELD VERIFICATION OF EXISTING CONDITIONS AND DETERMINATION OF SPECIFIC QUANTITIES ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- REMOVAL AND DISPOSAL OF DEMOLITION DEBRIS IS THE RESPONSIBILITY OF THE CONTRACTOR. VERIFY THE HAULING ROUTE THROUGH THE BUILDING, DEMOLITION STAGING AREA AND THE LOCATION OF THE DUMPSTER WITH THE C.O. PRIOR TO THE START OF THE DEMOLITION. DISPOSAL OF RUBBISH SHALL BE DONE IN A LEGAL MANNER.

## **DEMOLITION LEGEND**

EXISTING ELEMENTS

ELEMENTS TO BE DEMOLISHED

**EXISTING DOORS** 

EXISTING DOORS TO BE DEMOLISHED



OPEN TO BELOW

## **KEYNOTES**

- 1 DEMO EXISTING CHAINLINK WALL AND GATE
- REMOVE EXISTING PARTITION WALL AND DOOR
- REMOVE AND REPLACE EXISTING EXTERIOR DOORS
- REMOVE EXISTING EXTERIOR DOOR AND SEAL / INFILL
- 5 REMOVE EXISTING LOCKERS
- REMOVE EXISTING PLUMBING FIXTURES AND TOILET
- REMOVE AND REPLACE EXISTING CABINETS AND PLUMBING
- REMOVE EXISTING CABINETRY
- REMOVE EXISTING TRANSOM WINDOW AND SEAL / INFILL
- 10 EXISTING BRIDGE CRANE RUNWAY BEAMS ABOVE

**US Army Corps** of Engineers ®

BLAIRREMY REMERRIA

IN PLAN - GROU BUILDING 214

SHEET ID

AD101