



DIGI
SECURITY SYSTEMS

We have prepared a quote for you

**Rogers Public Schools - New Technology
Office**

Quote # 017904
Version 1

Prepared for:

Rogers Public Schools

Dan Caley
Dan.Caley@rpsar.net

Monday, March 17, 2025

Rogers Public Schools
Dan Caley
500 W Walnut St
Rogers, AR 72756
Dan.Caley@rpsar.net

Dear Dan,

DIGI Security Systems will provide the following material and services:

DEMO

- DIGI Security will demo the entire existing intrusion alarm system including all sensors, cabling, keypads, power supplies, etc. to ensure all components of the existing intrusion detection system are removed from the building in its entirety.
- DIGI Security will remove the cabling and electronic door hardware on all existing interior access control doors. All cabling servicing interior access control doors will be removed in its entirety from the head end termination location, all the way through to the final device connection location.

STRUCTURED CABLING

- DIGI Security will reroute all existing structured cabling to service 254 network drops throughout the interior of the building.
- DIGI Security will route all cabling servicing modular furniture through split duct, and into modular furniture cable pathways.
- DIGI Security will pull back all unused cabling penetrating existing walls, and neatly coil above the ceiling for future cabling needs.
- DIGI Security will terminate all CAT6 cabling with new CommScope Uniprise CAT6 M-Series jacks, and install inside CommScope faceplates, modular furniture plates, and surface mount boxes
- DIGI Security will test and label all cabling according to TIA standards, and Roger's Public School's specifications.
- Certification results will be provided to Roger's Public School upon completion of this project.

VIDEO SURVEILLANCE

- DIGI Security will pull (20) CommScope Uniprise plenum rated green CAT6 cable out to new camera locations.
- DIGI Security will terminate all CAT6 cabling with CommScope CAT6 Uniprise jacks.
- DIGI Security will test and label all cabling according to TIA standards and Roger's Public School's specifications.
- DIGI Security will install (14) interior cameras provided by Roger's Public Schools.
- DIGI Security will install (6) exterior cameras provided by Roger's Public Schools.
- DIGI Security will provide all Avigilon camera hardware required for camera installation. Roger's Public Schools will provide IR Rings and Dome Covers for the multi-sensor cameras.
- DIGI Security will configure and install (1) NVR provided by Roger's Public Schools. All NVR and camera settings will be configured according to Roger's Public School's specifications.
- DIGI Security will test system for proper functionality and operation, and will make any changes necessary for system optimization.

ACCESS CONTROL

- DIGI Security will pull plenum rated composite access control cabling out to (3) door locations for access control.
- DIGI Security will install (1) 4-Door Life Safety Panel.
- DIGI Security will install (1) Avigilon 1502.

- DIGI Security will install (1) Avigilon MR52.
- DIGI Security will install (3) Adam's Rite electric deadlatches.
- DIGI Security will install (3) HID readers.
- DIGI Security will install (3) PIR sensors.
- DIGI Security will install (4) Door Position sensors.
- DIGI Security will program and configure all (3) doors inside Avigilon's Access Control Software according to Roger's Public School's specifications.
- DIGI Security will test system for proper functionality and operation, and will make any changes necessary for system optimization.

EXCLUSIONS

- This price assumes all existing cabling and patch panels are in proper condition and meet or exceed industry standards. Any troubleshooting and repair of existing cabling and patch panels will be an additional cost.
- This price assumes all Avigilon cameras provided by Roger's Public Schools are in proper operating condition and meet or exceed industry standards. Any replacement cameras will be provided at an additional cost.
- This price assumes Avigilon NVR provided by Roger's Public Schools is in proper operating condition and meets or exceeds industry standards.
- All VAC power shall be provided by others.
- All network switches shall be provided by others.

TIPS CONTRACT # 230202

A handwritten signature in black ink, appearing to read "Andrew Fairchild".

Andrew Fairchild
Account Manager
Arkansas