

**SC JOHNSON AR - STE 300  
RENOVATION**

903 N. 47TH ST. STE 300  
ROGERS, AR 72756



1	4	ISSUE FOR DEMO PERMIT	12/12/2025
3		UPDATED IFE	12/08/2025
2		90% CD REVIEW	11/11/2025
1		ISSUE FOR ENGINEERING	10/21/2025

DELTA ISSUE DESCRIPTION DATE




**NEW YORK**  
100 BROADWAY 12th FLOOR  
NEW YORK CITY, NY 10005  
TEL 212-682-6909

©2025 INTERIOR ARCHITECTS, P.C., A NEW YORK PROFESSIONAL SERVICES CORPORATION. ALL DRAWINGS AND WRITTEN MATERIAL HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED, OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT.

Owner Approval  
05SCJS.0037.000 1/8" = 1'-0"  
Job No. Scale

**DEMOLITION REFLECTED  
CEILING PLAN**

**A-0.1**



1 03 DEMO RCP  
1/8" = 1'-0"



**DEMO RCP LEGEND**

- TYP. CEILING GRID AND LIGHT FIXTURE TO BE REMOVED
- EXIT SIGN TO BE REMOVED
- EXISTING CONSTRUCTION TO BE DEMOLISHED
- EXISTING CONSTRUCTION TO REMAIN

**SHEET NOTES**

1. EXISTING ELEMENTS TO REMAIN UNLESS NOTED OTHERWISE.
2. SEE ENGINEERING DRAWINGS FOR INFORMATION REGARDING REMOVAL OF MEP, TEL/DATA AND SECURITY EQUIPMENT. REMOVE ABANDONED TEL/DATA CABLING WHERE DIRECTED BY OWNER AND/OR APPLICABLE OWNERS DATA/TELECOM VENDOR/SUBCONTRACTOR.
3. REMOVE CEILINGS, INCL. BUT NOT LIMITED TO GRID, ACOUSTIC PANELS, GYP. BD, CEILINGS, SPECIALTY CEILINGS, HANGERS, FRAMING AND SUPPORTS, UNLESS CLEAN & PREPARED FOR NEW WORK.
4. REMOVE LIGHT FIXTURES INCL. BUT NOT LIMITED TO SUPPORTS, CONDUIT AND WIRING. COORDINATE WITH OWNER'S REPRESENTATIVE/BUILDING MANAGEMENT IF ANY LIGHT FIXTURES INDICATED FOR REMOVAL SHOULD BE SALVAGED AND STORED FOR RE-USE, OR RETURNED TO BUILDING STOCK. ANY FIXTURES SCHEDULED TO BE RELOCATED SHOULD BE TESTED AND BE IN FULL OPERATING ORDER BEFORE STORING UNLESS NOTED OTHERWISE.
5. BRACING TO REMAIN AT ALL EXISTING PARTITIONS SCHEDULED TO REMAIN.
6. COORDINATE WITH OWNER'S REPRESENTATIVE/BUILDING MANAGEMENT IF ANY ACOUSTIC CEILING PANELS OR GRID INDICATED FOR REMOVAL SHOULD BE SALVAGED AND STORED FOR RE-USE, OR RETURNED TO BUILDING STOCK. ALL BROKEN, STAINED, OR DAMAGED TILES OR GRID SHALL BE DISCARDED AS APPLICABLE.
7. COORDINATE WITH OWNER'S REPRESENTATIVE/BUILDING MANAGEMENT IF ANY EXISTING COMPLIANT FIRE ALARM DEVICES, EXIT SIGNS, LIGHTING AND HVAC DEVICES INDICATED FOR REMOVAL SHOULD BE SALVAGED AND STORED FOR RE-USE, OR RETURNED TO BUILDING STOCK.

**KEYNOTES**

NO.	DESCRIPTION
009	EXISTING CEILING AND LIGHTING IN ELEVATOR LOBBY TO REMAIN.