

### SIGNAGE SCHEDULE

SIGN TEXT	ROOM No.	SIGN TYPE	SIGN DESCRIPTION	COUNT
Phase A				
STERILE STORAGE, OVERFLOW	L107	A	IN-CREATIVE SIGN RM SGN (A)	1
ELECTRICAL	L112	D	IN-CREATIVE SIGN RM SGN (D)	1
BREAK DOWN	L102	A	IN-CREATIVE SIGN RM SGN (A)	1
BREAK DOWN	L102	A	IN-CREATIVE SIGN RM SGN (A)	1
STORAGE	L104	D	IN-CREATIVE SIGN RM SGN (D)	1
SUPPLY OFFICE	L105	A	IN-CREATIVE SIGN RM SGN (A)	1
IT	L106	D	IN-CREATIVE SIGN RM SGN (D)	1
COPY ROOM	L107	A	IN-CREATIVE SIGN RM SGN (A)	1
STERILE STORAGE	L108	A	IN-CREATIVE SIGN RM SGN (A)	1
STERILE STORAGE	L108	A	IN-CREATIVE SIGN RM SGN (A)	1
SEE DETAIL ON SHEET AF604-A	L108	F	IN-CREATIVE SIGN RM SGN (F)	1
SEE DETAIL ON SHEET AF604-A	L108	F	IN-CREATIVE SIGN RM SGN (F)	1
SEE DETAIL ON SHEET AF604-A	L110	C	IN-CREATIVE SIGN RM SGN (C)	1
SEE DETAIL ON SHEET AF604-A	L110	F	IN-CREATIVE SIGN RM SGN (F)	1
SEE DETAIL ON SHEET AF604-A	L111	C	IN-CREATIVE SIGN RM SGN (C)	1
HAC	L113	D	IN-CREATIVE SIGN RM SGN (D)	1
SEE DETAIL ON SHEET AF604-A	L113	F	IN-CREATIVE SIGN RM SGN (F)	1
Phase A: 17				17
Grand total: 17				17

### INTERIOR FINISH SCHEDULE - A

Room No.	Room Name	Level	Floor Finish	Base Finish	Wall Finish				Ceiling Finish	Millwork Horizontal	Millwork Vertical	Wall Protection	Comments
					North	South	East	West					
FIRST FLOOR													
E-102	ELECTRICAL	FIRST FLOOR	EPY-1	RB-1	P-2	P-2	P-2	P-2	EXISTING	---	---	---	
L101	ELECTRICAL	FIRST FLOOR	EPY-1	RB-1	P-2	P-2	P-2	P-2	EXISTING	---	---	---	
L102	BREAK DOWN	FIRST FLOOR	C-1	RB-1	P-1	P-1	P-1	P-1	AT-1	---	---	WP-3	
L103	CORR	FIRST FLOOR	RES-6A	RES-6A	P-1	P-1	P-1	P-1	AT-1	---	---	WP-1	
L104	STORAGE	FIRST FLOOR	RES-3	RES-3	P-2	P-2	P-2	P-2	AT-1	---	---	---	
L105	SUPPLY OFFICE	FIRST FLOOR	CPT-1	RB-1	P-1	P-1	P-1	P-1	AT-1	---	---	---	
L106	IT	FIRST FLOOR	EPY-1	RB-1	P-1	P-1	P-1	P-1	EXISTING	---	---	---	3/4" PLYWOOD
L107	COPY ROOM	FIRST FLOOR	CPT-1	RB-1	P-1	P-1	P-1	P-1	AT-1	---	---	---	
L108	STERILE STORAGE	FIRST FLOOR	RES-6A	RES-6A	P-1	P-1	P-1	P-1	AT-1	---	---	WP-2	
L110	TOILET	FIRST FLOOR	PWT-1	---	PWT-1	PWT-1	PWT-1	PWT-1	GWB(SC)P-1	---	---	---	FULL HEIGHT WALL TILE; *DEDUCT ALTERNATE 1: DOWNGRADE BATHROOM PORCELAIN TILE WALLS AND FLOORS TO WALL PAINT AND RESINOUS EPOXY FLOORING.
L111	TOILET	FIRST FLOOR	PWT-1	---	PWT-1	PWT-1	PWT-1	PWT-1	GWB(SC)P-1	---	---	---	FULL HEIGHT WALL TILE; *DEDUCT ALTERNATE 1: DOWNGRADE BATHROOM PORCELAIN TILE WALLS AND FLOORS TO WALL PAINT AND RESINOUS EPOXY FLOORING.
L112	STERILE STORAGE, OVERFLOW	FIRST FLOOR	RES-6A	RES-6A	P-1	P-1	P-1	P-1	AT-1	---	---	WP-2	
L113	HAC	FIRST FLOOR	PWT-1	---	PWT-1P-2	PWT-1P-2	PWT-1P-2	PWT-1P-2	AT(SP)	---	---	---	50" WALL TILE WAINSCOT
L115	SUPPLY TECH OFFICE	FIRST FLOOR	CPT-1	RB-1	P-1	P-1	P-1	P-1	AT-1	---	---	---	
L115A	SUPPLY TECH SUPERVISOR	FIRST FLOOR	CPT-1	RB-1	P-1	P-1	P-1	P-1	AT-1	---	---	---	
L116	EMS PRIMARY	FIRST FLOOR	CPT-1	RB-1	P-1	P-1	P-1	P-1	AT-1	---	---	---	
T-100	IT	FIRST FLOOR	EPY-1	RB-1	P-1	P-1	P-1	P-1	EXISTING	---	---	---	

A

B

C

D

E

F

4/12/2024 11:19:29 AM

BIM 360://19022 - Fayetteville IDIQ Project No. 664-19-403 Renovation of SPS/19022 - ARCH - R2020.rvt

Revision Number	Revisions:	Date:

**CONSULTANTS**  
CONSULTING STRUCTURAL ENGINEERS

**ARCHITECT/ENGINEER OF RECORD**  
A/E:  
HARRELL DESIGN GROUP PC  
10720 SIKES PLACE, SUITE 100  
CHARLOTTE, NC 28277  
704-814-1346  
POC: LEE HARRELL PE, LEED AP, QCCP  
PRESIDENT  
WWW.HARRELLDG.COM  
COPYRIGHT © 2024

**STAMP**  
Professional Engineer Seal for Lee Harrell, State of North Carolina, License No. 10000.

**DRAWING TITLE**  
INTERIOR FINISH SCHEDULE AND SIGNAGE SCHEDULE

**APPROVED**

**PHASE**  
CONSTRUCTION DOCUMENTS SUBMISSION

**FULLY SPRINKLERED**

**PROJECT TITLE**  
RENOVATE SPACE FOR LOGISTICS (B-1)

**PROJECT NUMBER**  
564-24-104

**BUILDING NUMBER**  
1

**LOCATION**  
FAYETTEVILLE VA MEDICAL CENTER

**ISSUE DATE**  
11 APRIL 2024

**CHECKED**  
Checker

**DRAWN**  
Author

**DRAWING NUMBER**  
AF602-A

**Engineering Service**  
VETERANS HEALTH CARE SYSTEM OF THE OZARKS  
VA U.S. Department of Veterans Affairs