PLUMBING ROUGH-IN SCHEDULE

KEY	ITEM	DESCRIPTION			
P 1		AREA FLOOR DRAINS	See Mechanical Plans for fixture specifications.		
P 2	8	DOUBLE DECK CONVECTION OVEN	Plumber to supply disconnect.		
		NATURAL GAS (2) 3/4"	BTU 120,000	HT + 0 "AFF	
		GAS NOTE Two (2) gas rough-In locations required @+24" A.F.F & @+48" A.F.F			
			Plumber to BTC thru gas quick disconnect kit (by KEC)		
P 3		SPARE NUMBER			
P 4		SPARE NUMBER			
P 5	10	GRIDDLE/OPEN BURNER RANGE			
		NATURAL GAS 1-1/4"	BTU 130,000	HT + 24 "AFF	
		GAS NOTE Plumber to BTC thru gas quick disconnect kit (by KEC).			
P 6		FLOOR SINK	Drains from item #15 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE 1-1/2"	TYPE FS	HT + 0 "AFF	
P 7	15	S/S WORK TABLE W/SINK	Drains to P6 Plumber to bring hot & cold water down from ceiling via S/S chase integrail with this item.		
		SUPPLY CW 1/2"	HW 1/2"	HT +102 "AFF	
		INDIRECT WASTE 1-1/2"	TYPE NONE	HT + 0 "AFF	
P 8	16	HAND SINK W/SOAP & TOWEL DISP			
		SUPPLY CW 1/2"	HW 1/2"	HT + 22 "AFF	
		DIRECT WASTE 1-1/2"	TYPE NONE	HT + 20 "AFF	
P 9		FLOOR SINK	Drains from item #19 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE (3) 2"	TYPE FS	HT + 0 "AFF	
P 10	19	THREE COMPARTMENT POT SINK	Drains to P9 Two (2) rough-in location required.		
		SUPPLY CW 3/4"	HW 3/4"	HT + 14 "AFF	
		INDIRECT WASTE (3) 2"	TYPE NONE	HT + 0 "AFF	
P 11		FLOOR SINK	Drains from items #22 & #28 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE 2", 1/2"	TYPE FS	HT + 0 "AFF	
P 12	22	DISH MACHINE W/BOOSTER	Drains to P11		
		SUPPLY CW	HW 3/4"	HT + 8 "AFF	
		INDIRECT WASTE 2"	TYPE NONE	HT + 0 "AFF	
P 13		SPARE NUMBER			
P 14		SPARE NUMBER			
P 15	25	GARBAGE DISPOSAL, 2 HP	Plumber to BTC CW from Item #27 (Pre-Rinse Assembly)		
		SUPPLY CW 1/2"	HW	HT + 0 "AFF	
		DIRECT WASTE 2"	TYPE NONE	HT + 10 "AFF	
P 15	27	PRE-RINSE UNIT	Plumber to BTC Through to Item #25		
		SUPPLY CW 1/2"	HW 1/2"	HT + 14 "AFF	
P 16	30 1	WATER FILTER	Plumber to BTC cold water through to Item #30		
		SUPPLY CW 1/2"	HW	HT + 94 "AFF	
P,17		FLOOR SINK	Drains from items #29 & #30 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE 1", 3/4"	TYPE FS	HT + 0 "AFF	
P 18	35	SINGLE AIRPOT COFFEE BREWER	BTC from water filter Exposed piping Chrome		
		SUPPLY CW 1/2"	HW	HT + 60 "AFF	
P 19	36	ICE TEA BREWER	BTC from water filter Exposed piping Chrome		
		SUPPLY CW 1/2"	HW	HT + 60 "AFF	
P 20	37	COFFEE URN	BTC from water filter Exposed piping Chrome		
		SUPPLY CW 1/2"	HW	HT + 60 "AFF	
P 21		FLOOR SINK	Drains from items #31 #39, & #40 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE (3)1/2", 1-1/2"	TYPE FS	HT + 0 "AFF	
P 22	40	S/S BUILT-IN HAND SINK	Drains to P21 Plumber to BTC cold water to water stationn (item #39)		
		SUPPLY CW 1/2"	HW 1/2"	HT + 14 "AFF	
		INDIRECT WASTE 1-1/2"	TYPE NONE	HT + 0 "AFF	
P 100		AREA FLOOR DRAINS	See Mechanical Plans for fixture specifications.		
P 101	101	ICE & BEVERAGE DISPENSER	Drains to P102 Do not tie drains together Plumber to stub cold water up floor for flus stem.		
		SUPPLY CW 1/2"	HW	HT + 12 "AFF	
		INDIRECT WASTE 1", 3/4"	TYPE NONE	HT + 0 "AFF	
P 102		FLOOR SINK	Drains from stem #100 & #101 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE 1", 3/4", 1/2"	TYPE FS	HT + 0 "AFF	
P 103		SPARE NUMBER			
P 104		FLOOR SINK	Drains from stems #113 & #115 Provide w/ 3/4 section grate Install flush or just below finshed floor		
		INDIRECT WASTE 1", 2"	TYPE FS	HT + 0 "AFF	
P 105	112	THREE COMPARTMENT POT SINK	Drains to P106 Two (2) rough-in locations required.		
		SUPPLY CW 3/4"	HW 3/4"	HT + 14 "AFF	
		INDIRECT WASTE (3) 2"	TYPE NONE	HT + 0 "AFF	
P 106		FLOOR SINK	Drains from stem #112 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE (3) 2"	TYPE FS	HT + 0 "AFF	
P 107	115	DISH MACHINE W/BOOSTER	Drains to P104 140 degree F maximum hot water connection.		
		SUPPLY CW	HW 3/4"	HT + 8 "AFF	
		DIRECT WASTE 2"	TYPE NONE	HT + 0 "AFF	

KEY	ITEM	DESCRIPTION			
P 108	116	GARBAGE DISPOSAL, 2 HP	Plumber to BTC CW from Item #116 1 (Pre Rinse Assembly)		
		SUPPLY CW 1/2"	HW	HT + 0 "AFF	
		DIRECT WASTE 2"	TYPE NONE	HT + 10 "AFF	
P 108	116 1	PRE-RINSE UNIT	Plumber to BTC CW to Item #116 (Garbage Disposer)		
		SUPPLY CW 1/2"	HW 1/2"	HT + 14 "AFF	
P 109	117	HAND SINK W/SOAP & TOWEL DISP			
		SUPPLY CW 1/2"	HW 1/2"	HT + 22 "AFF	
		DIRECT WASTE 1-1/2"	TYPE NONE	HT + 20 "AFF	
P 110		FLOOR SINK	Drains from item #121 Provide w/ 3/4 section grate Install flush or just below finished floor.		
		INDIRECT WASTE (2) 1-1/2"	TYPE FS	HT + 0 "AFF	
P 111	121	S/S PREP TABLE W/SINK	Drains to P110		
		SUPPLY CW 1/2"	HW 1/2"	HT + 14 "AFF	
		INDIRECT WASTE (2) 1-1/2"	TYPE NONE	HT + 0 "AFF	
P 112		OPEN SITE DRAIN	Drains from stems #126 1 & #127 1		
		INDIRECT WASTE (2) 1/2"	TYPE OSD	HT + 2 "AFF	
P 113	126.2	COMPRESSOR UNIT	Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower).		
		SUPPLY CW 1/2"	HW	HT + 0 "AFF	
P 114	127.2	COMPRESSOR UNIT	Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower)		
		SUPPLY CW 1/2"	HW	HT + 0 "AFF	
P 115	130	HAND SINK W/SOAP & TOWEL DISP			
		SUPPLY CW 1/2"	HW 1/2"	HT + 22 "AFF	
		DIRECT WASTE 1-1/2"	TYPE NONE	HT + 20 "AFF	
P 116	137	SPREADER PLATE CABINET			
		NATURAL GAS 1-1/4"	BTU 190,000	HT + 24 "AFF	
		GAS NOTE	Plumber to BTC thru gas quick disconnect kit (by KEC). Plumber to BTC to the following Hot Top/Two Burner Range (#138) - 130,000 BTU's Char Broiler (#139) - 60 000 BTU's		
P 117	141	HEAVY DUTY GAS FRYER			
		NATURAL GAS 1"	BTU 80,000	HT + 24 "AFF	
		GAS NOTE	Plumber to BTC thru gas quick disconnect kit (by KEC)		
P 118		FLOOR SINK	Drains from items #146 & #147 Provide w/ 3/4 section grate Install flush or just below finished floor		
		INDIRECT WASTE 1", 3/4"	TYPE FS	HT + 0 "AFF	
P 119	147 1	WATER FILTER	Plumber to BTC cold water through to Item #147		
		SUPPLY CW 1/2"	HW	HT + 96 "AFF	
P 120		OPEN SITE DRAIN	Drains from item #155		
		INDIRECT WASTE 1/2"	TYPE OSD	HT + 2 "AFF	
P 121	155	S/S WORK COUNTER	Plumber to connect to dipperwell, Item #148 1 Drains to P120		
		SUPPLY CW 1/2"	HW	HT + 18 "AFF	
		INDIRECT WASTE 1/2"	TYPE NONE	HT + 0 "AFF	
P 122	149	TWIN AIRPOT BREWER W/FAUCET			
		SUPPLY CW 1/2"	HW	HT + 48 "AFF	
P 123		OPEN SITE DRAIN	Drains from item #136		
		INDIRECT WASTE. (3) 1/2"	TYPE OSD	HT + 2 "AFF	
P 124	145	FLOOR TROUGH			
		DIRECT WASTE 3"	TYPE NONE	HT + -6 "AFF	
P 125	150	ICE TEA BREWER			
		SUPPLY CW 1/2"	HW	HT + 48 "AFF	
P 126		FLOOR SINK	Drains from stems #164 Provide w/ 3/4 section grate. Install flush or just below finished floor		
		INDIRECT WASTE 1-1/2"	TYPE FS	HT + 0 "AFF	
P 127	136 1	COMPRESSOR UNIT	Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower)		
		SUPPLY CW 1/2"	HW	HT + 0 "AFF	
P 128	136 2	COMPRESSOR UNIT	Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower)		
		SUPPLY CW 1/2"	HW	HT + 0 "AFF	
P 129	172	HEAVY DUTY GAS RANGE			
		NATURAL GAS 1"	BTU 215,000	HT + 24 "AFF	
		GAS NOTE	Plumber to BTC thru gas quick disconnect kit (by KEC)		
P 130		OPEN SITE DRAIN	Drains from item #176 Note steam temperature resistant pipe		
		INDIRECT WASTE 2"	TYPE OSD	HT + 2 "AFF	
P 131	176 1	KLEENSTEAM SYSTEM	Plumber to BTC thru to Item #176 (Combi Oven) Plumber to completly install Filter as provided by the KEC.		
		SUPPLY CW 1/2"	HW	HT + 96 "AFF	
P 132	154	S/S BUILT-IN HAND SINK			
		SUPPLY CW 1/2"	HW 1/2"	HT + 20 "AFF	
		DIRECT WASTE 1-1/2"	TYPE NONE	HT + 18 "AFF	

WILLIAM J. CLINTON PRESIDENTIAL CENTER

LITTLE ROCK, ARKANSAS

Architect

POLSHEK PARTNERSHIP LLP
320 West 13th Street
New York, New York 10014
212 807 7171

Coordinating Architects

POLK STANLEY YEARY ARCHITECTS
700 South Schiller Street
Little Rock, Arkansas 72201
501 378 0878

WITSELL EVANS & RASCO
901 West Third Street
Little Rock, Arkansas 72201
501 374 5300

WOODS CARADINE ARCHITECTS
2200 South Main Street
Little Rock, Arkansas 72206
501 374 4060

Landscape Architects

HARGREAVES ASSOCIATES
118 Magazine Street
Cambridge, Massachusettes 02139
617 661 0070

LANDSCAPE ARCHITECTURE, Inc.
2300 Cottondale Lane, Suite 202
Little Rock Arkansas 72202
501 374 5810

Structural Engineer

LESLIE E ROBERTSON ASSOC , RLLP
30 Broad Street, 47th Floor
New York, New York 10004
212 750.9000

MEP Engineers

FLACK + KURTZ Inc.
475 Fifth Avenue
New York, New York 10017
212 532 9600

CROMWELL ARCHITECTS ENGINEERS
101 South Spring Street
Little Rock, Arkansas 72201
501 372 2900

FoodService Consultants

NEXT STEP DESIGN, INC
1116 West Street, Suite C
Annapolis, Maryland 21401
410 263 1200

Seal

Issue	Date
100% Construction Docs	9/27/02
90% Progress Printing	8/30/02
100% Construction	6/14/02
100% DD	2/28/02



Job No 9908

Scale -

Date SEPTEMBER 27, 2002

Title FOOD SERVICE PLUMBING SCHEDULE

Sheet No FS-P2.1

FOR OFFICIAL USE ONLY