

1 UPPER LEVEL MUSEUM KITCHEN PLAN
 P103b P202 1/8" = 1'-0"

PLUMBING ROUGH-IN SCHEDULE (TYPICAL FOR DWGS P201 AND P202)

<p>P1 AREA FLOOR DRAINS See Mechanical Plans for fixture specifications</p> <p>P2 DOUBLE DECK CONVECTION OVEN Plumber to supply disconnect. NATURAL GAS (2) 3/4" BTU 120,000 HT + 0 *AFF GAS NOTE Two (2) gas rough-in locations required @+24" A F F & @+48" A F F Plumber to BTC thru gas quick disconnect kit (by KEC)</p> <p>P3 SPARE NUMBER</p> <p>P4 SPARE NUMBER</p> <p>P5 GRIDDLE/OPEN BURNER RANGE NATURAL GAS 1-1/4" BTU 130,000 HT + 24 *AFF GAS NOTE Plumber to BTC thru gas quick disconnect kit (by KEC)</p> <p>P6 FLOOR SINK Drains from item #15 INDIRECT WASTE 1-1/2" TYPE FS HT + 0 *AFF</p> <p>P7 S/S WORK TABLE W/SINK Drains to P6 Plumber to bring hot & cold water down from ceiling via S/S chase integral with this item SUPPLY CW 1/2" HW 1/2" HT + 102 *AFF INDIRECT WASTE 1-1/2" TYPE NONE HT + 0 *AFF</p> <p>P8 HAND SINK W/SOAP & TOWEL DISP SUPPLY CW 1/2" HW 1/2" HT + 22 *AFF DIRECT WASTE 1-1/2" TYPE NONE HT + 20 *AFF</p> <p>P9 FLOOR SINK Drains from item #19 INDIRECT WASTE (3) 2" TYPE FS HT + 0 *AFF</p> <p>P10 THREE COMPARTMENT POT SINK Drains to P9 Two (2) rough-in location required SUPPLY CW 3/4" HW 3/4" HT + 14 *AFF INDIRECT WASTE (3) 2" TYPE NONE HT + 0 *AFF</p> <p>P11 FLOOR SINK Drains from items #22 & #28 INDIRECT WASTE 2", 1/2" TYPE FS HT + 0 *AFF</p> <p>P12 DISH MACHINE W/BOOSTER Drains to P11 SUPPLY HW 3/4" HT + 8 *AFF INDIRECT WASTE 2" TYPE NONE HT + 0 *AFF</p> <p>P13 SPARE NUMBER</p> <p>P14 SPARE NUMBER</p> <p>P15 GARBAGE DISPOSAL, 2 HP Plumber to BTC CW from Item #27 (Pre-Rinse Assembly) SUPPLY CW 1/2" HT + 0 *AFF DIRECT WASTE 2" TYPE NONE HT + 10 *AFF</p> <p>P15 PRE-RINSE UNIT Plumber to BTC Through to Item #25 SUPPLY CW 1/2" HW 1/2" HT + 14 *AFF</p>	<p>P16 WATER FILTER Plumber to BTC cold water through to Item #30 SUPPLY CW 1/2" HT + 94 *AFF</p> <p>P17 FLOOR SINK Drains from items #29 & #30 INDIRECT WASTE 1", 3/4" TYPE FS HT + 0 *AFF</p> <p>P18 SINGLE AIRPOT COFFEE BREWER SUPPLY CW 1/2" HT + 48 *AFF</p> <p>P19 ICE TEA BREWER SUPPLY CW 1/2" HT + 48 *AFF</p> <p>P20 COFFEE URN SUPPLY CW 1/2" HT + 48 *AFF</p> <p>P21 FLOOR SINK Drains from items #31, #39, & #40 INDIRECT WASTE (3) 1/2", 1-1/2" TYPE FS HT + 0 *AFF</p> <p>P22 S/S BUILT-IN HAND SINK Drains to P21 Plumber to BTC cold water to water station (item #38) SUPPLY CW 1/2" HW 1/2" HT + 14 *AFF INDIRECT WASTE 1-1/2"</p> <p>P100 AREA FLOOR DRAINS See Mechanical Plans for fixture specifications</p> <p>P101 ICE & BEVERAGE DISPENSER</p> <p>P101f Drains to P102 Plumber to stub cold water up floor for this item SUPPLY CW 1/2" HT + 12 *AFF INDIRECT WASTE 1", 3/4" HT + 0 *AFF</p> <p>P102 FLOOR SINK Drains from item #100 & #101 INDIRECT WASTE 1", 3/4", 1/2" TYPE FS HT + 0 *AFF</p> <p>P103 SPARE NUMBER</p> <p>P104 FLOOR SINK Drains from items #113 & #115 INDIRECT WASTE 1", 2" TYPE FS HT + 0 *AFF</p> <p>P105 THREE COMPARTMENT POT SINK P112 Drains to P106 Two (2) rough-in locations required SUPPLY CW 3/4" HW 3/4" HT + 14 *AFF INDIRECT WASTE (3) 2" TYPE NONE HT + 0 *AFF</p> <p>P106 FLOOR SINK Drains from item #112 INDIRECT WASTE (3) 2" TYPE FS HT + 0 *AFF</p> <p>P107 DISH MACHINE W/BOOSTER P115 Drains to P104 140 degree F minimum hot water connection SUPPLY HW 3/4" HT + 8 *AFF DIRECT WASTE 2" TYPE NONE HT + 0 *AFF</p>	<p>P108 GARBAGE DISPOSAL, 2 HP Plumber to BTC CW from Item #116 1 (Pre-Rinse Assembly) SUPPLY CW 1/2" HT + 0 *AFF DIRECT WASTE 2" TYPE NONE HT + 10 *AFF</p> <p>P108 PRE-RINSE UNIT 116 Plumber to BTC CW to Item #116 (Garbage Disposer) SUPPLY CW 1/2" HT + 14 *AFF</p> <p>P109 HAND SINK W/SOAP & TOWEL DISP SUPPLY CW 1/2" HW 1/2" HT + 22 *AFF DIRECT WASTE 1-1/2" TYPE NONE HT + 20 *AFF</p> <p>P110 FLOOR SINK Drains from item #121 Provide w/ 3/4" section grate Install flush or just below finished floor INDIRECT WASTE (2) 1-1/2" TYPE FS HT + 0 *AFF</p> <p>P111 S/S PREP TABLE W/SINK 121 Drains to P110 SUPPLY CW 1/2" HW 1/2" HT + 14 *AFF INDIRECT WASTE (2) 1-1/2" TYPE NONE HT + 0 *AFF</p> <p>P112 OPEN SITE DRAIN Drains from items #126 1 & #127 1 INDIRECT WASTE (2) 1/2" TYPE OSD HT + 2 *AFF</p> <p>P113 COMPRESSOR UNIT 126 Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower) SUPPLY CW 1/2" HW HT + 0 *AFF</p> <p>P114 COMPRESSOR UNIT 127 Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower) SUPPLY CW 1/2" HW HT + 0 *AFF</p> <p>P115 HAND SINK W/SOAP & TOWEL DISP SUPPLY CW 1/2" HW 1/2" HT + 22 *AFF DIRECT WASTE 1-1/2" TYPE NONE HT + 20 *AFF</p> <p>P116 SPREADER PLATE CABINET NATURAL GAS 1-1/4" BTU 190,000 HT + 24 *AFF GAS NOTE Plumber to BTC thru gas quick disconnect kit (by KEC) Plumber to BTC to the following Hot Top/Two Burner Range (#138) 130,000 BTU's Char Broiler (#139) - 60,000 BTU's</p> <p>P117 HEAVY DUTY GAS FRYER NATURAL GAS 1" BTU 80,000 HT + 24 *AFF GAS NOTE Plumber to BTC thru gas quick disconnect kit (by KEC)</p> <p>P118 FLOOR SINK Drains from items #146 & #147 INDIRECT WASTE 1", 3/4" TYPE FS HT + 0 *AFF</p> <p>P119 WATER FILTER 147 Plumber to BTC cold water through to item #147 SUPPLY CW 1/2" HT + 96 *AFF</p> <p>P120 OPEN SITE DRAIN Drains from item #155 INDIRECT WASTE 1/2" TYPE OSD HT + 2 *AFF</p> <p>P121 S/S WORK TABLE 155 Plumber to connect to dipperwell Drains to P120</p>	<p>1/2" SUPPLY CW HW HT + 18 *AFF INDIRECT WASTE 1/2" TYPE NONE HT + 0 *AFF</p> <p>P122 TWIN AIRPOT BREWER w/FAUCET 149 SUPPLY CW 1/2" HT + 48 *AFF</p> <p>P123 OPEN SITE DRAIN Drains from item #136 INDIRECT WASTE (3) 1/2" TYPE OSD HT + 2 *AFF</p> <p>P124 FLOOR TROUGH DIRECT WASTE 3" TYPE NONE HT + 16 *AFF</p> <p>P125 ICE TEA BREWER SUPPLY CW 1/2" HT + 48 *AFF</p> <p>P126 FLOOR SINK Drains from items #160 & #161 INDIRECT WASTE (4) 1-1/2" TYPE FS HT + 0 *AFF</p> <p>P127 COMPRESSOR UNIT 136 1 Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower) SUPPLY CW 1/2" HT + 0 *AFF</p> <p>P128 COMPRESSOR UNIT 136 2 P Plumber to verify exact location of compressor * 1/2" condenser water supply and return connections required (from building cooling tower) SUPPLY CW 1/2" HT + 0 *AFF</p> <p>P129 HEAVY DUTY GAS RANGE NATURAL GAS 1" BTU 215,000 HT + 24 *AFF GAS NOTE Plumber to BTC thru gas quick disconnect kit (by KEC)</p> <p>P130 OPEN SITE DRAIN Drains from item #176 INDIRECT WASTE 2" TYPE OSD HT + 2 *AFF</p> <p>P131 KLEENSTEAM SYSTEM 176 1 P Plumber to BTC thru to Item #176 (Comb Oven) Plumber to completely install Filter, as provided by the KEC SUPPLY CW 1/2" HT + 96 *AFF</p> <p>P132 S/S BUILT-IN HAND SINK P154 SUPPLY CW 1/2" HW 1/2" HT + 20 *AFF DIRECT WASTE 1-1/2" TYPE NONE HT + 18 *AFF</p>
---	---	---	--

KITCHEN EQUIPMENT PLUMBING GENERAL NOTES (TYPICAL FOR DWGS P201 AND P202)

- 1 PLUMBING CONTRACTOR TO PROVIDE FINAL CONNECTIONS TO ALL KITCHEN EQUIPMENT ITEMS PER LOCAL, STATE AND NATIONAL PLUMBING CODES
- 2 PLUMBING CONTRACTOR TO VERIFY REQUIREMENTS OF ALL KITCHEN EQUIPMENT ITEMS PROVIDED BY OTHERS BEFORE ROUGHING IN AND MAKING FINAL CONNECTIONS
- 3 PLUMBING CONTRACTOR TO FURNISH AND INSTALL ALL SHUT-OFF VALVES, SHOCK ABSORBERS, SNAP ACTION VALVES, TRIM, TRAPS, ETC REQUIRED FOR FINAL CONNECTION TO OUTLETS
- 4 PLUMBING CONTRACTOR TO FURNISH, INSTALL AND CONNECT ALL WATER, DRAIN, INDIRECT DRAIN LINES, ETC FOR ALL KITCHEN EQUIPMENT
- 5 PLUMBING CONTRACTOR TO FLUSH ALL LINES BEFORE MAKING FINAL CONNECTIONS
- 6 REFER TO FOODSERVICE PLANS FOR ROUGH-IN CONNECTIONS

WILLIAM J. CLINTON PRESIDENTIAL CENTER

LITTLE ROCK, ARKANSAS

Architect
 POLSHEK PARTNERSHIP LLP
 320 West 13th Street
 New York, New York 10014
 212.807.7171

Coordinating Architects
 POLK STANLEY YEARY ARCHITECTS Ltd
 700 South Schiller Street
 Little Rock, Arkansas 72201
 501.378.0878

WITSELL EVANS RASCO
 901 West Third Street
 Little Rock, Arkansas 72201
 501.374.5300

WOODS CARADINE ARCHITECTS
 2200 South Main Street
 Little Rock, Arkansas 72206
 501.374.4080

Landscape Architects
 HARGREAVES ASSOCIATES
 118 Magazine Street
 Cambridge, Massachusetts 02139
 617.861.0070

LANDSCAPE ARCHITECTURE, Inc.
 2300 Cottondale Lane Suite 202
 Little Rock, Arkansas 72202
 501.374.5610

Structural Engineer
 LESLIE E. ROBERTSON ASSOC. R.L.P.
 30 Broad Street, 4th Floor
 New York, New York 10004
 212.750.9000

MEP Engineers
 FLACK + KURTZ Inc
 475 Fifth Avenue
 New York, New York 10017
 212.532.9600


CROMMELL ARCHITECTS ENGINEERS
 101 South Spring Street
 Little Rock, Arkansas 72201
 501.372.2900

Curtainwall Consultant
 R. A. HEINTGES ARCHITECTS
 126 Fifth Avenue, 9th Floor
 New York, New York 10011
 212.652.2966

100% PLUMBING CONSTRUCTION DRAWINGS ISSUE - JULY 1, 2002



100% Construction Documents	09/27/02
90% Progress Printing	09/30/02
Plumbing Contract Documents	07/01/02
Issue	Date



Job No POLSHEK & PARTNERS ARCH 0908
 CROMMELL AE 99-114


Scale

Date JULY 01, 2002

Title **ENLARGED MUSEUM LOWER LEVEL KITCHEN PLAN and ROUGH-IN NOTES**

Sheet No

P202



FOR OFFICIAL USE ONLY