



EQUIPMENT LIST			
ITEM NO	QTY	EQUIPMENT CATEGORY	EQUIPMENT REMARKS
01	2	HAND SINK	WALL BACKING REQUIRED BY G.C. *
02	1	ICE MAKER W/ BIN	
03	1	REACH-IN FREEZER	
04	1	CHARBROILER W/ CABINET BASE	
05	1	WORK TABLE W/ SHELVES	WALL BACKING REQUIRED BY G.C. *
06	1	UNDERCOUNTER DISHWASHER	BELOW DRAINBOARD
07	1	3 COMP'T SINK W/SHELVES & POT RACK	WALL BACKING REQUIRED BY G.C. *
08	1	UTILITY CART	NOT SHOWN
09	1	VENT HOOD W/ FIRE SUPPRESSION	
10	1	RANGE ON CONVECTION OVEN BASE	
11	1	WORK TOP REFRIG. W/ SHELVES	WALL BACKING REQUIRED BY G.C. *
12	2	MOBILE PAN RACK	
13	1	CONVEYOR OVEN	VERIFY CLEARANCE REQUIREMENT
14	2	MOBILE TABLE	
15	1	GRIDDLE ON CONVECTION OVEN BASE	
16	1	FRYER	
17	1	WORK TABLE	
18	1	STAINLESS STEEL SHELF UNIT	
19	5	STORAGE SHELVING	2 UNITS WITH CASTERS
20	1	COOLER SHELVING PACKAGE	
21	1	WALK-IN COOLER	
22	1	VENTLESS GRIDDLE/FRYER	
23	1	SANDWICH PREP UNIT W/ OVERSHELVES	WALL BACKING REQUIRED BY G.C. *
24	1	WORK COUNTER	
25	1	UNDERCOUNTER REFRIGERATOR	
26	1	PANINNI GRIDDLE	
27	2	PORTABLE FOOD WELL	
28	1	GRAB & GO DISPLAY	
29	1	CASH REGISTER	BY OTHERS
30	1	PHONE	BY OTHERS
31	1	FRONT COUNTER	
32	1	HEATED CABINET	
33	1	UNDERCOUNTER FREEZER	
34	1	BEVERAGE COUNTER	
35	1	ICE/BEVERAGE DISPENSER	
36	1	COFFEE BREWER(120/208)	W/ PORTABLE SATELLITES
37	1	TEA MAKER	W/ PORTABLE DISPENSERS
38	2	TRASH RECEPTACLE	VERIFY LOCATION WITH OWNER
39	1	DISPOSAL	
40	1	S/S DOOR TRIM	

* ALL WALL SHELVES TO BE TWO TIER --SEE BACKING DETAILS ON PAGE K4 FOR WALL MOUNTED ITEMS

GENERAL NOTES

- A- KITCHEN EQUIPMENT CONTRACTOR TO DELIVER AND SET IN PLACE ALL NEW EQUIPMENT. ALL ITEMS LABELED AS "EXISTING" OR "BY OTHERS" SHALL BE DELIVERED AND SET BY OTHERS.
- B- KITCHEN EQUIPMENT CONTRACTOR SHALL DELIVER WALK-INS, ERECT PANELS AS SHOWN, MOUNT ALL REFRIGERATION COMPONENTS, INSTALL REFRIGERATION LINES, CHARGE SYSTEM, AND MAKE SYSTEM READY FOR FINAL ELECTRICAL AND PLUMBING CONNECTIONS BY RESPECTIVE TRADES. ALL WIRING, CONTROL WIRING AND DRAINLINE HEATER BY ELECTRICAL, EVAPORATOR DRAINS BY PLUMBING
- C- VENT HOOD, FANS AND CURBS TO BE SUPPLIED BY KITCHEN CONTRACTOR. HANGING OF HOOD BY KITCHEN EQUIPMENT CONTRACTOR. DUCTWORK TO BE PROVIDED AND INSTALLED BY MECHANICAL.
- D- FANS & CURBS TO BE LOCATED AND INSTALLED BY MECHANICAL AND/OR GENERAL CONTRACTOR
- E- GENERAL CONTRACTOR TO PROVIDE ALL WALL BACKING NECESSARY FOR WALL MOUNTED ITEMS AND ALL WALL/ROOF/FLOOR PENETRATIONS REQUIRED. COORDINATE ON SITE.
- F- COORDINATE WITH OTHER TRADES WHEN LOCATING PERMANENT FIXTURES.
- G- DO NOT LOCATE HVAC DIFFUSERS NEAR VENT HOOD. IF NECESSARY, USE PERFORATED TYPE.
- H- KITCHEN EQUIPMENT CONTRACTOR NOT RESPONSIBLE FOR ANY ARCHITECTURAL DEVIATIONS FROM THIS PLAN

SCALE: 1/4" = 1'

SHEET TITLE:
*KITCHEN EQUIPMENT
 ARRANGEMENT PLAN*

HEIFER INTERNATIONAL
PHASE 2 BUILDING
LITTLE ROCK , AR

SHEET NO.
K1
 SHEET 1 OF 5
 PROJECT NO.
 HEIF01
 DATE
 03/13/08
 REVISION
 02/02/09



DRAWN BY: MT