



GARVER ENGINEERS

CROMWELL

101 SOUTH SPRING ST
LITTLE ROCK AR 72201
TELEPHONE 501-372-2900
FACSIMILE 501-372-0482

EXISTING METAL STUD & GYP BD WALL TO REMAIN.
PROVIDE NEW FINISHES PER SCHEDULE. WALL
EXTENDS TO APPROXIMATELY 6" ABOVE CEILING

EXISTING METAL STUD & GYP BD WALL TO REMAIN.
NEW METAL STUD CRIPPLE WALL WITH GYP BD
FINISH & SOUND INSULATION TO STRUCTURE ABOVE.
(APPROXIMATELY 3'-6" HIGH)

NEW METAL STUD & GYP BOARD WALL WITH
SOUND INSULATION FULL HEIGHT TO
STRUCTURE ABOVE.

EXISTING FIRE BARRIER TO REMAIN. FIRE
CAULK ALL PENETRATIONS.

INTERIOR ELEVATION KEY

GENERAL FLOOR PLAN NOTES:

A. CONTRACTOR SHALL REMOVE & REINSTALL EXISTING EMPLOYEE CARD SWIPE WHERE EXISTING DOOR FRAMES ARE REPLACED.

B. PROVIDE NEW HANDRAIL, CRASH RAIL & CORNER GUARDS AT LOCATIONS INDICATED ON DRAWING I-102. SEE FINISH SCHEDULE ON DRAWING A-601 FOR NEW FINISHES.

C. WHERE NEW WALLS ALIGNS WITH EXISTING WALLS CONTRACTOR SHALL PROVIDE STUD WIDTHS AS REQUIRED TO MATCH OVERALL EXISTING WALL THICKNESS SO THAT NEW FINISHES ALIGN FLUSH.

D. ROOM IDENTIFICATION SIGNS SHALL BE GOVERNMENT FURNISHED AND INSTALLED.

KEYED FLOOR PLAN NOTES:

1. TYPICAL SYMBOL FOR NEW WALL CONSTRUCTION OR OPENING INFILL. SEE WALL LEGEND FOR DESCRIPTION.
2. TYPICAL SYMBOL FOR EXISTING WALL CONSTRUCTION. CONTRACTOR SHALL REMOVE ALL FASTENERS, FILL HOLES & PREPARE SURFACE TO RECEIVE NEW FINISHES.
3. NEW RECESSED FIRE EXTINGUISHER CABINET & EXTINGUISHER.
4. NEW METAL FURRING & GYP BD OVER EXISTING GYP BD WALL. SEE WALL TYPES. LOCATE WALL SO THAT FINISHED FACE IS FLUSH WITH FINISHED FACE OF FURRED WALL OVER BRICK BEYOND.
5. NEW PLUMBING FIXTURE & ACCESSORIES. SEE PLUMBING PLANS.
6. NEW EMPLOYEE CARD SWIPE. RELEASES WHERE PANIC HARDWARE OCCURS. SEE DOOR SCHEDULE.
7. SEAL EXISTING WALL PENETRATIONS WHERE ABANDONED PIPE WAS REMOVED. SEE MECHANICAL PLAN.
8. NEW HOLLOW METAL FRAME & GLAZING.
9. NEW MILLWORK.
10. APPX. LOCATION OF RELOCATED HOT/COLD PACK RACK. PROVIDE WALL BACKING PER DETAIL 3/A-501. COORDINATE EXACT LOCATION IN FIELD WITH DEPT. HEAD.
11. ENCAPSULATE EXISTING LEAD BASED PAINT ON FLOOR & CURBS WITH NEW PAINT. SEE FINISH SCHEDULE FOR TYPE.
12. NEW METAL FURRING & GYP BOARD FINISH OVER EXISTING BRICK. SEE WALL TYPES. REFER TO DETAIL 12/A201 FOR TERMINATIONS AT OPENINGS.
13. FLOOR MOUNTED & OVERHEAD BRACKETED PLASTIC LAMINATE COMPARTMENTS.
14. RELOCATED MILLWORK.
15. RELOCATED ICE MACHINE.
16. GFGI HYDROCOALATOR EQUIPMENT.
17. "DUMMY" QUICK CONNECT, MEDICAL FACE PLATE.(AIR, OXY, VAC) SEE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION.
18. EXISTING METAL STAIR. PREPARE MATERIAL TO RECEIVE NEW PAINT. PAINT SAFETY YELLOW PER BASE STANDARDS.
19. NEW SURFACE MOUNTED WALL BRACKET & FIRE EXTINGUISHER.
20. NEW TUBE STEEL GUARDRAIL. SEE DETAIL 13/A201.

[illegible]

PROJECT TITLE
REPAIR & RENOVATE MEDICAL CLINIC PH IV
LITTLE ROCK AIR FORCE BASE
JACKSONVILLE ARKANSAS

100% CEMENT PILE

SHEET TITLE

FLOOR PLAN-AREA "B"

PHYSICAL THERAPY, EDUCATION & TRAINING

DRAWN BY P.JL	LEAD DESIGNER K. TAYLOR
TECH. REVIEWER P.JL	PROJECT NUMBER NKAK#06-8006-4
DESIGNED BY P. LEDFORD	SHEET
DATE JULY 1, 2008	A-102-A
SCALE AS NOTED	7 of 50

A-102-A

7 OF 50