



1 REFLECTED CEILING PLAN - AREA "B" - PHYSICAL THERAPY, EDUCATION & TRAINING  
1/8"=1'-0"

WALL LEGEND

- EXISTING METAL STUD & GYP BD WALL TO REMAIN. PROVIDE NEW FINISHES PER SCHEDULE. WALL EXTENDS TO APPROXIMATELY 6" ABOVE CEILING
- EXISTING METAL STUD & GYP BD WALL TO REMAIN. NEW METAL STUD CRIPPLE WALL WITH GYP BD FINISH & SOUND INSULATION TO STRUCTURE ABOVE. (APPROXIMATELY 3'-6" HIGH)
- NEW METAL STUD & GYP BOARD WALL WITH SOUND INSULATION FULL HEIGHT TO STRUCTURE ABOVE.
- NEW METAL STUD & GYP BOARD HALF WALL.
- EXISTING FULL HT SMOKE WALL TO REMAIN. ALL WALLS & OPENINGS SHALL BE SMOKE RESISTIVE. PATCH & SEAL ALL PENETRATIONS.
- SECURITY WALL PER DOD STANDARDS. NEW OR MODIFIED EXISTING WALL, PER WALL TYPES ABOVE, FULL HEIGHT TO STRUCTURE. ALL OPENINGS SHALL BE PROTECTED PER DOD STANDARDS.

CEILING LEGEND

- NEW 2 x 2 ACOUSTICAL TILE & METAL GRID
- NEW GYP. BD. CEILING
- NEW SUSPENDED ALUMINUM DECORATIVE GRID (8"x8" SQUARES) SEE DETAIL 2/A-101R SIMILAR FOR HANGER INFORMATION ONLY.
- EXISTING CEILING TO REMAIN
- LIGHT FIXTURE. SEE ELECTRICAL DRAWINGS
- MECHANICAL REGISTERS. SEE MECH DRAWINGS
- WALL TYPE KEY. SEE A-501.

KEYED REFLECTED CEILING PLAN NOTES:

- SEE FINISH SCHEDULE, DRAWING A-601, FOR CEILING HEIGHTS.
- PATCH HEAD AT OPENING.
- GYP BD FURR DOWN @ 7'-0" A.F.F. AT RECEPTION DESK. SEE 6/A501.
- GYP BD FURR DOWN @ 9'-0" A.F.F. AT CONFERENCE ROOM. SEE 6/A501.
- EXISTING CEILING TO REMAIN. PATCH AS REQUIRED WITH LIKE MATERIALS.
- RELOCATED SURFACE MOUNTED PROJECTION SCREEN & PROJECTOR SUPPORT.
- NEW RECESSED PROJECTOR SCREEN & RETRACTABLE PROJECTOR SUPPORT CENTERED ON WALL.
- NEW LOCKABLE, METAL, CEILING ACCESS PANEL. PAINT TO MATCH CEILING COLOR. SEE DETAIL 3/A-101R. MATCH SIZE OF EXISTING REMOVED @ RM F-124.
- GYP BD FURR DOWN. MATCH HEIGHT OF ADJACENT CORRIDOR CEILING. SEE DETAIL 6/A501 SIM.
- NEW PREFINISHED ALUMN ROOF HATCH WITH INTEGRAL CURB & PAD LOCK HASP. INFILL EXISTING OPENING AS REQUIRED WITH LIKE MATERIALS.
- SUSPENDED DECORATIVE ALUMINUM GRID @ 8'-0" A.F.F.
- SURFACE MOUNTED ALUMINUM TRACK FOR SIDE FOLDING SECURITY DOOR. INSTALL PER MANUFACTURERS RECOMMENDATIONS.
- PROVIDE GYP BD HEAD, FLUSH WITH CEILING, WHERE EXISTING DOOR FRAME WAS REMOVED.
- CONTINUOUS GYP BD DRAPERY POCKET. SEE DETAIL 7/A501.
- CONTRACTOR SHALL RE-INSTALL EXISTING, HEAD MOUNTED, VERTICAL BLINDS IN NEW DRAPERY POCKET. OMIT EXISTING BLIND VALANCE & TURN OVER TO GOVERNMENT.
- NEW SURFACE MOUNTED, CLEAR ANODIZED 6063-T5 ALUMINUM, CURTAIN TRACK WITH NYLON WHEELED CARRIERS. PROVIDE "GENERAL CUBICLE" MODEL #1062N OR EQUAL. ATTACH TO CEILING GRID WITH #8 PAN HEAD SCREWS @ EACH END AND @ 24" O.C. SEE FINISH SCHEDULE NOTES FOR CURTAIN INFORMATION.



LITTLE ROCK A.F.B.  
ARKANSAS

**GARVER ENGINEERS**

1010 BATTERY STREET  
LITTLE ROCK, ARKANSAS 72202  
www.garverengineers.com  
(501) 376-3633

**CROMWELL**  
ARCHITECTS ENGINEERS

101 SOUTH SPRING ST  
LITTLE ROCK, AR 72201  
TELEPHONE 501-372-2900  
FACSIMILE 501-372-0482

No.	Revision/Issue	Date	By	App'd

PROJECT TITLE  
REPAIR & RENOVATE MEDICAL CLINIC PH IV  
LITTLE ROCK AIR FORCE BASE  
JACKSONVILLE, ARKANSAS

100% SUBMITTAL

SHEET TITLE  
**REFLECTED CEILING PLAN -  
AREA "B"**

PHYSICAL THERAPY, EDUCATION & TRAINING

DRAWN BY <b>PJL</b>	LEAD DESIGNER <b>K. TAYLOR</b>
TECH. REVIEWER <b>PJL</b>	PROJECT NUMBER <b>NKAK#06-8006-4</b>
DESIGNED BY <b>P. LEDFORD</b>	SHEET <b>A-102-R</b>
DATE JULY 1, 2008	
SCALE AS NOTED	8 OF 50