



LITTLE ROCK A.F.B.
ARKANSAS

DEMOLITION LEGEND

- EXISTING WALLS/PARTITIONS TO REMAIN
- EXISTING WALLS/PARTITIONS BEING REMOVED
- EXISTING LIGHT FIXTURES TO BE REMOVED
- EXISTING LIGHT FIXTURES TO BE REMOVED
- EXISTING LIGHT FIXTURES TO REMAIN
- EXIT LIGHT TO BE REMOVED

DRAWING NOTES:

- REMOVE ALL EXISTING LIGHT FIXTURES AT LOCATIONS SHOWN ON PLAN. SELECT FIXTURES MAY BE TEMPORARILY RETAINED FOR CONSTRUCTION LIGHTING, WITH TEMPORARY SUPPORTS ADDED (CEILING GRID IS BEING REMOVED).
- REMOVE FIXTURE "WHIPS" BACK TO FIRST JUNCTION BOX. RETAIN HOME RUN WIRING IN CONDUIT FOR CONNECTION TO NEW FIXTURES BEING INSTALLED.
- RETAIN EXISTING SWITCH BOXES AND WIRING IN THE WALLS/PARTITIONS NOT BEING REMOVED, EXCEPT AS OTHERWISE NOTED ON PLAN. REMOVE SWITCH AND ASSOCIATED WIRING AND CONDUIT BACK TO FIRST JUNCTION BOX IN THE WALLS/PARTITIONS THAT ARE BEING REMOVED.

PROJECT TITLE
REPAIR MEDICAL CENTER PH 3
LITTLE ROCK AFB, ARKANSAS

SHEET TITLE
LIGHTING DEMOLITION PLAN

DRAWN BY RJR	LEAD DESIGNER AM
TECH REVIEWER KF	PROJECT NUMBER NKAK 06-8001
DESIGNED BY KF	SHEET E0.11
DATE 8-11-06	SCALE 1/8"=1'-0"
	29 OF 37

1 LIGHTING DEMOLITION PLAN
SCALE: 1/8" = 1'-0"

