

SYMBOLS LEGEND

DOOR SCHEDULE

DOOR NUMBER PER SCHEDULE, SEE DOOR SCHEDULE & ELEVATIONS

WINDOW SCHEDULE

WINDOW PER ELEVATIONS

DRAWING TITLE SYMBOL

DETAIL NUMBER

SCALE

SHEET NUMBER WHERE DRAWN

SHEET NUMBER WHERE CUT (IF APPLICABLE)

BUILDING / INTERIOR ELEVATION SYMBOL

ELEVATION NUMBER

SHEET NUMBER WHERE DRAWN

SHEET NUMBER WHERE CUT

BUILDING / WALL SECTION SYMBOL

SECTION NUMBER

SHEET NUMBER WHERE DRAWN

SHEET NUMBER WHERE CUT

DETAIL SYMBOL

DETAIL NUMBER

DIRECTION DETAIL CUT

SHEET NUMBER WHERE DRAWN

SHEET NUMBER WHERE CUT

DETAIL NUMBER

SHEET DRAWN ON

SHEET CUT ON

AREA DETAILED

MATCH LINE

MATCH LINE

ROOM NUMBER SYMBOL

ROOM NUMBER ON PLAN

REVISION INDICATION

REVISION NO.

GENERAL AREA OR DETAIL INCLUDED ON LATEST REVISION

PLAN INDICATIONS

METAL STUD PARTITION

CONCRETE MASONRY UNIT (CMU)

CONCRETE

PARTITION TYPE SEE PARTITION SCHEDULE A602

SECTION INDICATIONS

EARTH

CONCRETE

GRAVEL

CONCRETE MASONRY UNIT (CMU)

BRICK

CERAMIC TILE

ACOUSTICAL TILE

WOOD, ROUGH CARPENTRY

WOOD, FINISH CARPENTRY

WOOD, BLOCKING

PLYWOOD, SMALL SCALE

METAL, LARGE SCALE

GYPSUM BOARD (GWB)

BATT INSULATION

RIGID INSULATION

CODE STUDY

GOVERNING CODES: 2003 IBC, 2002 AFPC- NFPA 101, SEISMIC CATAGORY "D", UFC 4-510-01(MHDBK 1191)

OCCUPANCY TYPE: "B" BUSINESS (EXISTING BUILDING)

CONSTRUCTION TYPE: II-B FULLY SPRINKLED

AREA OF RENOVATION: 6,975 SF @ SECOND FLOOR

OCCUPANT LOAD RENOVATION AREA: 70 MAX

NUMBER OF EXITS REQUIRED: 2 PROVIDED: 2

MAX EXIT TRAVEL DISTANCE: 200' COMMON PATH: 75'

FIRE RESISTIVE RATING FOR BLDG ELEMENTS: 0 HR. STORAGE/JANITOR < 100 SF: 0 HR

GENERAL NOTES

- A. CONTRACTOR SHALL SCHEDULE ALL UTILITY SHUT DOWNS WITH FACILITY MANAGER. NOTICE SHALL BE GIVEN TO THE CONTRACTING OFFICER AS SPECIFIED IN THE PROJECT MANUAL.
- B. A PHASING PLAN IS NOT REQUIRED. ENTIRE AREA OF RENOVATION SHALL BE TURNED OVER TO THE CONTRACTOR PRIOR TO CONSTRUCTION.
- C. CONTRACTOR SHALL CONSTRUCT FULL HEIGHT DUST PARTITIONS PRIOR TO START OF CONSTRUCTION TO PREVENT THE PASSAGE OF AIR BORNE MATERIALS. CONTRACTOR SHALL SUBMIT A DUST PARTITION LAYOUT TO THE CONTRACTING OFFICER FOR APPROVAL. CONTRACTOR SHALL PROVIDE TEMPORARY EXIT SIGNS & LIGHTS AS REQUIRED TO MAINTAIN EXISTING EXITS.
- D. LEAD BASED PAINTS ARE PRESENT IN THE AREA OF CONSTRUCTION. LEAD BASED PAINT ABATEMENT IS IN THE SCOPE OF WORK & THE CONTRACTORS RESPONSIBILITY. CONTRACTOR SHALL REVIEW THE PROJECT MANUAL & LIMITED LEAD BASED PAINT INSPECTION REPORT FOR SPECIFIC REQUIREMENTS PRIOR TO SUBMITTING A BID.
- E. ASBESTOS CONTAINING MATERIALS IN AREA OF CONSTRUCTION SHALL BE REMOVED BY THE GOVERNMENT UNDER SEPARATE CONTRACT PRIOR TO START OF CONSTRUCTION. A LIMITED ASBESTOS INSPECTION REPORT IS PROVIDED IN THE PROJECT MANUAL.

