





Mark	Description	Date	Appr.	Mark	Description	Date	Appr.

Contract No.	DMC01-03-R-0021
Contract Price	11
Submitted By:	Atkins
Reviewed By:	Atkins
Design By:	Atkins
Drawn By:	Atkins
Contract Date:	02/04/03
File Name:	193003X-000
Dwg. Code:	


 DEPARTMENT OF THE ARMY
 U.S. ARMY CORPS OF ENGINEERS
 LITTLE ROCK DISTRICT
 LITTLE ROCK, ARKANSAS
 Submitted By: 
 Reviewed By: 
 Design By: 
 Drawn By: 
 Contract Date: 02/04/03
 File Name: 193003X-000
 Dwg. Code:
 Contract No.: DMC01-03-R-0021
 Contract Price: 11

ADAL C-130U AIRCRAFT FUSELAGE TRAINER
 LRAFB, LITTLE ROCK AR
 Project No. WMAK 043005
 EROSION CONTROL PLAN

Sheet Reference Number:
C-202
 Sheet 9 of 91



SCALE: 1:500

Erosion Control Symbols

	Hay Bale
	Silt Fence

Symbol Legend

Existing	Proposed
	Sign
	Area Inlet
	Water Meter
	Fire Hydrant
	Gate Valve
	Telephone Riser
	Telephone Pole
	Power Pole
	Light Pole
	Bollard
	Removable Bollard

Linework Legend

	Building Footprints
	Electrical, Lighting
	Fire Protection Water Line
	Natural Gas
	Potable Water Lines
	Storm Drains
	Roof Drain
	Sidewalks
	Sanitary Sewer
	Curb & Gutter
	Force Protection Line
	Parking Stripe
	Concrete Drive
	Contours

- NOTES:
1. THE LOCATIONS OF EROSION CONTROL DEVICES SHOWN ARE SCHEMATIC. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COMPLY WITH LOCAL, STATE AND FEDERAL REGULATIONS REGARDING EROSION CONTROL.
 2. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ERECTING, MAINTAINING, AND REPAIRING ALL EROSION CONTROL DEVICES UNTIL THE SITE IS STABILIZED, AND FOR REMOVING SAME WHEN THE SITE IS STABILIZED. THE CONTRACTOR ALONE SHALL BE LIABLE FOR ALL PENALTIES, FINES, OR OTHER CONSEQUENCES OF HIS FAILURE TO MAINTAIN EROSION CONTROL.
 3. SILT FENCES, STRAW BALE BARRIERS AND OTHER EROSION CONTROL DEVICES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY. IF ANY EROSION CONTROL DEVICE DECOMPOSES OR BECOMES INEFFECTIVE PRIOR TO ESTABLISHMENT OF PERMANENT VEGETATION, THE DEVICE SHALL BE REPLACED PROMPTLY.
 4. CONTRACTOR SHALL REMOVE SEDIMENT FROM ALL EROSION CONTROL DEVICES AND BASINS WHEN THE SILT HAS REACHED A DEPTH OF EIGHT INCHES OR IN ANY OF THESE DEVICES.
 5. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE EROSION DEVICE IS NO LONGER REQUIRED, SHALL BE DRESSED TO CONFORM WITH THE FINISH GRADE AND SEEDED.
 6. ALL DISTURBED AREAS SHALL BE MULCHED FOR EROSION CONTROL NO LATER THAN 14 DAYS FOLLOWING THE LAST CONSTRUCTION ON THE AREA, UNLESS CONSTRUCTION IS TO RESUME ON THE AREA WITHIN 21 DAYS OF THE LAST CONSTRUCTION ON THE AREA.

