# ROOM FINISH SCHEDULE

| ROOM NUMBER | ROOM NAME | FLOOR | BASE | WALLS NORTH | WALLS SOUTH | WALLS EAST | WALLS WEST | CEILING MATL. | CEILING HEIGHT | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| 101 | HALL | PT3 | B4 | N/A | N/A | N/A | N/A | ACT1 | 3658 | |
| 102 | ENTRY | PT1, PT2, PT3 | B4 | P1 | P1 | P1 | P1 | ACT1, ACT2, P1 | VARIES | RECESSED FLOOR MAT |
| 103 | CORRIDOR | PT1, PT2, PT3 | B4 | WC1 | WC1 | WC1 | WC1 | ACT1 | 2750 | |
| 104 | OFFICE | CPT1 | B3 | WC1 | WC1 | WC1 | WC1 | ACT1 | 2750 | |
| 105 | BRIEFING ROOM 4 | CPT1 | B3 | WC1 | WC1 | WC1 | WC1 | ACT1 | 2750 | |
| 106 | BRIEFING ROOM 3 | CPT1 | B3 | WC1 | WC1 | WC1 | WC1 | ACT1 | 2750 | |
| 107 | BRIEFING ROOM 2 | CPT1 | B3 | WC1 | WC1 | WC1 | WC1 | ACT1 | 2750 | |
| 108 | BRIEFING ROOM 1 | CPT1 | B3 | WC1 | WC1 | WC1 | WC1 | ACT1 | 2750 | |
| 109 | STORAGE | P6 | B2 | P1 | P1 | P1 | P1 | ACT1 | 2750 | |
| 110 | JANITOR | PT8 | B5 | P1 | P1 | P1 | P1 | ACT1 | 2750 | |
| 111 | CORRIDOR | P5 | B1 | P4 | P4 | N/A | P4 | ACT1 | 2750 | |
| 112 | STORAGE | P6 | B2 | P1 | P1 | P1 | P1 | ACT1 | 2750 | |
| 113 | MEN | PT4, PT5 | B6,B7 | PT4, PT7, P3 | PT4, PT7, P3 | PT4, PT7, P3 | PT4, PT7, P3 | ACT1 | 2750 | |
| 114 | WOMEN | PT4, PT6 | B6,B8 | PT4, PT7, P2 | PT4, PT7, P2 | PT4, PT7, P2 | PT4, PT7, P2 | ACT1 | 2750 | |
| 115 | MECHANICAL ROOM | P6 | B2 | P1 | P1 | P1 | P1 | ACT3 | --- | |
| 116 | MAINTENANCE | P6 | B2 | P1 | P1 | P1 | P1 | ACT1 | 2750 | |
| 117 | TRAINER BAY | P5 | B1 | P4 | P4 | P4 | P4 | ACT4 | VARIES | PAINT EXPOSED STRUCTURE |

# MATERIAL LEGEND

| | MARK | DESCRIPTION |
|---|---|---|
| CARPET | CPT-1 | BIGELOW, CITYSCAPES W010-3118 MIXED MEDIA |
| TILE | PT-1 | AMERICAN OLEAN TK-14 TRANSVAAL, POLISHED (400x400) |
| | PT-2 | AMERICAN OLEAN TK-14 TRANSVAAL, UNPOLISHED (400x400) |
| | PT-3 | AMERICAN OLEAN W73 PEPPER GRANITE (400x400) |
| | PT-4 | AMERICAN OLEAN D59 TAUPE MIST (50x50) |
| | PT-5 | AMERICAN OLEAN D09 SATIN IMPERIAL PURPLE (50x50) |
| | PT-6 | AMERICAN OLEAN D30 SATIN OLIVE (50x50) |
| | PT-7 | AMERICAN OLEAN Y64 GLOSS BLACK (50x50) |
| | PT-8 | AMERICAN OLEAN N04 PRAIRE FLASH (200x200) |
| BASES | B-1 | JOHNSONITE 40 BLACK |
| | B-2 | JOHNSONITE 20 CHARCOAL |
| | B-3 | BIGELOW, CITYSCAPES W010-3118 MIXED MEDIA 100mm |
| | B-4 | AMERICAN OLEAN W73 PEPPER GRANITE (400x100) |
| | B-5 | AMERICAN OLEAN N04 PRAIRE FLASH (200x100) |
| | B-6 | AMERICAN OLEAN D59 TAUPE MIST (50x50) |
| | B-7 | AMERICAN OLEAN D09 SATIN IMPERIAL PURPLE (50x50) |
| | B-8 | AMERICAN OLEAN D30 SATIN OLIVE (50x50) |

| | MARK | DESCRIPTION |
|---|---|---|
| PAINT | P-1 | DEVOE 2M43D BIGHORN, LATEX ENAMEL, FINISH EGGSHELL |
| | P-2 | SHERWIN WILLIAMS 1174 GETAWAY GREEN, LATEX ENAMEL, FINISH EGGSHELL |
| | P-3 | SHERWIN WILLIAMS 1560 RADICCHIO, LATEX ENAMEL, FINISH EGGSHELL |
| | P-4 | SHERWIN WILLIAMS SW 7069 IRON ORE, LATEX ENAMEL, FINISH FLAT |
| | P-5 | SHERWIN WILLIAMS SW 7069 IRON ORE, LATEX ENAMEL, FINISH FLAT W/ ARMORSEAL FLOOR - THANE CRU |
| | P-6 | SEALED CONCRETE |
| | P-7 | SHERWIN WILLIAMS SW 7069 IRON ORE, ALKYD ENAMEL, FINISH SATIN |
| CEILINGS | ACT-1 | USG FROST CLIMA PLUS, 490 |
| | ACT-2 | PAINTED GYPSUM BOARD |
| | ACT-3 | OPEN TO STRUCTURE |
| | ACT-4 | OPEN TO STRUCTURE-SHERWIN WILLIAMS SW 7069 IRON ORE, LATEX ENAMEL, FINISH FLAT |
| MISCELLANEOUS | PL-1 | PLASTIC LAMINATE: WILSONART 4623-60 GRAPHITE NEBULA |
| | B-1 | BLINDS: LEVELOR 885 DARK BRONZE MONACO |
| | G-1 | GROUT: TEC 915 LIGHT SMOKE |
| | G-2 | GROUT: TEC 927 LIGHT PEWTER |
| | WC-1 | VINYL WALLCOVERING: TOWER, RAVELLO, COLOR WOODRIFT T2-RL-07 |
| | S-1 | CLEAR FINISH NATURAL OAK |

# DOOR COLOR SCHEDULE

| DOOR NUMBER | PUSH SIDE COLOR | PULL SIDE COLOR |
|---|---|---|
| 101 | MATCH EXISTING | P-7 |
| 102A | STOREFRONT | STOREFRONT |
| 102B | STOREFRONT | STOREFRONT |
| 103A | S-1 | S-1 |
| 103B | P-7 | P-7 |
| 103C | P-7 | P-7 |
| 104 | S-1 | S-1 |
| 105 | S-1 | S-1 |
| 106 | S-1 | S-1 |
| 107 | S-1 | S-1 |
| 108 | S-1 | S-1 |
| 109 | P-7 | P-7 |
| 110 | P-7 | P-7 |
| 112 | P-7 | P-7 |
| 113 | P-7 | P-7 |
| 114 | P-7 | P-7 |
| 115 | P-7 | P-7 |
| 116 | P-7 | P-7 |
| 117A | P-7 INTERIOR | MATCH EXISTING EXTERIOR |
| 117B | P-7 INTERIOR | MATCH EXISTING EXTERIOR |
| 117C | P-7 INTERIOR | MATCH EXISTING EXTERIOR |
| 117D | P-7 INTERIOR | MATCH EXISTING EXTERIOR |
| 117E | P-7 | MATCH EXISTING EXTERIOR |

NOTE: ALL DOOR FRAMES TO BE P-7

NOTE:
ALL DIMENSIONS AND/OR DIMENSIONS SHOWN IN CALLOUTS/NOTES ARE IN MILLIMETERS (mm) UNLESS OTHERWISE NOTED.

U.S. ARMY CORPS OF ENGINEERS
LITTLE ROCK DISTRICT

| Mark | Description | Date | Appr. | Mark | Description | Date | Appr. |
|---|---|---|---|---|---|---|---|

Designed by: SJJ
Drawn by: JWT
Contract Date:
Reviewed by: DW
Drwg. Code:
File Name: 151001I-601
Plot date: 02/26/03
Plot scale: 1:1
Submitted by:
Atkins Benham, Inc.
Contract No.: DACA03-03-B-0031
Initiation No.: DACA03-03-R-0031

DEPARTMENT OF THE ARMY
U.S. ARMY CORPS OF ENGINEERS
LITTLE ROCK DISTRICT
LITTLE ROCK, ARKANSAS

Atkins Benham
0193 402-1900 www.atkinsbenham.com
group of companies
WS Atkins

ADAL C-130J AIRCREW FUSELAGE TRAINER
LRAFB, LITTLE ROCK AR.
Project No. NKAK 043005

ROOM FINISH SCHEDULE AND MATERIAL LEGEND

Sheet Reference Number:
I-601
Sheet 41 of 91

Drawing: F:\2402151001 LRAFB C130J FUSELAGE TRAINER\20_CAD\\151001I-601 Saved: 03/27/2003 18:21 By: tbg DimScale: 1.00 (TM=0)
XRefs: 151001G-BS001.DWG 151001I-SH01.DWG 151001I-SH02.DWG 151001I-SH03.DWG