

INTERIOR FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR		BASE		WALL (PLAN NORTH)		WALL (PLAN EAST)		WALL (PLAN SOUTH)		WALL (PLAN WEST)		CEILING			ROOM NO.	REMARKS (SEE NOTES BELOW)
		MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	HEIGHT		
319B	CLOSET	EXCONC	CPT5	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	7'-2"	319B	
320	ELECTRICAL	EXCONC	CONC / H	CGWB	RB	CGWB	FRP, P3	CGWB	FRP, P3	CGWB	P3	CGWB	P3	EXPOSED	EXP/P	VARIES	320	NOTES : 4, 5
321	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	321	NOTES : 1, 3, 4, 5, 8
321A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB	CT1	CGWB	CT1	CGWB	CT2	CGWB	CT1	GWB	P4	8'-0"	321A	NOTE : 4, 5, 7, 10
321B	CLOSET	EXCONC	CPT5	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	7'-2"	321B	
322	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	322	NOTES : 1, 3, 4, 5, 8
322A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB	CT2	CGWB	CT1	CGWB	CT1	CGWB	CT1	GWB	P4	8'-0"	322A	NOTE : 4, 5, 7, 10
322B	CLOSET	EXCONC	CPT5	GWB	RB	GWB	P1	GWB	P1	GWB	P1	CGWB	P1	GWB	P4	7'-2"	322B	
323	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	323	NOTES : 1, 3, 4, 5, 8
323A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB	CT1	CGWB	CT2	CGWB	CT1	CGWB	CT1	GWB	P4	8'-0"	323A	NOTE : 4, 5, 7, 10
323B	CLOSET	EXCONC	CPT5	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	7'-2"	323B	
324	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	324	NOTES : 1, 3, 4, 5, 8
324A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										8'-0"	324A	NOTE : 4, 5, 7, 10
324B	CLOSET	EXCONC	CPT5	GWB	RB	GWB										7'-2"	324B	
325	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	325	NOTES : 1, 3, 4, 5, 8
325A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										8'-0"	325A	NOTE : 4, 5, 7, 10
325B	CLOSET	EXCONC	CPT5	GWB	RB	GWB										7'-2"	325B	
326	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	326	NOTES : 1, 3, 4, 5, 8
326A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										8'-0"	326A	NOTE : 4, 5, 7, 10
326B	CLOSET	EXCONC	CPT5	GWB	RB	GWB										7'-2"	326B	
327	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	327	NOTES : 1, 3, 4, 5, 8
327A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										8'-0"	327A	NOTE : 4, 5, 7, 10
327B	CLOSET	EXCONC	CPT5	GWB	RB	GWB										7'-2"	327B	
328	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	328	NOTES : 1, 3, 4, 5, 8
328A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										8'-0"	328A	NOTE : 4, 5, 7, 10
328B	CLOSET	EXCONC	CPT5	GWB	RB	GWB										7'-2"	328B	
329	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	329	NOTES : 1, 3, 4, 5, 8
329A	CLOSET	EXCONC	CPT5	GWB	RB	GWB										8'-0"	329A	
329B	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										7'-2"	329B	NOTE : 4, 5, 7, 10
330	BEDROOM	EXCONC	CPT5, LVT1	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	330	NOTES : 1, 3, 4, 5, 8
330A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										8'-0"	330A	NOTE : 4, 5, 7, 10
330B	CLOSET	EXCONC	CPT5	GWB	RB	GWB										7'-2"	330B	
331	BEDROOM	EXCONC	CPT5, LVT1	CGWB	RB	GWB	P1	GWB	P1	CGWB	P1	GWB	P1	GWB	P4	VARIES	331	NOTES : 1, 3, 4, 5, 8
331B	CLOSET	EXCONC	CPT5	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	7'-4"	331B	
332	BEDROOM	EXCONC	CPT5, LVT1	CGWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	332	NOTES : 1, 3, 4, 5, 8
332A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB										8'-0"	332A	NOTE : 4, 5, 7, 10
332B	CLOSET	EXCONC	CPT5	GWB	RB	GWB										7'-2"	332B	
333	BEDROOM	EXCONC	CPT5, LVT1	CGWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	VARIES	333	NOTES : 1, 3, 4, 5, 8
333A	BATHROOM	EXCONC	PT1	CGWB	PT2	CGWB	CT1	CGWB	CT1	CGWB	CT2	CGWB	CT1	GWB	P4	7'-4"	333A	NOTE : 4, 5, 7, 10
333B	CLOSET	EXCONC	CPT5	GWB	RB	GWB	P1	GWB	P1	GWB	P1	GWB	P1	GWB	P4	7'-4"	333B	
334	UTILITY CORRIDOR	EXCONC	CONC / H	GWB	RB	GWB	P3	GWB	P3	GWB	P3	GWB	P3	EXPOSED	EXP/P	VARIES	334	NOTES : 4, 5

NOTE :
1. 5/16" THICK NON SKID ABRASIVE STRIPS AT ALL FLOOR TYPE TRANSITIONS WITH THE EXCEPTION OF LVT TO CARPET IN BEDROOMS.
2. CT2 ACCENT TILE ON BACKSPLASH.
3. CORNER GUARDS ON ALL EXTERIOR CORNERS THROUGHOUT THE SPACE.
4. EXISTING FLOORING TO BE REMOVED, REPAIRED AND SURFACE PREPPED PER MANUFACTURERS RECOMMENDATION FOR INSTALLATION NEW MATERIALS.
5. EXISTING ACOUSTICAL CEILING TO BE REMOVED, SUBSTRATES TO BE CLEANED / REPAIRED AND NEW ACT / GWB TO BE INSTALLED PER MANUFACTURERS RECOMMENDATION. EXPOSED CEILINGS TO BE CLEANED, REPAIRED AND PREPPED PER MANUFACTURER RECOMMENDATIONS FOR DRY FALL APPLICATION.
6. CT1 36W FLOOR TO CEILING O.C. OF WATER FOUNTAIN WITH JOLLY FINISHED EDGE.
7. CT 1 HORIZONTAL APPLICATION. CT2 HERRINGBONE INSTALLATION.
8. EACH BEDROOM WILL HAVE 4' X 4' LVT ENTRY.
9. SHOWER WALLS TO BE PT3 VERTICAL STACK INSTALLATION.

INTERIOR FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR		BASE		WALL (PLAN NORTH)		WALL (PLAN EAST)		WALL (PLAN SOUTH)		WALL (PLAN WEST)		CEILING			ROOM NO.	REMARKS (SEE NOTES BELOW)
		MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	HEIGHT		

APP'D

DESCRIPTION

DATE

REV #

APPROVED

CHIEF ENGINEER

APPROVED

CIVIL ENGINEER

DETAILS (1)

ROOM FINISH SCHEDULE

LEVEL THREE

AIR MOBILITY COMMAND

19TH CIVIL ENGINEER SQUADRON

LITTLE ROCK, ARKANSAS

DATE:

JULY 2026

DESIGNED

BY:

Designer

DRAWN

BY:

Author

BUILDING

NO.:

PROJECT

NO.:

SHEET

REF.:

A-602

SHEET

NO.:

1

OF

XX

STATUS:65% PRELIMINARY DESIGN