



FEEDER SCHEDULE				
(X)	# OF SETS	CONDUCTORS	GROUND CONDUCTOR	CONDUIT SIZE
300.4	1	4-350KCMIL CU	1-4 CU	3"
150.4	1	4-12 CU	1-12 CU	1/2"
100.4	1	4-2 CU	1-6 CU	1 1/2"
60.4	1	4-4 CU	1-10 CU	1"

E10 TVSS SHALL BE 200KA MINIMUM, EQUIVALENT TO SQUARE D SURGELOGIC.