



1. REMOVE ALL ELECTRICAL IN AND ABOUT THIS FACILITY WHETHER SHOWN OR NOT, UNO.
2. REMOVE CONDUCTORS TO SOURCE. REMOVE ALL EXPOSED AND ACCESSIBLE CONDUIT. REMOVE ALL TELEPHONE, DATA, ETC. CABLING AND CONDUITS.
3. EXISTING EXTERIOR LIGHTING LOCATED NEAR THE BUILDING BUT NOT MOUNTED ON THE BUILDING SHALL REMAIN AND ANY CONDUITS AND CONDUCTORS FROM BUILDING SHALL REMAIN AND BE RE-CONNECTED TO NEW PANELS.

ED1	REMOVE ALL EXISTING LIGHT FIXTURES, LIGHTING CONTROLS, ELECTRICAL WIRING DEVICES, AND ALL SYSTEMS DEVICES/OUTLETS IN THIS ROOM. MECHANICAL EQUIPMENT REMOVED BY MECHANICAL CONTRACTOR. ELECTRICAL CONTRACTOR TO REMOVE ASSOCIATED ELECTRICAL EQUIPMENT. REMOVE THE WIRE AND CONDUITS BACK TO SERVING PANEL.
ED2	DEMO EXISTING PANELBOARDS. REMOVE FEEDER BACK TO MDP. CONDUIT IN BLOCK WALLS AND SLAB FLOOR TO REMAIN.
ED3	EXISTING UTILITY PAD MOUNTED TRANSFORMER.
ED4	DEMO EXISTING MDP AND ELECTRICAL SERVICE FEEDERS AND CONDUIT BACK TO UTILITY TRANSFORMER PAD.
ED5	DEMO ELECTRICAL EQUIPMENT ASSOCIATED WITH MECHANICAL EQUIPMENT IN THIS AREA TO BE DEMOLISHED.
ED6	DEMO EXISTING LIGHT FIXTURES. REMOVE THE CONDUCTORS AND CONDUIT BACK TO PANEL. REMOVE ALL ASSOCIATED CONTROLS. CONDUIT IN BLOCK WALLS AND SLAB FLOOR TO REMAIN.
ED7	DEMO EXISTING BOLLARD WITH LIGHT. REMOVE THE CONDUCTORS AND CONDUIT BACK TO PANEL. CONDUIT IN BLOCK WALLS AND SLAB FLOOR TO REMAIN.
ED8	DEMO ELECTRICAL EQUIPMENT, CONDUIT, AND CONDUCTORS ASSOCIATED WITH MECHANICAL EQUIPMENT IN THIS AREA TO BE DEMOLISHED.
ED9	TYPICAL DORM ROOM LAYOUT. REFER TO FIRST FLOOR FOR TYPICAL DORM ROOM LAYOUT.
ED10	REMOVE FIRE ALARM ANTENNA.
ED11	REMOVE EXISTING FIRE ALARM EQUIPMENT AND ALL ASSOCIATED CONDUITS AND CONDUCTORS.
ED12	DEMO EMS (EXISTING FIBER PULL BOX).
ED13	REMOVE CATV PULL BOX.

DATE:
JULY 2026
DESIGNED
BY:
JLS
DRAWN
BY:
MUC
BUILDING
NO.:

PROJECT
NO.:

SHEET
REF.:

ED101

SHEET
NO.:
1 OF XX