

## INTERIOR ELEVATION NOTES

REFER TO A0.05 FOR ADA MOUNTING HEIGHTS UNLESS SPECIFIED IN THIS SHEET. HAND SANITIZER DISPENSERS TO BE INSTALLED IN NUMEROUS LOCATIONS. CONFIRM LOCATIONS W/ OWNER. HAND SOAP DISPENSERS TO BE INSTALLED IN NUMEROUS LOCATIONS. CONFIRM LOCATIONS W/ OWNER. FOAM SEAT CLEANER DISPENSERS TO BE INSTALLED IN ALL RESTROOM STALLS. CONFIRM LOCATIONS W/ OWNER. STAINLESS STEEL SANITARY NAPKIN DISPOSALS TO BE INSTALLED IN ALL WOMEN'S RESTROOM STALLS. CONFIRM LOCATIONS W/ OWNER. ALL TOILET STALLS TO HAVE 42' GRAB BAR MOUNTED OVER TOILET PAPER

LOCATION: NOTE: ALL OUTSIDE CORNER EDGES WHERE THIS TILE IS INSTALLED MUST BE METAL USED ON THE SALES AREA FLOORS AND WALLS (EXCEPT THE GIFT AREA FLOORS). USED ON RESTROOM WALLS FOR BOTTOM AND TOP BANDS.
USED AS WALL BASE IN ALL ROOMS THAT HAVE THIS TILE ON THE FLOOR AND ON THE TOE KICK OF ALL CABINETRY. USED ON WALLS IN KITCHEN AREA.

USED ON FLOOR AND BASE IN KITCHEN AREA, INSIDE TEXAS ROUND UP AND INSIDE SWEET STREET AREA INCLUDING AT TOE BASE OF MILLWORK INSIDE TEXAS ROUNDUP/SWEET COVE BASE USED IN FOUNTAIN STORAGE, COFFEE SUPPLY, ICEE ROOM, AND KITCHEN

-3 LOCATION: NOTE: ALL OUTSIDE CORNER EDGES WHERE THIS TILE IS INSTALLED MUST BE METAL USED AT PONY WALLS AT SALES COUNTERS AND ON THE CUSTOMER SIDE OF MILLWORK. USED ON THE RESTROOM WALLS. USED ON THE CUSTOMER SIDE OF THE TEXAS ROUNDUP/SWEET STREET MILLWORK AND

USED AS AN ACCENT BAND ON THE CUSTOMER SIDE OF THE MILLWORK AT THE SALES COUNTERS, TEXAS ROUNDUP/SWEET STREET, AND DELI LINE-UP. USED AS AN ACCENT BAND ON THE RESTROOM WALLS. THERE IS A BAND APPROXIMATELY 48" AFF AND 9'-4" AFF. REFER TO INTERIOR ELEVATIONS. USED AS AN ACCENT BORDER ON THE FLOOR ENTERING THE RESTROOMS.

## **KEYED NOTES**

1 T-1 TILE AS SCHEDULED.

8 BLACK SLATWALL AND WOOD TRIM WD-1. RE: 9-12/A8.01 @ SALES FLOOR, 16 & 20/A8.01 @ B.O.H.

 $raket{9}$  ALUMINUM/GLASS STOREFRONT RE: DOOR/WINDOW SCHEDULE

(12) DOOR, FRAME AND HARDWARE. RE: DOOR SCHEDULE

13) MILLWORK.-RE: FINISH SCHEDULE & MILLWORK DETAIL SHEET A8.01

14 T1 TILE . CUT TILE TO TOE KICK OR WALL BASE HEIGHT. FIELD COORDINATE.

(15) 1" x 4" ROUGH CEDAR TRIM W/ MITERED CORNERS

(16) MASONRY STONE FINISH AS SCHEDULED.

17 MOUNTING HEIGHT TO BOTTOM OF DECORATIVE LIGHT FIXTURE SHALL BE MOUNTED AT 6'-0"

(18) 2"X2" 18 GA. BRUSHED STAINLESS STEEL CORNER GUARD.

(19) STAINLESS STEEL SHEETS BEHIND KITCHEN HOODS AND FRYER AREA. FIELD VERIFY. RE: A1.31

20 STEEL WALL BUMPER. RE: 14/A7.01

 $\langle 21 \rangle$  HAND WASH SINK, RE PLUMB.

(22) OCCUPANCY LIGHT. CENTER OVER DOOR OPENING. RE: 12 / A7.01

(23) PAINT WALLS RE: PARTITION TYPES FOR DETAILS

 $\langle 28 \rangle$  ALUMINUM ROUNDED BULL NOSE TRIM AS SCHEDULED.

(30) WALL MOUNTED PLUMBING FIXTURE. RE: PLUMBING DWGS.

 $\langle 32 \rangle$  Individual framed Mirror Centered @ Ea. Sink Bowl. Owner to approve Style.

(33) TOILET TISSUE DISPENSER. OWNER PROVIDED

(34) ADA TOILET ROOM SIGN. OWNER PROVIDED

(35) PAPER TOWEL DISPENSER.OWNER PROVIDED

36 ELECTRICAL PANEL. RE: ELECTRICAL DRAWINGS

FINISH. PULLS TO BE HAFELE ALUM HANDLE 70MM WIDE, COLOR- DARK OIL-RUBBED BRONZE. WHERE APPLICABLE CABINETS WILL BE LINE BORES FOR ADJUSTABLE SHELVING.

(38) INTERIOR OF CABINETS TO HAVE WHITE LAMINATE LINER.

(39) WALL PATTERNS IN TOILET ROOMS, REF. A3.41-A3.42

40 DIAPER CHANGING STATION. OWNER PROVIDED

 $\langle 41 \rangle$  RE: PLUMBING DRAWINGS FOR MOP SINK FAUCET

 $\langle 43 \rangle$  KV 183 WALL STANDARDS AT 32" O.C. FASTENED TO WALL STUDS. PROVIDE 183C BRACKETS AND

RICHPAN 1040 PVC FLEXIBLE MEMBRANE UNDER MORTOR BED. APPLY 24" UP WALL AND TO TOP

(45) 3/4" DIA. PERFORATED SOLID SURACE SEE PLUMBING DWGS. FOR EXAUST VENT COORDINATION. (46) PROVIDE ADDITIONAL MILLWORK SUPPORTS TO CARRY WEIGHT OF THE ICE DISPENSER AND ICE

(47) INSULATED STAINLESS STEEL DRIP TRAY

49 SANITIZER DISPENSERS INSTALLED BY G.C. PROVIDED BY OWNER. CONFIRM TOTAL W/ OWNER. (50) HAND SOAP DISPENSERS INSTALLED BY G.C. PROVIDED BY OWNER. CONFIRM TOTAL W/ OWNER.

51> FOAM SEAT CLEANER DISPENSERS INSTALLED AT EACH STALL BY G.C. PROVIDED BY OWNER. CONFIRM TOTAL WITH OWNER.

(52) STAINLESS STEEL SANITARY NAPKIN DISPOSAL INSTALLED AT ALL WOMEN STALLS PROVIDED BY

(54) STAINLESS STEEL SINK. REFER TO SHEET A9.10 & A9.11 EQUIPMENT PLAN

(55) ELECTRONIC ARTICLE SURVEILLANCE SYSTEM EQUIPMENT AS SCHEDULED

(56) 2x12 WALL BUMPER. RE:4,5, & 7/A1.21 & 8/A7.01

(57) 4"x4"x48" 1/4" STEEL ANGLE CORNER GUARD. RE: 4,5, & 7/A1.21

(58) ACCESS PANEL AS SCHEDULED.

METAL COMPONENTS. NO PLASTIC COMPONENTS ALLOWED. (60) SINKMASTER SOAP DISPENSER. MOUNT 6" INSIDE EDGE OF BOWL. RE: KITCHEN EQUIP. SHCED.

(62) PAINT TILT PANEL AROUND OVER HEAD DOORS.

(63) 2" x 2" ALUMINUM ANGLE CORNER GUARD. RE: 22/A1.21


BENTON, ARKANSAS



Buc-ee's Benton, LLC Saline County, Arkansas TEL: (979) 230-2920

## LAWRENCE S. LEVINSON, A.I.A.

7 n
_
_
_



04/23/2025

SSUED FOR REVIEW:	04/26/2024	
SSUED FOR BID:	05/14/2024	
SSUED FOR PERMIT:	05/14/2024	
Copyright 2024 Lawrence S. Levinson, AIA., Warning: This document is protected by U.S. Copyright Law Under Section 102 of the U.S. Copyright and the Architectural Works Copyright		

Protection Act of 1990. Unauthorized reproduction and distribution of this document or any portion of it, other than for use of this particular project, is prohibited and may result in severe

civil and criminal penalties, and will prosecuted to maximum extent possible under the law.

INTERIOR ELEVATIONS

LAARC PROJECT NUMBER: