



MILLWORK NOTES / SCHEDULE	MILLWORK - KEYED NOTES
GENERAL: 1. MILLWORK TO BE INSTALLED AFTER TILE ON FLOOR. 2. SUPPLY ACCESS PANELS AS REQUIRED. FIELD VERIFY EXACT LOCATIONS. 3. WHERE APPLICABLE CABINETS WILL BE LINE BORES FOR ADJUSTABLE SHELVING. 4. ALL MILWORK TO OFFEE, FOUNTAIN, AND ICEE AREAS SHALL BE CONSTRUCTED USING 19MM (3/47) *KOMATEX' INTEGRAL FOAM SHEETS UNLESS NOTED OTHERWISE. 5. PROVIDE 3/4" THK. VERTICAL SUPPORTS IN BASE CABINETS CONT. FROM FRONT TO BACK @ 40°.0.C. MAX. 6. BaC RACKS ARE PROVIDED BY OWNER. INSTALLED BY CONTRACTOR. 7. GROMMETS TO BE 2 3/8". VERIFY PLACEMENT WITH OWNER. 1. HINGES: BLUM, CLIP TOP BLUMOTION SOFT CLOSE, STEEL WI POLISHED FINISH. 2. PULLS: HAFELE, ALUMINUM HANDLE, DARK OLI-RUBBED BRONZE ITEM # 124.02.332 3. CATCHES: EPCO MAGNETIC 4. LED LIGHTS: HAFELE, *LOOK' 12V STRIP. 5. 1.4" PLEX-GLASS INSERT 6"WX57HX30". WITH ADJUSTABLE PARTITIONS COLORS: 1. 1. ALL SOLID SURFACE TO BE SSF-1. UNLESS OTHERWISE NOTED. 2. ALL SOLID SURFACE TO BE SSF-1. UNLESS OTHERWISE NOTED. 3. INTERIOR CABINETS EXPOSED SURFACES TO BE PL-3. UNLESS OTHERWISE NOTED. 3. INTERIOR CABINETS ENDES CONFIRM WITH OWNER.	1 T-1 TILE AS SCHEDULED.
	2 T-3 TILE AS SCHEDULED.
	3 T-4 TILE AS SCHEDULED.
	(4) SOLID SURFACE- W/ BULLNOSE EDGES
	5 PONY WALL ASSEMBLY. CERAMIC TILE AS SCHEDULED, OVER 5/8" CEMENT BOARD, OVER 18 GA MTL. STUD FRAMING @ 16" O.C.
	6 CABLE CHASE BEYOND, PROVIDE 1/4 BEND OFFSETS IN CORNER CASE.
	T ACCESS PANEL
	8 12"x12" ACCESS PANEL
	9 RAW PLYWOOD FOR TILE
	(10) GROMMET 2 3/8"
	(11) SCHEDULED SAFE
	$\langle 12 \rangle$ LINE OF CIGARRETE SHELVING
	(13) EQUIPMENT RE: SCHEDULE
	(14) DROP-IN REFRIGERATED COLD WELLS.
	$\langle 15 \rangle$ 8" DIAMETER TRASH HOLE WITH 3" DEEP PVC SLEEVE BELOW SOLID SURFACE COUNTER.
	(16) TRASH CAN, BY OTHERS.
	(17) 30-1/8"L x 6-1/2"H x 6-1/8"D COVE FOR INSERT TYPICAL.
	18 LED LIGHTING "LOOX" 12V STRIP LIGHTING TYP.
	(19) 1/4" PLEXI-GLASS INSERT 6"Dx5H"x30"L W/ ADJUSTABLE PARTITIONS TYP. 6 / A8.00
	20) 1/4"x8" ROUTED OPEN AIR VENTS
	21 FLOOR SINK RE: PLUMBING
	22 PROVIDE ACCESS PANEL FOR FLOOR SINK IN THE FIELD. V.I.F. AND COORDINATE AS REQUIRED
	23 1-1/2" RADIUS @ ALL CORNERS
	24 COMPX NATIONAL CAM LOCK, ITEM C8053-14A, KEYING TO C415A W/ D8783 BLANK.
	(25) MILLWORK DOOR WITH SCHEDULED HARDWARE.
	26 3/8" x 16" ROUTED OPEN AIR VENTS @ 1-1/4" SPACING.
	(27) DOORS AT ONE SIDE FACING DELI, WITH SCHEDULED HARDWARE.
	28 REMOVABLE MILLWORK INSERT. FUTURE SAFE LOCATION.
	29 DRAWER PULLS. HAFELE, DARK OIL-RUBBED BRONZE, ITEM 116.07.319 @ FILE CABINET ONLY.
	(30) DOVETAIL JOINTS AT DRAWER CORNERS.



Buc-ee's Benton, LLC Saline County, Arkansas TEL: (979) 230-2920

