




Buc-ee's Benton, LLC
Saline County, Arkansas

BUC-EE'S TRAVEL CENTER
BENTON, ARKANSAS
74K - L - 2025 -Q1
INTERSTATE 30 & STATE HIGHWAY 229
BENTON, ARKANSAS 72019

LAWRENCE S.
LEVINSON, A.I.A.

7800 Washington Ave., Suite 600
main: 713.600.3600

ISSUE/REVISION LOG:		
No.	DESCRIPTION	DATE
1	OWNER CHANGES	09/09/2024
3	OWNER CHANGES	04/23/2025



ISSUED FOR REVIEW:	04/26/2024
ISSUED FOR BID:	05/14/2024
ISSUED FOR PERMIT:	05/14/2024

Copyright 2024 Lawrence S. Levinson, AIA. Warning: This document is protected by U.S. Copyright Law Under Section 102 of the U.S. Copyright and the Architectural Works Copyright Protection Act of 1990. Unauthorized reproduction and distribution of this document or any portion of it, other than for use of this particular project, is prohibited and may result in severe civil and criminal penalties, and will be prosecuted to maximum extent possible under the law.

A8.16

MILLWORK DETAILS -
CASHIER COUNTER 7

LAARC PROJECT NUMBER: 2024-107.000

BENTON, ARKANSAS

GENERAL:

1. MILLWORK TO BE INSTALLED AFTER SET ON FLOOR.
2. SUPPLY ACCESS PANELS AS REQUIRED. FIELD VERIFY EXACT LOCATIONS.
3. WHERE APPLICABLE CABINETS WILL BE LINE BORDERS FOR ADJUSTABLE SHELVING.
4. ALL MILLWORK IN COFFEE, FOUNTAIN, AND CUBE AREAS SHALL BE CONSTRUCTED USING 18MM 3/4" THICK INTERIOR GRADE SHEETS UNLESS NOTED OTHERWISE.
5. PROVIDE 3/4" THICK VERTICAL SUPPORTS IN BASE CABINETS CONT. FROM FRONT TO BACK OF 48" O.C. MAX.
6. BAG RACKS PROVIDED BY OWNER. INSTALLED BY CONTRACTOR.
7. GROMMETS TO BE 23P. VERIFY PLACEMENT WITH OWNER.

HARDWARE:

- HINGES: BLUM, 2" UP PLUMATION STOP CLOSE. STEEL, W/ POLISHED FINISH.
- PULLS: HAFELE, ALUMINUM HANDEL, DARK OIL RUBBED BRONZE. ITEM # 124 02 03.
- CATCHES: EPOCH MAGNETIC.
- LED LIGHTING: HAFELE, 120V 2700K, 5W STRIP.
- 1/4" PLEX-GLASS INSERT W/ 50X130X1/4" WITH ADJUSTABLE PARTITIONS

COLORS:

1. ALL SOLID SURFACE TO BE SSF-1. UNLESS OTHERWISE NOTED.
2. ALL LAMINATE AT EXTERIOR EXPOSED SURFACE AREAS TO RECEIVE PL-1, UNLESS OTHERWISE NOTED.
3. INTERIOR CABINETS EXPOSED SURFACES TO BE PL-3. UNLESS OTHERWISE NOTED.

NOTE: FIELD VERIFY THE ABOVE FINISHES, CONFORM WITH OWNER.

- ① T-1 TILE AS SCHEDULED.
- ② T-3 TILE AS SCHEDULED.
- ③ T-4 TILE AS SCHEDULED. ③
- ④ SOLID SURFACE- W/ BULLNOSE EDGES
- ⑤ PONY WALL ASSEMBLY CERAMIC TILE AS SCHEDULED. OVER 5/8" CEMENT BOARD. OVER 18" O.C. MTL. STUD FRAMING @ 16" O.C.
- ⑥ CABLE CHASE BEYOND. PROVIDE 1/4 BEND OFFSETS IN CORNER CASE.
- ⑦ ACCESS PANEL
- ⑧ 12"x12" ACCESS PANEL
- ⑨ RAW PLYWOOD FOR TILE
- ⑩ GROMMET 2 3/8"
- ⑪ SCHEDULED SAFE
- ⑫ LINE OF CIGARRETE SHELVING
- ⑬ EQUIPMENT. -- RE. SCHEDULE
- ⑭ DROP-IN REFRIGERATED COLD WELLS.
- ⑮ 8" DIAMETER TRASH HOLE WITH 3" DEEP PVC SLEEVE BELOW SOLID SURFACE COUNTER.
- ⑯ TRASH CAN, BY OTHERS.
- ⑰ 30-1/8"L x 6-1/2"H x 6-1/8"D COVE FOR LIGHTING TYPICAL.
- ⑱ LED LIGHTING "LOOK" 12V STRIP LIGHTING TYP.
- ⑲ 1/4" PLEXI-GLASS INSERT 6"Dx5"Hx30"L W/ ADJUSTABLE PARTITIONS TYP. 6 / A & 00
- ⑳ 1/4"x8" ROUTED OPEN AIR VENTS
- ㉑ FLOOR SINK RE. PLUMBING
- ㉒ PROVIDE ACCESS PANEL FOR FLOOR SINK IN THE FIELD. V.I.F. AND COORDINATE AS REQUIRED.
- ㉓ 1-1/2" RADIUS @ ALL CORNERS
- ㉔ COMPX NATIONAL CAM LOCK. ITEM C8053-14A. KEYING TO C415A W/ D8783 BLANK.
- ㉕ MILLWORK DOOR WITH SCHEDULED HARDWARE.
- ㉖ 3/8" x 16" ROUTED OPEN AIR VENTS @ 1-1/4" SPACING.
- ㉗ DOORS AT ONE SIDE FACING DEFLT. WITH SCHEDULED HARDWARE.
- ㉘ REMOVABLE MILLWORK INSERT. FUTURE SAFE LOCATION.
- ㉙ DRAWER PULLS. HAFEL. DARK OIL-RUBBED BRONZE. ITEM 16.07.319 @ FILE CABINET ONLY.
- ㉚ DOVETAIL JOINTS AT DRAWER CORNERS.
- ㉛ SOFT CLOSE CABINET DRAWER GUIDES. KNAPE-VOGT MODEL GS8850.
- ㉜ SCHEDULED LAMINATE ON EXTERIOR OF CABINET AND PL-3 ON INTERIOR OF CABINET.
- ㉝ HANGING FOLDER RAIL. FULL LENGTH OF DRAWER.
- ㉞ EMERGENCY FUEL SHUT OFF. ONLY AT CASHIER 5. RE. FUEL SYSTEM DRAWINGS.
- ㉟ 12"x4" STAINLESS STEEL SURFACE MOUNTED LOUVERED VENT.
- ㊱ ALUMINUM ROUNDED BULL NOSE TRIM AS SCHEDULED. TYP. @ ALL TILED MILLWORK CORNERS

NOT ALL NOTES ARE USED ON THIS SHEET

$$3/4'' = 1'-0''$$
$$\frac{3}{4}'' = 1'-0''$$
$$\frac{3}{4}'' = 1'-0''$$
