

#### T.R.U./SWEET ST. GENERAL NOTES

TO PERFORMING ANY WORK & SHALL NOTIFY THE ARCHITECT IMMEDIATELY OF ANY CONDITIONS THAT MAY EXIST. THAT ARE NOTE COVERED UNDER THESE PLANS. THE CONTRACTOR AND ALL SUB-CONTRACTORS SHALL NOT DAMAGE ANY INSTRUMENTS OR EQUIPMENT DURING THE COURSE OF THE PROJECT. THE CONTRACTOR AND ALL SUB-CONTRACTORS SHALL RETURN ANY INSTRUMENTS OR EQUIPMENT THAT ARRIVES DAMAGED. METAL STUD FRAMING SHALL BE 18 GA. @ 16" O.C. UNLESS OTHERWISE NOTED. RE: STRUCRURAL FOR DETAILS. WALL, MILLWORK, & EQUIPMENT ELEVATIONS ARE MEASURED FROM FINISHED FLOOR, UNLESS OTHERWISE NOTED. DIMENSIONS ARE TO FINISH FACE OF MATERIAL, UNLESSS OTHERWISE NOTED. PROVIDE DOUBLE STUDS, BLOCKING, BRACING & STEEL BACK-UP PLATES REQUIRED TO SUPPORT EQUIPMENT, MISCELLANEOUS ITEMS, E.G. CASEWORK, CABINETS, FIXTURES, SIGNS WALL MOUNTED EQUIPMENT, ETC. TYPICAL. ALL SYMBOLS, ABBRIVIATIONS, & NOTES MARKED "TYPICAL," OR "TYP," SHALL APPLY IN ALL SIMILAR CIRCUMSTANCES.

### T.R.U./SWEET ST. COLOR LEGEND

REFERENCE MECHANCIAL, ELECTRICAL, PLUMING, TECHNOLOGY, & REFRIGERATION DRAWINGS FOR MECHANICAL, POWER, LIGHTING, DATA, PLUMING, & REFRIGERATION

REFERENCE FOOD SERVICE DRAWINGS FOR SCHEDULED EQUIPMENT.

DO NOT SCALE DRAWINGS.

PLUMBING FIXTURES & LOCATIONS ELECTRICAL FIXTURES & LOCATIONS DATA FIXTURES & LOCATIONS LIGHTING FIXTUES & LOCATIONS REFRIGERATION FIXTURES & LOCATIONS SPECIAL MILLWORK ITEMS EQUIPMENT BUMPERS

#### T.R.U./SWEET ST. MILLWORK NOTES

WHERE APPLICABLE CABINETS WILL BE LINE BORED FOR ADJUSTABLE SHELVING. ALL MILLWORK IN TEXAS ROUND UP & FUDGE AREAS SHALL BE CONSTRUCTED USING 19MM (3/4") "KOMATEX" INTEGRAL FOAM SHEETS UNLESS NOTED OTHERWISE. PROVIDE 3/4" THK. VERTICAL SUPPORTS IN BASE CABINETS CONT. FROM FRONT TO BACK @ HINGES: BLUM, CLIP TOP BLUMOTION SOFT CLOSE, STEEL W/ POLISHED FINISH.
PULLS: HAFELE, ALUMINUM HANDLE, DARK OIL-RUBBED BRONZE ITEM # 124.02.332 CATCHES: EPCO MAGNETIC

LED LIGHTS: HAFELE, "LOOX" 12V STRIP. 1/4" PLEXI-GLASS INSERT 6"W x 5"H x 30"L WITH ADJUSTABLE PARTITIONS ALL SOLID SURFACE TO BE SSF-1, UNLESS OTHERWISE NOTED.

ALL LAMINATE AT EXTERIOR EXPOSED SURFACE AREAS TO BE PL-1, UNLESS OTHERWISE NOTED. INTERIOR CABINETS EXPOSED SURFACES TO BE PL-3, UNLESS OTHERWISE NOTED. NOTE: FIELD VERIFY THE ABOVE FINISHES, CONFIRM WITH OWNER.

## SWEET ST. MILLWORK - KEYED NOTES

SOLID SURFACE TOP AS SCHEDULED WITH BULLNOSE EDGE PROFILE, & 1 1/2" RADIUS AT ALL CORNERS, ON 3/4" KOMATEX SUBSTRATE. 2) JOIN SOLID SURFACE COUNTERS WITH CONTINUOUS BULLNOSE EDGE PROFILE & 1 1/2" RADIUS AT ALL CORNERS, ON 3/4" KOMATEX SUBSTRATE.

(3) 2 3/8" GROMMET WITH COVER. (4) 8" DIAMETER TRASH HOLE WITH 3" DEEP PVC SLEEVE BELOW SOLID SURFACE COUNTER.

5) WALL CAP. SOLID SURFACE AS SCHEUDLED. SQUARE EDGE PROFILE ON EQUIPMENT SIDE & BULLNOSE PROFILE SIDES ON ALL OTHER SIDES, & 1 1/2" RADIUS AT ALL CORNERS. UNLESS NOTED OTHERWISE.

(8) MILLWORK SUPPORT LEG. RE: 14 / A8.76 & - / ---

 $\langle 9 \rangle$  HAND LAVATORY STATION.

(11) CUT OUT FOR SINK FIXTURES.

(12) WOOD PLANK FINISH AS SCHEDULED.

(13) BASE AS SCHEDULED.

(14) FLOOR TILE AS SCHEDULED.

(15) WALL TILE AS SCHEDULD, ON 5/8" CEMENT BOARD, ON 18 GA METAL STUD FRAMING @ 16" O.C.

(16) WALL TILE AS SCHEDULED, ON KOMATEX BOARD.

(17) BACKSPLASH. SOLID SURFACE AS SCHEDULED.

 $\langle$ 20angle ADJUSTABLE SHELF WITH LINE BORED HOLES @ 1" O.C.

(21) MILLWORK DOOR WITH SCHEDULED HARDWARE.

(22) FIXED DISPLAY SHELF.

(23) 27"h x 43"w x 1/4"t, TEMPERED CLEAR GLASS.

(24) HAFELE "LOOX" 12V LED LIGHTING TYP.  $\langle 25 \rangle$  2 1/2" x 1" FULL LENGTH, STEEL TUBE REINFORCING.

(26) OPENING FOR ELECTRICAL WIRING.

(27) UTILITY CHASE IN MILLWORK CASE FOR ELECTRICAL & PLUMBING. 28) ACCESS PANEL IN BACK OF MILLWORK CASE FOR ELECTRICAL & PLUMBING CONNECTIONS &

(29) MAKE EDGE OF SCHEDULED SOLID SURFACE TOP FLUSH WITH FINISH.

(30) 3" BLACK PLASTIC TRIM BAND FASTEN WITH FLUSH COUNTERSUNK SCREWS. PAINT SCREW

(31) EQUIPMENT POWER LOCATION. COORDINATE FINAL LOCAITON WITH FOOD SERIVICE EQUIPMENT

(32) DATA LOCATION.

(34) ATTACH EQUIPMENT ELECTRICAL CABLES & PLUMNBING TUBING TO UNDERSIDE OF COUNTER &

(35) ALUMINUM ROUNDED BULL NOSE TRIM WITH 1/8" GROUT JOINT EACH SIDE

(36) STONE SLAB, BY OWNER. 25" HIGH SNEEZE GUARD. MFR. ADM, MODEL RING EP-5, BRUSHED STAINLESS STEEL, FLANGE WITH COVER, & 1/4" TEMPERED GLASS.

3 BAY 17" HIGH SNEEZE GUARD WITH LED TUBE. MFR. ADM, MODEL EP-22, BRUSHED STAINLESS STEEL, FLANGE WITH COVER, WITH LED LIGHTING BAR, & 1/4 TEMPERED GLASS.

PROVIDE 3" x 4 1/2" x 16 1/2" UNDER COUNTER MOUNTED CABLE TRAY ADJACENT TO GROMET HOLE, VIVO CABLE TRAY, MODEL #DESK-AC06-1C, BLACK.

40 2" HOLE WITH STAINLESS STEEL GROMMET & POT FILL NOZZLE

41 1 1/2" HOLE FOR REMOTE VALVE FOR POT FILL NOZZLE

(42) PROVIDE 12"x12" SURFACE MOUNTED ACCESS PANEL TO MILLWORK CHASE

STAINLESS STEEL DRAWER LINER. LINER SHALL BE THE FULL LENGTH & HEIGHT OF THE INSIDE OF THE DRAWER.

45) PROVIDE 14"x14" ACCESS OPENING FOR FLOOR SINK & WASTE DRAIN.

46 MAKE EDGE OF SCHEDULED SOLID SURFACE TOP FLUSH WITH WOOD PLANK FINISH.

NOT ALL NOTES ARE USED ON THIS SHEET



Buc-ee's Benton, LLC Saline County, Arkansas

TEL: (979) 230-2920

# LAWRENCE S. LEVINSON, A.I.A.

7800 Washington Ave., Suite 600 main: 713.600.3600		Houston, TX 77007 www.laarc.com
ISSUE	E/REVISION LOG:	
No.	DESCRIPTION	DATE
1	OWNER CHANGES	09/09/2024
3	OWNER CHANGES	04/23/2025



04/23/2025

SSUED FOR REVIEW:	04/26/2024		
SSUED FOR BID:	05/14/2024		
SSUED FOR PERMIT:	05/14/2024		
Copyright 2024 Lawrence S. Levinson, AIA., Warning: This document is protected by U.S. Copyright Law Under Section 102 of the U.S. Copyright and the Architectural Works Copyright Protection Act of 1990. Unauthorized reproduction and distribution of this document or any portion of it, other than for use of this particular project, is prohibited and may result in severe			

A8.95<sub>1</sub>

civil and criminal penalties, and will prosecuted to maximum extent possible under the law.

SWEET STREET - MILLWORK DETAILS

BENTON, ARKANSAS

2025-000.000 LAARC PROJECT NUMBER: