

### T.R.U./SWEET ST. GENERAL NOTES

TO PERFORMING ANY WORK & SHALL NOTIFY THE ARCHITECT IMMEDIATELY OF ANY CONDITIONS THAT MAY EXIST, THAT ARE NOTE COVERED UNDER THESE PLANS. THE CONTRACTOR AND ALL SUB-CONTRACTORS SHALL NOT DAMAGE ANY INSTRUMENTS OR EQUIPMENT DURING THE COURSE OF THE PROJECT.
THE CONTRACTOR AND ALL SUB-CONTRACTORS SHALL RETURN ANY INSTRUMENTS OR EQUIPMENT THAT ARRIVES DAMAGED. METAL STUD FRAMING SHALL BE 18 GA. @ 16" O.C. UNLESS OTHERWISE NOTED. RE: STRUCRURAL FOR DETAILS. WALL, MILLWORK, & EQUIPMENT ELEVATIONS ARE MEASURED FROM FINISHED FLOOR, UNLESS OTHERWISE NOTED. DIMENSIONS ARE TO FINISH FACE OF MATERIAL, UNLESSS OTHERWISE NOTED. PROVIDE DOUBLE STUDS, BLOCKING, BRACING & STEEL BACK-UP PLATES REQUIRED TO SUPPORT EQUIPMENT, MISCELLANEOUS ITEMS, E.G. CASEWORK, CABINETS, FIXTURES, SIGNS WALL MOUNTED EQUIPMENT, ETC. TYPICAL. ALL SYMBOLS, ABBRIVIATIONS, & NOTES MARKED "TYPICAL," OR "TYP," SHALL APPLY IN ALL

SIMILAR CIRCUMSTANCES REFERENCE MECHANCIAL, ELECTRICAL, PLUMING, TECHNOLOGY, & REFRIGERATION DRAWINGS FOR MECHANICAL, POWER, LIGHTING, DATA, PLUMING, & REFRIGERATION REFERENCE FOOD SERVICE DRAWINGS FOR SCHEDULED EQUIPMENT

## T.R.U./SWEET ST. COLOR LEGEND

PLUMBING FIXTURES & LOCATIONS ELECTRICAL FIXTURES & LOCATIONS DATA FIXTURES & LOCATIONS LIGHTING FIXTUES & LOCATIONS REFRIGERATION FIXTURES & LOCATIONS SPECIAL MILLWORK ITEMS EQUIPMENT BUMPERS

#### T.R.U./SWEET ST. MILLWORK NOTES

MILLWORK WALLS TO BE INSTALLED PRIOR TO TILE ON FLOOR. MILLWORK CABINETS TO BE INSTALLED AFTER TILE ON FLOOR & WALLS, SUPPLY ACCESS PANELS AS REQUIRED. FIELD VERIFY EXACT LOCATIONS. WHERE APPLICABLE CABINETS WILL BE LINE BORED FOR ADJUSTABLE SHELVING. ALL MILLWORK IN TEXAS ROUND UP & FUDGE AREAS SHALL BE CONSTRUCTED USING 19MM (3/4") "KOMATEX" INTEGRAL FOAM SHEETS UNLESS NOTED OTHERWISE.

HINGES: BLUM, CLIP TOP BLUMOTION SOFT CLOSE, STEEL W/ POLISHED FINISH.

PULLS: HAFELE, ALUMINUM HANDLE, DARK OIL-RUBBED BRONZE ITEM # 124.02.332 **CATCHES:** EPCO MAGNETIC LED LIGHTS: HAFELE, "LOOX" 12V STRIP.

1/4" PLEXI-GLASS INSERT 6"W x 5"H x 30"L WITH ADJUSTABLE PARTITIONS ALL SOLID SURFACE TO BE SSF-1, UNLESS OTHERWISE NOTED. ALL LAMINATE AT EXTERIOR EXPOSED SURFACE AREAS TO BE PL-1, UNLESS OTHERWISE NOTED. INTERIOR CABINETS EXPOSED SURFACES TO BE PL-3, UNLESS OTHERWISE NOTED.

NOTE: FIELD VERIFY THE ABOVE FINISHES, CONFIRM WITH OWNER.

# SWEET ST. MILLWORK - KEYED NOTES

1) SOLID SURFACE TOP AS SCHEDULED WITH BULLNOSE EDGE PROFILE, & 1 1/2" RADIUS AT ALL

2) JOIN SOLID SURFACE COUNTERS WITH CONTINUOUS BULLNOSE EDGE PROFILE & 1 1/2" RADIUS AT ALL CORNERS, ON 3/4" KOMATEX SUBSTRATE.

BULLNOSE PROFILE SIDES ON ALL OTHER SIDES, & 1 1/2" RADIUS AT ALL CORNERS. UNLESS

8 MILLWORK SUPPORT LEG. RE: 14 / A8.76 & - / ---

9 HAND LAVATORY STATION.

10 POT FILL SINK

(11) CUT OUT FOR SINK FIXTURES.

(13) BASE AS SCHEDULED.

(15) WALL TILE AS SCHEDULD, ON 5/8" CEMENT BOARD, ON 18 GA METAL STUD FRAMING @ 16" O.C

21) MILLWORK DOOR WITH SCHEDULED HARDWARE

22) FIXED DISPLAY SHELF.

(23) 27"h x 43"w x 1/4"t, TEMPERED CLEAR GLASS.

(25) 2 1/2" x 1" FULL LENGTH, STEEL TUBE REINFORCING

26) OPENING FOR ELECTRICAL WIRING.

(27) UTILITY CHASE IN MILLWORK CASE FOR ELECTRICAL & PLUMBING. 28 ACCESS PANEL IN BACK OF MILLWORK CASE FOR ELECTRICAL & PLUMBING CONNECTIONS &

ig(29ig) MAKE EDGE OF SCHEDULED SOLID SURFACE TOP FLUSH WITH FINISH.

(30) 3" BLACK PLASTIC TRIM BAND FASTEN WITH FLUSH COUNTERSUNK SCREWS. PAINT SCREW

(33) WATER VALVE BOX.

34 ATTACH EQUIPMENT ELECTRICAL CABLES & PLUMNBING TUBING TO UNDERSIDE OF COUNTER &

(35) ALUMINUM ROUNDED BULL NOSE TRIM WITH 1/8" GROUT JOINT EACH SIDE

36 STONE SLAB, BY OWNER.

(37) 25" HIGH SNEEZE GUARD. MFR. ADM, MODEL RING EP-5, BRUSHED STAINLESS STEEL, FLANGE WITH COVER, & 1/4" TEMPERED GLASS.

3 BAY 17" HIGH SNEEZE GUARD WITH LED TUBE. MFR. ADM, MODEL EP-22, BRUSHED STAINLESS STEEL, FLANGE WITH COVER, WITH LED LIGHTING BAR, & 1/4 TEMPERED GLASS.

HOLE. VIVO CABLE TRAY, MODEL #DESK-AC06-1C, BLACK.

(40) 2" HOLE WITH STAINLESS STEEL GROMMET & POT FILL NOZZLE.

 $\overline{\langle 41 \rangle}$  1 1/2" HOLE FOR REMOTE VALVE FOR POT FILL NOZZLE

(42) PROVIDE 12"x12" SURFACE MOUNTED ACCESS PANEL TO MILLWORK CHASE. MILLWORK DRAWER WITH STAINLESS STEEL DRAWERS GLIDES, KNAPE-VOGT MODEL 6400 SS & DRAWER PULLS, HAFELE, DARK OIL-RUBBED BRONZE, ITEM 116.07.319 AT DRAWERS ONLY.

PROVIDE 14"x14" ACCESS OPENING FOR FLOOR SINK & WASTE DRAIN. (46) MAKE EDGE OF SCHEDULED SOLID SURFACE TOP FLUSH WITH WOOD PLANK FINISH.

NOT ALL NOTES ARE USED ON THIS SHEET

Buc-ee's Benton, LLC Saline County, Arkansas

TEL: (979) 230-2920

02

## LAWRENCE S. LEVINSON, A.I.A.

7800 Washington Ave., Suite 600 main: 713.600.3600		Houston, TX 77007 www.laarc.com	
SSUE/REVISION LOG:			
No.	DESCRIPTION	DATE	
1	OWNER CHANGES	09/09/2024	
3	OWNER CHANGES	04/23/2025	



04/23/2025

SUED FOR REVIEW:	04/26/2024
SUED FOR BID:	05/14/2024
SUED FOR PERMIT:	05/14/2024
copyright 2024 Lawrence S. Levinson, AIA., Warning: T	, ,

Protection Act of 1990. Unauthorized reproduction and distribution of this document or any portion of it, other than for use of this particular project, is prohibited and may result in severe civil and criminal penalties, and will prosecuted to maximum extent possible under the law.

SWEET STREET - MILLWORK DETAILS

2025-000.000 LAARC PROJECT NUMBER:

BENTON, ARKANSAS