

1. SEE SHEETS ds-001 & ds-002 FOR GENERAL STRUCTURAL NOTES AND ABBREVIATION KEY.
2. TOP OF EXIST. SLAB ELEVATION = 0'-0" UNLESS NOTED OTHERWISE.
3. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS BEFORE BEGINNING ANY WORK. DEVELOPMENT OF ANY SHOP DRAWINGS, OR PROCUREMENT OR FABRICATION OF ANY MATERIALS, NOTIFY ENGINEER OF RECORD IMMEDIATELY OF ANY DISCREPANCIES.
4. INDICATED LAYOUT OF EXISTING FOUNDATIONS IS PROVIDED FOR SCHEMATIC PURPOSES ONLY. CONTRACTOR SHALL NOT CUT INTO OR DISTURB ANY PORTION OF THE EXISTING FOUNDATIONS, UNLESS NOTED OTHERWISE.
5. GRANULAR FILL SHALL BE PLACED IN APPROXIMATELY 2" THICK LIFTS AND COMPACTED THOROUGHLY TO ENSURE PROPER SETTLEMENT.
6. TOP OF FOOTING SHALL BE 0'-0" U.N.O.
7. STAIR TREADS SHALL BE 1 1/2" THK X 11" GRIP STRUT, GALVANIZED.

SHEET LEGEND

C#	COLUMN TYPE, SEE SCHEDULE
F#	FOOTING TYPE, SEE SCHEDULE
	BAR GRATING, SEE NOTE 7
	CMU WALL

