



CONCRETE DRAINAGE SWALE








EROSION CONTROL NOTES:


- 1. A STORM WATER POLLUTION PREVENTION PLAN (SWP3) WILL BE PRODUCED BY THE OWNER (OPERATOR) FOR THE PROJECT TO BE COVERED UNDER THE ARKANSAS GENERAL PERMIT ARR150000. THE CONTRACTOR SHALL BE REQUIRED TO SIGN A COPY OF THE SWP3 AS FILED BY THE OWNER TO CONFIRM ASSOCIATION AND COMPLIANCE WITH THE REQUIREMENTS.
- 2. THE CONTRACTOR SHALL BE REQUIRED TO IMPLEMENT THE SWP3 ACCORDING TO THE REQUIREMENTS OF THE GENERAL PERMIT.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR AND SHALL PAY ALL COSTS ASSOCIATED WITH FINES OR PENALTIES THAT MAY BE IMPOSED BY THE GOVERNMENTAL AUTHORITY FOR THE FAILURE OF THE CONTRACTOR, THE CONTRACTOR'S SUBCONTRACTORS, THE CONTRACTOR'S SUPPLIERS OR THE CONTRACTOR'S AGENTS HAVING ACCESS TO THE SITE TO COMPLY WITH THE REQUIREMENTS OF THE GENERAL PERMIT AND/OR TO COMPLY WITH THE STORM WATER POLLUTION PREVENTION PLAN. THE OWNER SHALL BE ENTITLED TO WITHHOLD SUCH FROM CONTRACT FUNDS THAT MAY BE DUE TO THE CONTRACTOR AND/OR CLAIM THROUGH THE APPROPRIATE COURT HAVING JURISDICTION.
- 4. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE THE POSTING AND MAINTENANCE OF NOTICES IN THE AREA OF THE CONSTRUCTION WITH INFORMATION AS REQUIRED BY ADEQ REGULATION.
- 5. THE CONTRACTOR SHALL BE REQUIRED TO MAINTAIN AND UPDATE RECORDS AND INSPECTION REPORTS REQUIRED BY THE GENERAL PERMIT FOR STORM WATER DISCHARGES AND THE SPECIFIC STORM WATER POLLUTION PREVENTION PLAN. COPIES OF ALL DOCUMENTS SHALL BE AVAILABLE AT ALL TIMES AND PROVIDED TO THE OWNER AND/OR THE OWNER'S REPRESENTATIVE UPON DEMAND AND SHALL BE DELIVERED TO THE OWNER PRIOR TO FINAL PAYMENT.
- 6. INFORMATION REGARDING THE STORM WATER POLLUTION PREVENTION PLAN AND THE PERTINENT REGULATION MAY BE ACCESSED AT <u>www.adeq.state.ar.us</u>
- 7. SILT FENCES SHALL BE PLACED ALONG THE LIMITS OF CONSTRUCTION SLOPES TO PREVENT SOIL FROM LEAVING THE CONSTRUCTION AREA.
- 8. WORK SHALL NOT COMMENCE UNTIL EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.
- 9. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCE AS NEEDED TO MAINTAIN EFFECTIVENESS OF THE STRUCTURE. AS A MINIMUM, SILT SHALL BE REMOVED WHEN SEDIMENT DEPTH EXCEEDS HALF THE FABRIC HEIGHT. AFTER THE SILT FENCE IS NO LONGER NEEDED, THE SILT FENCE AND ALL DEPOSITED SEDIMENT SHALL BE REMOVED AND DISPOSED OF OFF SITE BY THE CONTRACTOR.
- 10. THE EXCAVATION AND MOVING OF SOIL MATERIALS, SHALL BE SCHEDULED SO THAT THE SMALLEST POSSIBLE AREAS WILL BE UNPROTECTED FROM EROSION FOR THE SHORTEST TIME FEASIBLE.
- 11. TEMPORARY SEEDING AND MULCH SHALL BE APPLIED TO PROTECT DISTURBED AREAS FROM EROSION. FINAL RESTORATION SHALL BE PER SPECIFICATIONS.
- 12. THE LOCATIONS OF THE CONCRETE WASHOUT AND THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE DETERMINED BY THE CONTRACTOR.
- 13. STREET SHALL BE SWEPT AS NECESSARY TO MINIMIZE OFFSITE TRACKING OF SEDIMENT.
- 14. EROSION CONTROL MEASURES SHALL BE IMPLEMENTED IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES (BMP'S).

EROSION CONTROL NOTES









AT FULL SIZE IF NOT ONE INCH SCALE ACCORDINGLY

~ •

FACILITY A

DATE: AUGUST 2024

DESIGNED BY: JDS

SHEET NO. CZ-3

SCALE: _

DRAWN BY:___


TILENAME:____

HWEI NO .:_

AS SHOWN


2020043

CZ-03




10 MIL. PLASTIC LINER


DITCH CHECK DETAIL



- 1. STAKES SHALL BE 1"x1" WOODEN TIMBER DRIVEN THROUGH THE STRAW WATTLE AND EMBEDDED A MINIMUM OF 6" INTO THE GROUND.
- 2. REMOVE AND DISPOSE OF SEDIMENT WHEN ACCUMULATION COVERS 33% OF THE WATTLE HEIGHT.

STRAW WATTLE INSTALLATION





- 1. EROSION CONTROL EEL TO BE INSTALLED WITH FLOCMAT OVER.
- 2. REMOVE AND DISPOSE OF SEDIMENT WHEN ACCUMULATION COVERS 50% OF THE DIKE'S HEIGHT.

EROSION CONTROL EEL WITH FLOCMAT

