



January 6, 2026

Ms. Erin Cumbo
Project Manager
USACE, Little Rock District
700 W Capital St.
Little Rock, AR 72207

Re: Amendment 0002 Documents
F-35: Special Access Program Facility
Ebbing ANGB, Fort Smith, AR
Contract: W9126G23D0005
Task: W9127S24F0007

Dear Ms. Cumbo:

This letter transmits the revised documents issued as part of Amendment 0002 to address current bidder inquiries for the F-35: Special Access Program Facility project.

This submittal includes the following revisions:

- **Specifications**
 - **31 00 00 – EARTHWORK – Attachment** – included portion of Geotechnical Investigation Report as an attachment in response to bidder inquiry.
 - **33 05 07.13 – UTILITY DIRECTIONAL DRILLING – new specification section** – changed utility installation from jack and bore to directional drilling for various electrical/comm conduits crossing existing pavements/ditch. Change due to feedback on other Ebbing projects. This specification section replaces the function of 33 05 23.
 - **33 05 23 – TRENCHLESS UTILITY INSTALLATION – removed specification section** – changed utility installation from jack and bore to directional drilling for various electrical/comm conduits crossing existing pavements/ditch. Change due to feedback on other Ebbing projects. This specification section's function is replaced by 33 05 07.13.
 - **Project Table of Contents** – Sections 33 05 07.13 was added to the project and 33 05 23 were removed from the project as noted above.

Ms. Erin Cumbo
USACE, Little Rock District
January 6, 2026
Page 2

- **Drawings**

- **G-002.1 – SHEET INDEX VOLUME 1** – Revised sheet list with updated drawings noted below
- **CU112.1 – UTILITY PLAN – AREA 2** – changed utility installation from jack and bore to directional drilling for various electrical/comm conduits crossing existing pavements/ditch. Change due to feedback on other Ebbing projects.
- **CU113.1 – UTILITY PLAN – AREA 3** – changed utility installation from jack and bore to directional drilling for various electrical/comm conduits crossing existing pavements/ditch. Change due to feedback on other Ebbing projects.
- **CU114.1 – UTILITY PLAN – AREA 4** – changed utility installation from jack and bore to directional drilling for various electrical/comm conduits crossing existing pavements/ditch. Change due to feedback on other Ebbing projects.
- **CU115.1 – UTILITY PLAN – AREA 5** – changed utility installation from jack and bore to directional drilling for various electrical/comm conduits crossing existing pavements/ditch. Change due to feedback on other Ebbing projects.
- **CU501.1 – UTILITY DETAILS** – Revised Detail G1 in response to bidder inquiry. Cathodic protection is not needed due to soil resistivity values obtained during the geotechnical investigation.
- **CU502.1 – UTILITY DETAILS** – Revised Details J12, J16, and E12 in response to bidder inquiry. Cathodic protection is not needed due to soil resistivity values obtained during the geotechnical investigation.
- **CU503.1 – UTILITY DETAILS** – Removed bollard requirement around fire hydrant and updated water tapping sleeve details based on feedback on other Ebbing projects.
- **CU506.1 – UTILITY DETAILS** – Revised Detail A1 to move the regulator orifice on the outlet structure to the bottom of the detention basin based on feedback on other Ebbing projects.
- **ES114** – sheet is to be included in Amendment 0002. Sheet was previously provided to USACE in August 2025.
- **ES115** – sheet is to be included in Amendment 0002. Sheet was previously provided to USACE in August 2025.
- **ES116** – sheet is to be included in Amendment 0002. Sheet was previously provided to USACE in August 2025.



Ms. Erin Cumbo
USACE, Little Rock District
January 6, 2026
Page 3

The revised documents are enclosed for your review.

Sincerely,

Seth Goeken, PE*, RCDD
Associate Electrical Engineer
Burns & McDonnell

* Registered in AR, KS, TX