

**SEDIMENT & EROSION CONTROL NOTES:**

- CONTRACTOR SHALL OBTAIN ALL PERMITS REQUIRED FROM A.D.E.Q. AND CITY OF ROGERS REGARDING RUNOFF, EROSION CONTROL, AND GRADING BEFORE BEGINNING CONSTRUCTION.
- ALL EROSION & SEDIMENT CONTROL DEVICES SHALL BE MAINTAINED AND OCCASIONALLY REPLACED THROUGHOUT THE CONSTRUCTION PROCESS.
- ALL EROSION & SEDIMENT CONTROL DEVICES SHOWN SHALL BE INSTALLED BEFORE CONSTRUCTION BEGINS. THOSE ITEMS SHALL REMAIN IN PLACE UNTIL DEEMED SAFE TO REMOVE BY ENGINEER.
- SOIL WHICH IS EXPOSED FOR MORE THAN FOURTEEN (14) DAYS WITH NO CONSTRUCTION ACTIVITY SHALL BE SEEDED, MULCHED, OR REVEGETATED.
- CONCRETE WASHOUTS SHALL NOT BE PLACED WITHIN 50 FT OF ANY WATER BODY (INCLUDING STORM DRAINS, INLETS, OR OPEN DRAINAGE)
- ANY PORTABLE TOILETS MUST BE AT LEAST 25 FEET AWAY FROM DRAINAGE FACILITIES.
- IF CONSTRUCTION ENTRANCE IS NOT NEEDED A TIRE WASH MUST BE PROVIDED

**WESTERN PLD FEATURE NOTE:**  
THE WESTERN PLD FEATURE SHALL BE DREDGED OUT AND THE MIXED MEDIA LAYER SHALL BE REPLACED

THE REGIONAL POND'S OUTLET STRUCTURE WILL NEED TO BE UNCLOGGED

**EROSION CONTROL**

