

ADDENDUM NO. 2 - Issued 08-28-2026
to the Project Manual and Drawings for

**JONESBORO FIELD OFFICE RECONSTRUCTION
ARKANSAS GAME AND FISH COMMISSION
JONESBORO, ARKANSAS
WDD JOB NO. 25-065**

WITTENBERG, DELONY & DAVIDSON, INC.
5050 NORTHSORE LANE
NORTH LITTLE ROCK, ARKANSAS 72118
(501)376-6681

This addendum forms a part of the contract documents and modifies or interprets the Project Manual and/or Drawings as noted herein.

GENERAL INFORMATION:

1. As stated at the Pre-Bid Conference, the deadline for submitting Requests for Information (RFIs) is Friday, 08-28-2026, EOB (end of the business day).

REFER TO THE PROJECT MANUAL:

Section 07 27 23:

1. Part 2.07.A. - DELETE Peel and Stick Underlayment.

Section 07 41 13:

1. Part 2.07.K. - DELETE Mid-States Asphalt QUIK-Stick FS Underlayment and ADD the following:
“Provide PAC-CLAD HT from Petersen Aluminum Corporation, a self-adhering, high temperature roofing underlayment or approved equal. Underlayment shall meet specified PAC-Clad Weather Tightness Warranty (WTW).”

REFER TO THE DRAWINGS:

Sheet S101:

1. Section 5/S201 applies at all new interior bearing wall and shear wall locations where a new thickened slab footing is required.
2. Existing thickened slabs and footings are shown with light lines and without a dark solid slab cut line.
3. Section 4/S201 applies at all interior hold-downs.

Sheet E201:

1. Detail 1 - Fire Alarm System Notes 1 through 4 describes intent for the owner-provided system.

END OF ADDENDUM NO. 2