

NOTE: REFER TO AUDIO VIDEO BACK BOX SCHEDULE FOR QUANTITIES OF EACH TERMINATION ID

AUDIO VIDEO TERMINATION SCHEDULE					
SIGNAL GROUP		CODE	WIRE QTY	DESTINATION	TOTAL SPARE REQUIREMENT
FH DY	III	SP12	1	AMRK	1
	V	STP	3	AMRK	1
HSAA					
	IV	ANTL	1	AMRK	1
HSAN					
	IV	ANTL	2	AMRK	1
HSAX					
	II	LINE	2	AMRK	1
	V	STP	4	AMRK	1
HSCM					
	II	ACOM	2	AMRK	1
HSCP					
	V	STP	1	AMRK	1
HSMX					
	II	ACOM	2	AMRK	1
	V	STP	7	AMRK	1
HSRM					
	I	MIC	2	AMRK	1
HSVI					
	V	STP	1	AMRK	1
LSCC					
	III	SP10	28	AMRK	3
LSCF					
	III	SP10	2	AMRK	1
LSMN					
	III	SP10	12	AMRK	2
LSSL					
	III	SP10	1	AMRK	1
STFB					
	V	STP	4	AMRK	1
STGA					
	I	MIC	6	AMRK	1
	II	ACOM	2	AMRK	1
	II	LINE	6	AMRK	1
	V	60S2	1	AMRK	1
	V	STP	6	AMRK	1
STGC					
	I	MIC	4	AMRK	1
	II	ACOM	2	AMRK	1
	II	LINE	4	AMRK	1
	V	60S2	1	AMRK	1
	V	STP	6	AMRK	1
STPA					
	V	STP	6	AMRK	1
STSC					
	III	VCTRL	1	AMRK	1
STTP					
	V	STP	1	AMRK	1

NOTE:

1. CONFIRM MOUNTING AND COLORS OF ALL PANELS WITHIN AUDIENCE OR CAMERA VIEW WITH ARCHITECT
2. ELEVATION FROM LEVEL IS DEFINED AS HEIGHT ABOVE FINISHED FLOOR TO CENTER OF THE BACK BOX

AUDIO VIDEO BACK BOX SCHEDULE					
TERMINATION ID	FUNCTION	QTY	BOX SIZE	ELEVATION FROM LEVEL	KEYNOTE
AMRK	AMP RACK	1	TROUGH AND LADDER BY CONTRACTOR	0' - 0"	
FHDY	FOH DISPLAY	3	CHIEF PAC525	7' - 0"	
HSAA	HOUSE ASSISTIVE LISTENING ANTENNA	1	6X6X6	9' - 10"	
HSAN	HOUSE ANTENNA	1	6X6X4	9' - 10"	
HSAX	HOUSE AUX PANEL	1	10X10X6	9' - 10"	
HSCM	HOUSE INTERCOM	1	6X6X6	1' - 6"	
HSCP	HOUSE PTZ CAMERA	1	4X4X4	9' - 10"	
HSMX	HOUSE MIX	1	10X10X6	1' - 6"	
HSV1	HOUSE VIDEO INPUT	1	6X6X6 WITH 1 GANG MUDRING	1' - 6"	
LSCC	CENTER CLUSTER LOUDSPEAKER	1	12X12X6	20" - 0"	
LSCF	CENTER FILL LOUDSPEAKER	2	6X6X6	20" - 1"	
LSMN	MAIN LOUDSPEAKER	2	8X8X6	18' - 11"	
LSSL	STAGE LIP LOUDSPEAKER	5	(none)	2' - 8"	STUB CONDUIT INTO LOUDSPEAKER ENCLOSURE
STFB	STAGE FLOOR BOX	2	FSR FL-600P	0' - 0"	
STGA	STAGE A DS	2	12X12X6	1' - 6"	
STGC	STAGE C US	2	12X12X6	1' - 6"	
STPA	STAGE PROJECTOR TYPE A	1	6X6X6	46' - 9"	
STSC	STAGE SCREEN	1	4 GANG	46' - 9"	
STTP	STAGE TOUCH PANEL	1	6X6X6 WITH 2 GANG MUDRING	3' - 6"	

ANY DIVISION 26 SCOPE OF
WORK SHOWN IS FOR
REFERENCE ONLY

REFER TO NOTE 3 AND THE
WORK SCOPE
SPECIFICATION TABLE ON
AV001



Project



**PHILANDER
SMITH
UNIVERSITY**

M.L. HARRIS
AUDITORIUM
RENOVATION

Volume

VOLUME 2

Design Phase

CONSTRUCTION DOCUMENTS

Revisions

[illegible]

Stamp

Notes

1. CROMWELL ARCHITECTS ENGINEERS, INC.
ALL RIGHTS RESERVED

2. THIS SHEET DESIGNED FOR COLOR PRINTING.
CRITICAL INFORMATION MAY BE LOST WITH
BLACK AND WHITE PRINTING.

Project Number

2024-06

Issue Date

09-10-2020

Sheet Title

AV SCHEDULES 2

Sheet Number

AV032