




 **1** WAREHOUSE ADDITION HVAC PLAN  
1/8" = 1'-0"

## KEYED NOTES

1. ROUTE REFRIGERANT LINES FROM THE CONDENSING UNIT TO THE AIR ROTATION UNIT. SIZE LINES ACCORDING TO THE REFRIGERANT MANUFACTURER'S RECOMMENDATIONS. SUPPORTS ALLOW THE CONCRETE AND UP THE SIDE OF THE AIR ROTATION UNIT. INSULATE LINES WITH PROTECTIVE ALUMINUM WRAP AND TIE THE TIES TO THE CONCRETE.
2. CONNECT GAS PIPING TO HEAT EXCHANGER. REFER TO PLUMBING DRAWINGS FOR INFORMATION.
3. ROUTE FULL SIZE CONDENSATE TO THE GROUND.
4. FILL SIZE SUPPLY DUCT INTO BUILDING. PROVIDE EXTERIOR WEATHERPROOF INSULATION SYSTEM PER THE SPECIFICATIONS. SEAL DUCTWORK PENETRATIONS INSIDE AND OUTSIDE AIRTIGHT.
5. 3-WAY DISCHARGE SUPPLY HAD PROVIDED MY THE ARU MANUFACTURER.
6. 60"Ø RETURN AIR PLenum. PROVIDE EXTERIOR WEATHERPROOF INSULATION SYSTEM PER THE SPECIFICATIONS. SEAL DUCTWORK PENETRATIONS INSIDE AND OUTSIDE AIRTIGHT.
7. PROVIDE 4" CONCRETE HOUSEKEEPING PAD.
8. ROUTE CONDENSATE AND REFRIGERANT LINE SET DOWN IN WALL AND STUB OUT APPROXIMATELY 1" ABOVE GRADE. SLEEVE ALL PIPES THROUGH ALL PIPE PENETRATIONS.
9. SIZE REFRIGERANT LINES PER MANUFACTURER'S RECOMMENDATIONS.

W Job Number:

99H

**SERVICE  
CENTER  
WAREHOUSE  
ADDITION**

## PERMIT AND BID ISSUE

Due Date: 12/1/2022

24/2026

## IONS

| NUMBER | DATE | DESCRIPTION |
|--------|------|-------------|
|--------|------|-------------|

## Contents:

WAREHOUSE  
ADDITION HVAC  
PLANS

THIS PAGE IS BEST  
VIEWED IN COLOR

M101