

:: Autodesk Docs://21A101 : 5/2/2025 2:42:11 PM Revit File: Plot Date:

Autodesk Revit 2023

DESCRIPTION OF MAJOR ITEMS IN PUMI ITEM DESCRIPTION 1 10" SPOOL, LENGTH AS REQUIRED WITH FLANGES 10" FLANGED 90" ELL. WITH 1/2" TAP 3 10" FLANGED 0.5.& Y. GATE VALVE WITH 1/2" TAP AND TAMPER SWITCH 4 FEBCO MODEL 825 YD REDUCED PRESSURE ASSEMBLY WITH MODULAR RELIEF VALVE AND TEST CONNECTION 5 10" FLANGED 0.5.& Y GATE VALVE WITH TAMPER SWITCH 6 10" FLANGED 0.5.& Y GATE VALVE WITH TAMPER SWITCH 8 12×10 FLANGED TEE 7 10" GROOVED SPOOL WITH GROOVED FLANGES, LENGTH AS REQUIRED 8 12×10 FLANGED ECCENTRIC REDUCER 9 FAIRBANKS MORSE FIRE PUMP 12"x8" 2823 AF 150 H.P. MOTOR ULL, F.M. APPROVED 2500 GPM © 65 PSI 10 10"x8" FLANGED CONCENTRIC REDUCER 11 0" FLANGED SPOOL WITH 1/2" WEDED OUTLET 12 10" RELIABLE MODEL "C" WAFER CHECK VALVE 13 10" FLANGED SPOOL WITH 1/2" WEDED OUTLET 14 NIBCO WD3510-4 WAFER 10" BUTTERFLY VALVE WITH TAMPER SWITCH 14A NIBCOWD3510-4 WAFER 10" BUTTERFLY VALVE WITHOUT TAMPER SW 15 20" WELDED HEADER WITH OUTLETS AS SHOWN 16 20" GROOVED SPOOL WITH GROOVED FLANGES 17 "RELIEF VALVE SET 175# U.L., F.M. APPROVED 18 6" FLANGED SPOOL LENGTH AS REQ'D.	QTY. 25 4 4 4 8 11 4 4 4 4 19 8 4 12 4 1 1 1	REVISION REVISION		Openation Openation Openation Openation
 19 6" FLANGED 90° ELL. 20 6"x10" CLOSED WASTE CONE 21 10" FLANGED X PLAIN END SPOOL (PAINTED) 22 10" FLANGED SPOOL (PAINTED) 23 10" FIRE PUMP TEST HEADER WITH (8) 2 1/2" OUTLETS AND (8) 2 1/2" ANGLE HOSE VALVES, CAPS, CHAINS AND 2 1/2" X 30" PLAYPIPES. 24 6" FLANGED 90° ELL. 25 6" FLANGED SPOOL, LENGTH AS REQ'D 26 6" FLANGED X THREAD SPOOL 27 6" RELIABLE MODEL "C" WAFER CHECK VALVE. 28 6" POTTER ROEMER FOUR WAY MODEL 5236 FIRE DEPT. CONNECTION WITH 1/2" BALL DRIP 29 2 1/2" O.S.& Y. FLANGED GATE VALVE 30 10" FLANGED SPOOL WITH 2 1/2" OUTLET 31 2 1/2" FLANGED SPOOL 32 1/2" FLANGED SPOOL 33 2 1/2" FLANGED CHECK VALVE WITH RUBBER FACED CLAPPER 35 2 1/2" SPOOL WITH 2 1/2"x9" FLG. & 2 1/2" X7" FLG. 36 2 1/2" SPOOL WITH 1/2" CONTROLLER CONNECTION & 1" RELIEF CONNECTION 37 10" FLANGED BASE 90" ELL. 38 METRON MODEL 1715 LOW SUCTION PRESSURE CUTOFF PANEL 39 JOCKEY PUMP & CONTROLLER 	1 1 3 2 10 9	BUILDING 1000 FIRE PUMP PLAN AND MATERIALS LIST	C	BY FOR REFERE
 40 METRON M-300 ACROSS THE LINE 100,000 AMP I.C. 460 VOLT WITH MOTOR LOCK OUT 41 METRON M-300 ACROSS THE LINE 100,000 AMP I.C. 460 VOLT WITH MOTOR LOCK OUT & SEQUENTIAL START 42 FLASHING RED LIGHT AND HORN 43 10" WEATHER PROOF ELECTRIC BELL 44 2 1/2" WATER FLOW SWITCH 45 1/2" BRASS CONTROL LINES WITH VALVE AND FITTINGS AS REQ'D – LENGTH AS REQUIRED 46 FIRE PUMP SPRINKLER SYSTEM COMPLETE 47 20", 10", 6", 4", & 2 1/2" BOLTS, NUTS AND GASKETS 48 PIPE STANDS 49 PIPE SUPPORTS FROM ROOF STRUCTURE 50 2900 GALLON CAPACITY FOAM TANK 51 4" STAINLESS STEEL BUTTERFLY GATE VALVES 52 4" FLEXIBLE CONNECTORS W/FLOATING FLANGES 53 4" STAINLESS STEEL "Y" TYPE STAINER 54 260 GALLON @ 200 PSI DISCHARGE PRESSURE FOAM CONCENTRATE PUMP & MOTOR ASSEMBLY W/GAUGES & BUILT-IN PRESSURE RELIEF VALVE AND BY PASS 55 8800 GALLON FOAM CONCENTRATE 55 8800 GALLON FOAM CONCENTRATE 56 4" STAINLESS STEEL PRESSURE REGULATING VALVE 57 FLUSHING CONNECTION ON 4" SPOOL 58 4" STAINLESS STEEL SWING CHECK 	1 3 1 1 12 1 AS REQ'D AS REQ'D AS REQ'D 2 8 4 1 1 2 1 1 2	Arkansas Modification Center UTLE ROCK, ARKANSAS	D	REV DATE DESCRIPTION
VALVE 200# 59 4" STAINLESS STEEL PIPE & FITTINGS 60 6" STAINLESS STEEL PIPE & FITTINGS DENOTES ITEM OF EQUIPMENT DENOTES NODE POINT	2 AS REO'D AS REO'D	r + Garver, P.A. REGISTERED OFTORNAL CARVER & CA	Ε	BILL AND HILARY CLINTON NATIONAL AIRPORT NATIONAL AIRPORT LITTLE ROCK, AR 72206 BUIMPOVEMENTS IMPROVEMENTS
		Garver	F	JOB NO.: 21A10111 DATE: MAY 2025 DESIGNED BY: JCF DRAWN BY: JCF BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY. DRAWING NUMBER R-17