



**SCOPE OF WORK
ASU CREST CENTER
JONESBORO, ARKANSAS**

Clark Job No. 1752

**BID PACKAGE 04.1 – MASONRY
VERSION 1.0**

**INCLUDING BUT NOT LIMITED TO:
SPECIFICATIONS:**

1. All work and material described in the following Sections are included within the scope of this Subcontract:
 - Division 00 Procurement and Contracting Requirements – All Sections
 - Division 01 General Requirements – All Sections
 - Section 04 20 00 – Unit Masonry
 - Section 04 72 00 – Cast Stone Masonry
 - Section 32 17 26 – Tactile Warning Surfacing

SCOPE OF WORK:

1. Furnish and install all concrete masonry units (CMU), including but not limited to:
 - a. Integral water repellent as specified.
 - b. Smooth-faced block.
 - c. Cementitious infill as shown.
 - d. Installation of reinforcement bar. Reinforcement bar supplied by others.
 - e. Integrally colored CMU.
2. Furnish and install cast stone caps at CMU walls as shown (RE: 7/A6.100, typ.), including but not limited to:
 - a. In accordance with Section 04 72 00 – Cast Stone Masonry.
3. Furnish and install all concrete caps on CMU walls (RE: Partition Types/A2.01).
4. Furnish and install all rigid insulation board at brick veneer locations.
5. Furnish and install bond beams as shown/specified.
6. Furnish and install all brick veneer, including but not limited to:
 - a. Mission Blend (ASU Blend) manufactured by Acme Brick or approved equal.
 - b. Three (3) color blend (33% each): Mission 1, Mission 2, Mission 3.
 - c. Texture: Velour.
 - d. Actual Size: Modular.
 - e. Grout and fill cavity solid at last course below weeps.
7. Furnish and install all masonry accessories required to complete this scope of work including but not limited to:
 - a. Mortar.
 - b. Grout.
 - c. Flashings.
 - d. Weeps.
 - e. Ties and anchors.
 - f. Vents.
 - g. Lap sealant.
 - h. Cleaning solutions.
 - i. Compressible fillers.
 - j. Continuous thru-wall flexible flashing.
 - k. Continuous mortar drainage material.
8. Furnish and install all detectable warning surfaces (RE: 12/C5.00), including but not limited to:
 - a. ADA paver by Wausau Tile.
 - b. 12" x 12", color: A-100.



**SCOPE OF WORK
ASU CREST CENTER
JONESBORO, ARKANSAS**

Clark Job No. 1752

**BID PACKAGE 04.1 – MASONRY
VERSION 1.0**

- c. Fill joints with polymeric sand.
- d. 1” thick mortar bed.
- e. Concrete screws or wedge anchors securing the pavers.
- 9. Installation of masonry lintels. Lintels provided by others.
- 10. Furnish and install labor and material required to construct onsite mock-up.
- 11. Strict compliance with all general and specific notes shown on the construction drawings.
- 12. All layout required for this scope of work.
- 13. Excavation and disposal of spoils off-site as required for this scope of work.
- 14. Coordination with third-party testing agency.
- 15. Field measuring for all items provided by this subcontractor.
- 16. All tools and equipment required to complete this subcontractor’s scope of work.
- 17. All scaffolding and/or lifts required to complete this subcontractor’s scope of work.
- 18. All hoisting and hoisting equipment required to complete this subcontractor’s scope of work.
- 19. Strict compliance with all OSHA guidelines.
- 20. Submittals as specified/required (product data, samples, installation instructions, shop drawings, engineered drawings, reports, certificates, sample warranties, etc.).
- 21. Delivery and storage of material (furnish connex(es) as required).
- 22. Freight to jobsite.
- 23. Receiving and unloading of material at the jobsite.
- 24. Daily clean-up during this subcontractor’s operations (dumpster provided by Clark).
- 25. Provide specified materials, model numbers and approved manufacturers only. Any deviations will be subject to removal and replacement, including any replacement of damaged items installed by others, at no additional cost.
- 26. Provide warranties and extended warranties as specified.
- 27. Provide attic stock as specified.
- 28. This Subcontractor will be required to provide detailed record documents (As-Builts) that document the following (including but not limited to): Architect’s proposal request changes, RFI’s, communication, Architect’s supplemental instructions, field changes and other such approved changes.
- 29. One (1) year warranty for material and workmanship from the date of substantial completion.
- 30. Sales tax as required.

EXCLUSIONS:

- 1. Bond.
- 2. Dumpster.
- 3. Sheathing.
- 4. Moisture barrier.
- 5. Concrete.
- 6. Concrete paving.
- 7. Painting.
- 8. Metal stud framing.

ALTERNATES:

- 1. None.



**SCOPE OF WORK
ASU CREST CENTER
JONESBORO, ARKANSAS**

Clark Job No. 1752

**BID PACKAGE 04.1 – MASONRY
VERSION 1.0**

ALLOWANCES:

1. None.

UNIT PRICES:

This Subcontract is a fixed lump sum Subcontract Agreement. For revisions to the scope of the project and/or revisions to the contract documents, the lump sum subcontract amount will be adjusted by change order at the following unit prices:

1. None.

SPECIAL TERMS AND CONDITIONS:

1. The scope of this work shall be completed within the specified schedule timeline.
2. This Subcontractor will provide sufficient manpower to meet the Project Schedule, including any overtime required to maintain the schedule, at no additional charge unless the necessity for overtime is caused by others failing to maintain their schedule through no fault of this Subcontractor or circumstances beyond control (such as “acts of God”).