



SCOPE OF WORK
ASU CREST CENTER
JONESBORO, ARKANSAS

Clark Job No. 1752

BID PACKAGE 08.3 – GLASS & GLAZING
VERSION 1.0

INCLUDING BUT NOT LIMITED TO:
SPECIFICATIONS:

1. All work and material described in the following Sections are included within the scope of this Subcontract:
 - Division 00 Procurement and Contracting Requirements – All Sections
 - Division 01 General Requirements – All Sections
 - Section 08 43 13 – Aluminum Framed Entrances and Storefronts
 - Section 08 44 13 – Aluminum Framed Curtain Walls
 - Section 08 80 00 – Glazing
 - Section 08 83 00 – Mirrors

SCOPE OF WORK:

1. Furnish and install all automatic door operators at aluminum door openings (wall-mounted and bollard assembly) (RE: 087100.A, 087100.B/A2.00).
2. Furnish and install all aluminum door thresholds (RE: 087100.C/A2.00).
3. Furnish and install all frameless plate glass mirrors, including but not limited to:
 - a. Mounting clips.
 - b. 5.0 mm thickness.
4. Furnish and install all aluminum curtain wall systems (RE: Section 08 44 13), including but not limited to:
 - a. 2-1/2" x 7-1/2" prefinished, thermally broken.
 - b. Clear anodized finish.
 - c. Gasketing.
 - d. Provide shop drawings complete with load calculations that are signed and sealed by a qualified professional engineer.
5. Furnish and install all aluminum storefront systems (RE: Section 08 43 13), including but not limited to:
 - a. 2" x 4-1/2" prefinished, thermally broken.
 - b. Clear anodized finish.
 - c. Gasketing.
6. Furnish and install all aluminum and glass doors (Types D1 & D2/1/A8.00 and Type E/A8.01), including but not limited to:
 - a. Exterior: 2-1/4" thick wide stile doors.
 - b. Interior: 1-3/4" thick wide stile doors.
 - c. Gasketing.
 - d. Hardware (RE: Section 08 71 00).
7. Furnish and install all exterior glazing (Glazing Type IG1/A5.00).
 - a. 1" clear insulated high-performance glass.
 - b. Solarban 70 Low-E on #2 surface.
 - c. Space between lites filled with argon.
8. Furnish and install all interior glazing (Glazing Type G1/A5.00).
 - a. 3/8" clear safety glass.
9. Furnish and install all aluminum foundation insulation protection flashing (RE: 9/A6.10, typ.).
10. Furnish and install all glass for door lites.
11. Furnish and install all glass for hollow metal frames.



**SCOPE OF WORK
ASU CREST CENTER
JONESBORO, ARKANSAS**

Clark Job No. 1752

**BID PACKAGE 08.3 – GLASS & GLAZING
VERSION 1.0**

12. Strict compliance with all general and specific notes shown on the construction drawings.
13. All layout required for this scope of work.
14. Coordination with third-party testing agency.
15. Field measuring for all items provided by this subcontractor.
16. All tools and equipment required to complete this subcontractor's scope of work.
17. All scaffolding and/or lifts required to complete this subcontractor's scope of work.
18. All hoisting and hoisting equipment required to complete this subcontractor's scope of work.
19. Strict compliance with all OSHA guidelines.
20. Submittals as specified/required (product data, samples, installation instructions, shop drawings, engineered drawings, reports, certificates, sample warranties, etc.).
21. Delivery and storage of material (furnish connex(es) as required).
22. Freight to jobsite.
23. Receiving and unloading of material at the jobsite.
24. Daily clean-up during this subcontractor's operations (dumpster provided by Clark).
25. Provide specified materials, model numbers and approved manufacturers only. Any deviations will be subject to removal and replacement, including any replacement of damaged items installed by others, at no additional cost.
26. Provide warranties and extended warranties as specified.
27. Provide attic stock as specified.
28. This Subcontractor will be required to provide detailed record documents (As-Builts) that document the following (including but not limited to): Architect's proposal request changes, RFI's, communication, Architect's supplemental instructions, field changes and other such approved changes.
29. One (1) year warranty for material and workmanship from the date of substantial completion.
30. Sales tax as required.

EXCLUSIONS:

1. Bond.
2. Dumpster.
3. Insulated metal panels.
4. Metal wall panels.
5. Hollow metal frames or doors.

ALTERNATES:

1. None.

ALLOWANCES:

1. None.

UNIT PRICES:

This Subcontract is a fixed lump sum Subcontract Agreement. For revisions to the scope of the project and/or revisions to the contract documents, the lump sum subcontract amount will be adjusted by change order at the following unit prices:

1. None.

SPECIAL TERMS AND CONDITIONS:



**SCOPE OF WORK
ASU CREST CENTER
JONESBORO, ARKANSAS**

Clark Job No. 1752

**BID PACKAGE 08.3 – GLASS & GLAZING
VERSION 1.0**

1. The scope of this work shall be completed within the specified schedule timeline.
2. This Subcontractor will provide sufficient manpower to meet the Project Schedule, including any overtime required to maintain the schedule, at no additional charge unless the necessity for overtime is caused by others failing to maintain their schedule through no fault of this Subcontractor or circumstances beyond control (such as “acts of God”).