

**SECTION 21 13 00**  
**FIRE-SUPPRESSION SPRINKLER SYSTEMS**

**PART 1 GENERAL**

**1.01 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

**1.02 SECTION INCLUDES**

- A. Wet-pipe sprinkler system.
- B. System design, installation, and certification.

**1.03 RELATED REQUIREMENTS**

- A. Section 07 84 00 - Firestopping.
- B. Section 21 05 00 - Common Work Results for Fire Suppression: Pipe and fittings.
- C. Section 21 05 48 - Vibration and Seismic Controls for Fire Suppression Piping and Equipment.
- D. Section 21 05 53 - Identification for Fire Suppression Piping and Equipment.
- E. Section 28 46 00 - Fire Detection and Alarm.

**1.04 REFERENCE STANDARDS**

- A. FM (AG) - FM Approval Guide; Current Edition.
- B. NFPA 13 - Standard for the Installation of Sprinkler Systems; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- C. UL (DIR) - Online Certifications Directory; Current Edition.

**1.05 ADMINISTRATIVE REQUIREMENTS**

- A. Preinstallation Meeting: Convene one week before starting work of this section.

**1.06 SUBMITTALS**

- A. See Section 01 30 00 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.
- C. Shop Drawings:
  - 1. Submit preliminary layout of finished ceiling areas indicating only sprinkler locations coordinated with ceiling installation.
  - 2. Indicate hydraulic calculations, detailed pipe layout, hangers and supports, sprinklers, components, and accessories. Indicate system controls.
  - 3. Submit shop drawings to Authorities Having Jurisdiction for approval. Submit proof of approval to Architect.
- D. Manufacturer's Certificate: Certify that system has been tested and meets or exceeds specified requirements and code requirements.
- E. Designer's qualification statement.
- F. Manufacturer's qualification statement.
- G. Installer's qualification statement.
- H. Operation and Maintenance Data: Include components of system, servicing requirements, record drawings, inspection data, replacement part numbers and availability, and location and numbers of service depot.
- I. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
  - 1. See Section 01 60 00 - Product Requirements for additional provisions.

2. Extra Sprinklers: Type and size matching those installed in quantity required by referenced NFPA design and installation standard.
3. Sprinkler Wrenches: For each sprinkler type.
- J. Project Record Documents: Record actual locations of sprinklers and deviations of piping from drawings. Indicate drain and test locations.

#### **1.07 QUALITY ASSURANCE**

- A. Maintain one copy of referenced design and installation standard on site.
- B. Comply with FM (AG) requirements.
- C. Designer Qualifications: Design system under direct supervision of a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.
- D. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- E. Installer Qualifications: Company specializing in performing the work of this section with minimum 3 years experience and approved by manufacturer.
- F. Equipment and Components: Provide products that bear FM (AG) label or marking.

#### **1.08 DELIVERY, STORAGE, AND HANDLING**

- A. Store products in shipping containers and maintain in place until installation. Provide temporary inlet and outlet caps. Maintain caps in place until installation.

### **PART 2 PRODUCTS**

#### **2.01 SPRINKLER SYSTEM**

- A. Sprinkler System: Provide coverage for building areas noted.
- B. Occupancy: Extra hazard; comply with NFPA 13.
- C. Water Supply: Determine volume and pressure from water flow test data.
- D. Interface system with building control system.
- E. Storage Cabinet for Spare Sprinklers and Tools: Steel, located adjacent to alarm valve.

#### **2.02 SPRINKLERS**

- A. Suspended Ceiling Type: Concealed pendant type with matching push on cover plate.
  1. Response Type: Quick.
  2. Coverage Type: Standard.
  3. Fusible Link: Fusible solder link type temperature rated for specific area hazard.
- B. Exposed Area Type: Upright type.
  1. Response Type: Quick.
  2. Coverage Type: Standard.
  3. Finish: Brass.
  4. Fusible Link: Fusible solder link type temperature rated for specific area hazard.
- C. Flexible Drop System: Stainless steel, multiple use, open gate type.
  1. Application: Use to properly locate sprinkler heads.
  2. Include all supports and bracing.
  3. Provide braided type tube as required for the application.
  4. Manufacturers:
    - a. Victaulic Company; Vic-Flex: [www.victaulic.com/#sle](http://www.victaulic.com/#sle).

### **PART 3 EXECUTION**

#### **3.01 INSTALLATION**

- A. Install in accordance with referenced NFPA design and installation standard.
- B. Install equipment in accordance with manufacturer's instructions.

- C. Place pipe runs to minimize obstruction to other work.
- D. Place piping in concealed spaces above finished ceilings.
- E. Center sprinklers in two directions in ceiling tile and provide piping offsets as required.
- F. Apply masking tape or paper cover to ensure concealed sprinklers, cover plates, and sprinkler escutcheons do not receive field paint finish. Remove after painting. Replace painted sprinklers.
- G. Flush entire piping system of foreign matter.
- H. Hydrostatically test entire system.
- I. Require test be witnessed by Fire Marshal.

### **3.02 INTERFACE WITH OTHER PRODUCTS**

- A. Ensure required devices are installed and connected as required to fire alarm system.

**END OF SECTION**

**This page was intentionally left blank for duplex printing.**