

SECTION 31 10 00
SITE CLEARING

PART 1 GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SECTION INCLUDES

- A. Clearing and protection of vegetation.
- B. Removal of existing debris.

1.03 RELATED REQUIREMENTS

- A. Section 01 10 00 - Summary: Limitations on Contractor's use of site and premises.
- B. Section 01 50 00 - Temporary Facilities and Controls: Site fences, security, protective barriers, and waste removal.
- C. Section 01 57 13 - Temporary Erosion and Sediment Control.
- D. Section 01 70 00 - Execution and Closeout Requirements: Project conditions; protection of bench marks, survey control points, and existing construction to remain; reinstallation of removed products.
- E. Section 02 41 00 - Demolition: Removal of built elements and utilities.
- F. Section 31 22 00 - Grading: Topsoil removal.
- G. Section 31 23 23 - Fill: Filling holes, pits, and excavations generated as a result of removal operations.

1.04 SUBMITTALS

- A. See Section 01 30 00 - Administrative Requirements, for submittal procedures.
- B. Site Plan: Showing:
 - 1. Areas for temporary construction and field offices.

1.05 QUALITY ASSURANCE

- A. An independent testing agency shall perform field quality test, as specified in Section 014533 - Special Inspections
- B. Employ services of a Geotechnical Consultant, approved by Architect, for the following services:
 - 1. Develop clearing techniques best suitable to site conditions at the time of construction.

PART 2 PRODUCTS

2.01 MATERIALS - NOT USED

PART 3 EXECUTION

3.01 SITE CLEARING

- A. Comply with other requirements specified in Section 01 70 00 - Execution and Closeout Requirements.
- B. Minimize production of dust due to clearing operations; do not use water if that will result in ice, flooding, sedimentation of public waterways or storm sewers, or other pollution.

3.02 EXISTING UTILITIES AND BUILT ELEMENTS

- A. Coordinate work with utility companies; notify before starting work and comply with their requirements; obtain required permits.
- B. Protect existing utilities to remain from damage.
- C. Do not disrupt public utilities without permit from authority having jurisdiction.
- D. Protect existing structures and other elements that are not to be removed.

3.03 VEGETATION

- A. Scope: Remove trees, shrubs, brush, and stumps in areas to be covered by building structure, paving, playing fields, lawns, and planting beds.
- B. Install substantial, highly visible fences at least 3 feet (1 m) high to prevent inadvertent damage to vegetation to remain:
 - 1. At vegetation removal limits.
 - 2. Around trees to remain within vegetation removal limits; locate no closer to tree than at the drip line.
 - 3. Around other vegetation to remain within vegetation removal limits.
- C. Vegetation Removed: Do not burn, bury, landfill, or leave on site, except as indicated.
- D. Restoration: If vegetation outside removal limits or within specified protective fences is damaged or destroyed due to subsequent construction operations, replace at no cost to Owner.

3.04 DEBRIS

- A. Remove debris, junk, and trash from site.
- B. Leave site in clean condition, ready for subsequent work.
- C. Clean up spillage and wind-blown debris from public and private lands.

END OF SECTION