

LEGEND	
---	PROPERTY LINE
FL	FIRE LANE STRIPING
④	PARKING COUNT
▨	CURB RAMP NOT IN PUBLIC ROW
♿	ACCESSIBILITY SPACE
PAVING MATERIAL LEGEND	
▨	STANDARD DUTY CONCRETE
▨	MEDIUM DUTY CONCRETE
▨	HEAVY DUTY CONCRETE
▨	CONCRETE SIDEWALK
▨	STRUCTURAL SLABS

KEYED NOTES	
①	PROPOSED MAN DOOR IN SCREEN WALL (REF ARCHITECTURAL PLANS FOR DETAILS AND SPECIFICATIONS)
②	PROPOSED GATE (REF ARCHITECTURAL PLANS FOR DETAILS AND SPECIFICATIONS)
③	PARKING LOT STRIPING, 4" SOLID WHITE STRIPE
④	PROPOSED 6" CURB.
⑤	END OF 6" CURB. INSTALL CURB TERMINATION.
⑥	4" SOLID WHITE STRIPING, 2'-0" O.C. @ 45°
⑦	PROPOSED ACCESSIBLE HC PARKING STALL WITH ACCESSIBLE PARKING SYMBOL AND SIGN
⑧	ACCESSIBLE RAMP
⑨	FIRE HYDRANT
⑩	PROPOSED SAWCUT/MATCH EXISTING PAVEMENT LINE
⑪	PROPOSED PIPE BOLLARD (CONTRACTOR TO NOTIFY ENGINEER FOR RELOCATION IN THE EVENT OF A CONFLICT WITH UTILITIES, FOUNDATION, ETC.)
⑫	PROPOSED GENERATOR PAD (REF. STRUCTURAL PLANS FOR DETAILS AND SPECIFICATIONS AND THE GEOTECHNICAL REPORT FOR PAD PREPARATION)
⑬	PROPOSED ANTI-CLIMB FENCING (COCHRANE CLEARVU, AMERISTAR MONTAGE II OR AMERISTAR IMPASSE II)
⑭	PROPOSED 8' HIGH CONTINUOUS RIBBON CHAIN-LINK FENCE WITH 3 STRAND BARBED WIRE TOP
⑮	PROPOSED SECURITY GATE (REF ARCHITECTURAL PLANS FOR DETAILS AND SPECIFICATIONS)
⑯	PROPOSED SCREEN WALL (REFERENCE ARCH. AND STRUCTURAL PLANS FOR DETAILS AND SPECIFICATIONS)

GENERAL NOTES	
1.	DIMENSIONS ARE TO FACE OF CURB UNLESS OTHERWISE NOTED.
2.	ALL RADII 3' UNLESS OTHERWISE NOTED.
3.	REFER TO ARCHITECTURAL PLANS FOR SITE LIGHTING POLES AND FIXTURES AND ELECTRICAL PLAN PRIOR TO PLACING PAVEMENT.
4.	REFER TO ARCHITECTURAL PLANS FOR EXACT BUILDING DIMENSIONS.
5.	SIDEWALKS TO HAVE A 5% MAXIMUM RUNNING SLOPE AND A 2% MAXIMUM CROSS SLOPE IN ACCORDANCE WITH ADA REQUIREMENTS.
6.	FIELD VERIFY ADA GRADES PRIOR TO PLACING PAVEMENT. CONTRACTOR SHALL CONSTRUCT ALL ACCESSIBLE ROUTES IN ACCORDANCE WITH ADA STANDARDS AND TAS.
7.	REF. IRRIGATION PLANS PRIOR TO PLACING PAVEMENT.
8.	CONTRACTOR SHALL BUDGET FOR ACCESSIBLE STALL STRIPING, FIRE LANE STRIPING, DIRECTIONAL ARROWS, ETC.
9.	SITE LIGHTING IS BY OTHERS. REF. SITE LIGHTING PLANS FOR LOCATIONS AND DETAILS PRIOR TO PLACING PAVEMENT.
10.	REF. BUILDING PLANS FOR ALL EXTERIOR STAIR DETAILS.
11.	CONTRACTOR TO ADJUST EXISTING SANITARY SEWER MANHOLES, STORM SEWER MANHOLES, ELECTRICAL MANHOLES, FIRE HYDRANTS, VALVE BOXES, WATER METERS, ETC. TO MATCH PROPOSED FINISHED GRADES IF NECESSARY.

ISSUES	
1	01/23/2026 DESIGN DEVELOPMENT


REVISIONS	

Kimley»Horn
© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
 1100 EAST PINEBLISS AVENUE, SUITE 100, TULSA, OKLAHOMA 74104
 LICENSE 200-48400
 MEMBER OF KIMLEY-HORN GROUP

NOT FOR CONSTRUCTION

This document is incomplete and may not be used for regulatory approval, permit or construction.
 Date of issue: 01/23/2026


SERVERFARM - ARK01
DESIGN DEVELOPMENT
 Clarksville, AR 72830



DIMENSION CONTROL AND PAVING PLAN (4 OF 8)

JOB SHEET 065011204

C116



CAUTION!!
 EXISTING UNDERGROUND UTILITIES IN THE AREA CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY REPAIRS TO EXISTING UTILITIES DUE TO DAMAGE INCURRED DURING CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES ON THE PLANS.