

- 1. TOP OF SLAB ELEVATION = SEE CIVIL. REFERENCE INTERIOR FLOOR LEVELS ARE AT +0'-0" UNLESS NOTED OTHERWISE.
2. PROVIDE CONTROL JOINTS IN GYPSUM BOARD WALLS ABOVE THE CORNER OF ALL INTERIOR DOOR AND WINDOW FRAMES...
3. ALL WALL-MOUNTED FIRE EXTINGUISHERS SHALL BE MOUNTED AT 45° AFF MAX. TO EXTINGUISHER HANDLE UNO.
4. PROVIDE CAST IRON BOOT AT ALL DOWN SPOUTS TO CURB-DRAINAGE SYSTEM...
5. PROVIDE 4" HIGH CORNER GUARDS AT ALL EXPOSED GYP. BOARD CORNERS MOUNTED AT 4" AFF TO BOTTOM.
6. ALL CORRIDORS ADJACENT TO DATA HALLS AND THE LOADING DOCK SHALL BE 10' CLEAR IN HEIGHT TO ALL PHYSICAL OBJECTS (PIPING, DUCTWORK, CAMERAS, DOOR FRAMES)...
7. COORDINATE CUSTOM WIRE MESH SCREEN ABOVE GALLERY WALLS WITH OWNER AND MEP CONSULTANT...
8. ALL CONCRETE EQUIPMENT PADS, ASSOCIATED SIDEWALKS, AND CONCRETE STAIR SUPPORT PADS FOR FUTURE EQUIPMENT SHALL BE INSTALLED AS PART OF DAY ONE SCOPE...
9. ALL DOORS HINGES SHALL BE LOCATED 6" AWAY FROM INTERIOR ROOM CORNER OR CENTERED IN ROOM UNO.
10. REFER TO CONSULTANT ENGINEER DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION.
11. ALL GENERAL NOTES APPLY UNLESS NOTED OTHERWISE ON DRAWINGS.
12. ALL NOTES MARKED AS TYP. APPLY TO SIMILAR CONDITIONS.
13. THESE DRAWINGS, DIMENSIONS GOVERN.
14. WALL DIMENSIONS IN NEW CONSTRUCTION ARE TO FACE OF FINISH UNLESS NOTED OTHERWISE.
15. PROVIDE DOUBLE STUDS BACK TO BACK ON BOTH SIDES OF NEW DOOR FRAMES.
16. PROVIDE CONTINUOUS SILICONE CAULK AT ALL NEW DOOR FRAMES WHERE GYP. BD. AND FRAMES MEET BEFORE PAINTING OCCURS.
17. "MIN." FOR DIMENSIONS INDICATES MINIMUM ACCEPTABLE DIMENSION, MOST "MIN." DIMENSIONS WILL BE GREATER THAN INDICATED.
18. DRAWING, NOTIFY ARCHITECT IMMEDIATELY. PROVIDE ALL NECESSARY MATERIALS, FIRE RETARDANT WOOD FRAMING, FITTINGS, BRACKETING, CASINGWORK, ACCESSORIES, ESCUTCHEONS, ETC. AS REQUIRED TO SATISFY COMPLETE THE WORK, INCLUDING BUT NOT LIMITED TO: DOOR AND WINDOW FRAMES, CONSULTANT ENGINEER WORK, MILLWORK, CASINGWORK, ACCESSORIES, HANDRAILS, GRAB BARS, FIXTURES, EQUIPMENT, FITTINGS, ETC.
19. CONTRACTOR SHALL PLASTER AND SCAR PATCH FOR ALL TRADES.
20. PROVIDE 24" X 24" ACCESS PANELS FOR ALL WALLS AND CEILINGS WHERE ACCESS TO PIPES AND VALVES OR PULL BOXES IS REQUIRED. ACCESS PANELS RATING SHALL MATCH WALLS RATING.
21. REFER TO A02-00 FOR PARTITION WALL TYPE TAGS.
22. DATA HALL AND RAH GALLERY PERIMETER WALLS SHALL BE PROVIDED WITH INSULATION AND VAPOR BARRIER AND CONTAINMENT. SEE NOTES AND DETAILS ON A02-00 AND FLOOR PLANS FOR ADDITIONAL INFORMATION.
23. REFER TO A02-00 FOR ADDITIONAL INFORMATION FOR PARTITIONS WALL TAGGED WITH "V". "V" INDICATES THE REQUIREMENT FOR CONTINUOUS VAPOR RETARDER, INSULATION, AND CONTAINMENT.
24. THERMAL INSULATION AND VAPOR BARRIER SHALL BE ADDED TO WALLS ON HUMIDITY CONTROLLED SIDE OF PARTITIONS SEPARATING SHELL AND CONDITIONED SPACES. REFERENCE PARTITION TAGS AND LEGEND.
25. ALL PENETRATIONS THROUGH ACOUSTIC PARTITIONS SHALL BE ACOUSTICALLY SEALED. ALL PENETRATIONS THROUGH FIRE RATED PARTITIONS SHALL BE FIRE SEALED/CAULKED TO MAINTAIN THE FIRE RATING OF THE WALL IT PENETRATES.
26. PROVIDE CONTINUOUS AIR BARRIER AND INSULATION AT EXTERIOR BLDG ENVELOPE TO COMPLY WITH CURRENT ENERGY CODE AT EXTERIOR CONCRETE.
27. FOR FIRE EXTINGUISHER REQUIREMENTS, SEE ALSO LIFE SAFETY PLANS.
28. COORDINATE ELECTRICAL, PHONE, AND DATA ROUGH IN LOCATIONS WITH OWNER PRIOR TO INSTALLATION.
29. REFER TO ELECTRICAL AND TELECOM DRAWINGS AND SPECIFICATIONS FOR REQUIREMENTS RELATED TO FIRE RETARDANT PLYWOOD AND FIRE RETARDANT PAINTING. PROVIDE 3/4" THICK FIRE TREATED PLYWOOD SHEET (STARTING AT 0' AFF, X 9'-0" AFF, TALL X LENGTH AS REQUIRED).
30. INSTALLED AT ALL CONDUIT PULL BOX LOCATIONS, PLYWOOD SHALL BE PAINTED ON ALL EXPOSED SIDES, COLOR TBD BY ARCHITECT. ENSURE A FIRE RATING LABEL IS VISIBLE ON PLYWOOD IN AT LEAST ONE LOCATION.
31. PROVIDE CONCRETE HOUSE KEEPING PADS AS REQUIRED AT EQUIPMENT. REFER TO CONSULTANT ENGINEER DRAWINGS AND SPECS. PADS SHALL BE SEALED AND CHAMFERED EDGE SHALL BE PROVIDED AT THE PERIMETER. ENSURE PAD LOCATIONS AND SIZES DO NOT OBSTRUCT MINIMUM COSE REQUIRED EGRESS AND/OR ADA CLEARANCES. COORDINATE INSTALLATION/DOCUMENTATION OF FIREPROOFING AT RATED PARTITIONS IF HOUSEKEEPING PAD IS LOCATED ADJACENT TO FIRE RATE WALL. SUBMIT ALL HOUSEKEEPING PADS TO ARCHITECT AND STRUCTURAL ENGINEER FOR REVIEW PRIOR TO CONSTRUCTION AND INSTALLATION.

ISSUES table with columns: No., Date, Description. Includes entries for 1/11/2025 CONCEPTUAL, 1/12/2025 SCHEMATIC DESIGN, 1/21/2025 STILL MILL ORDER, 4/12/2026 DESIGN DEVELOPMENT.

REVISIONS table with columns: No., Description. Includes entries for 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13.

NOT FOR CONSTRUCTION. This document is incomplete and may not be used for regulatory approval, permit or construction. Date of issue: 01/23/2026

ARK01 DESIGN DEVELOPMENT CLARKSVILLE, AR 72830

Grid coordinate table with columns L, K, J, I, H, G, F, E, D, C, B, A and rows P, N, M.

FLOOR PLAN - LEVEL ONE - OVERALL



1 FLOOR PLAN 3/64" = 1'-0"

1/23/2026 2:35:35 PM A02-01 FLOOR PLAN - LEVEL ONE - OVERALL