



1. REFER TO SPECIFICATION 23 09 00 FOR CONTROLS RELATED INSTALLATION REQUIREMENTS
2. REFER TO SPECIFICATION 23 09 93 FOR SEQUENCE OF OPERATIONS.
3. REFER TO ELECTRICAL PROJECT SPECIFICATIONS FOR ALL WIRING INSTALLATION REQUIREMENTS.
4. INSTALL FLEXIBLE CONNECTIONS IN RUNS OF RACEWAYS, CABLES, WIREWAYS, CABLE TRAYS, AND CABLES WHERE THEY ARE CONNECTED TO JOINTS, SEISMIC JOINTS, OR ARE SUBJECT TO STRUCTURAL DEFLECTIONS OR INTERSTORY BUILDING DRIFTS. FLEXIBLE CONNECTIONS SHALL BE INSTALLED WHERE ADJACENT SECTIONS OF RACEWAYS ARE SUPPORTED BY DIFFERENT STRUCTURAL MEMBERS OR WHERE THEY TERMINATE TO EQUIPMENT THAT IS ANCHORED OR SUPPORTED TO A DIFFERENT STRUCTURAL ELEMENT. CONTRACTOR SHALL COORDINATE WITH STRUCTURAL AND/OR MECHANICAL ENGINEERS IN ORDER TO PROVIDE THE REQUIRED FLEXIBLE CONNECTIONS.
5. CONTRACTOR SHALL COORDINATE INSTALLATION OF EQUIPMENT WITH OTHER CONTRACTORS AND OTHER TRADES AS NEEDED. THIS INCLUDES COORDINATING WITH LABOR LOCALITIES AND TRADE UNIONS WITH OWNER PERMITS TO INCORPORATE ANY TENANT REQUIREMENTS FOR NON-SKIPS.
6. INSTALLATION OF ALL THERMOSTATS AND DIFFERENTIAL TEMPERATURE SENSORS SHALL BE COORDINATED WITH ALL OTHER TRADES BEFORE FOR INSTALLATION HEIGHT ABOVE FINISHED FLOOR.
7. CONTROL PANELS ARE FED FROM TWO SEPARATE 120VAC POWER SOURCES.
8. PROVIDE FIELD COORDINATION WITH SYSTEM INTEGRATOR ON ALL PANELS.
9. CONTROLS AND ELECTRICAL CONTRACTORS TO COORDINATE ALL ETHERNET COPPER AND FIBER CABLE WITH TELECOM CONTRACTORS.

[illegible][illegible][illegible]

NOT FOR CONSTRUCTION

L	K	J	
G	E	C	A
H	F	D	B
P	N	M	

IC02-01G

