

ARCHITECTURAL ABBREVIATIONS

AB	ANCHOR BOLT	KG	KILOGRAM
ACOUST.	ACOUSTICAL	LCB	LIQUID CHALK BOARD
AD	AUXILIARY DRAIN	LM	LINEAL METER
ADJ.	ADJUSTABLE	LG	LONG
ADMIN.	ADMINISTRATION	MAS	MASONRY
A.F.F.	ABOVE FINISH FLOOR	MATL.	MATERIAL
AGGRE.	AGGREGATE	MAX	MAXIMUM
ALUM.	ALUMINUM	MB	MINI-BLINDS
BD	BOARD	M.D.	METAL DECK
B.F.F.	BELOW FINISH FLOOR	MECH.	MECHANICAL
BLKG	BLOCKING	MEMB.	MEMBRANE
BM	BEAM	MEZZ.	MEZZANINE
B.O.	BOTTOM OF	MFR	MANUFACTURER
BPL	BASE PLATE	MISC.	MISCELLANEOUS
BS	BOTH SIDES	MO	MASONRY OPENING
BTWN.	BETWEEN	M.S.	METAL STUD
B.U.R.	BUILT-UP ROOF	MTL.	METAL
CAL.	CALIPER	N.I.C.	NOT IN CONTRACT
CL	CENTERLINE	NS	NON-SHRINK
CFC	COMBINED FACILITIES COMPLEX	N.T.S.	NOT TO SCALE
CSF	COMBINED SHARED FACILITIES	OC	ON CENTER
CG	CORNER GUARD	OD	OUTSIDE DIAMETER
CJ	CONTROL JOINT	OFW	OUTSIDE FACE OF WALL
CLG	CEILING	OPNG	OPENING
CMU	CONCRETE MASONRY UNIT	OPP.	OPPOSITE
COL.	COLUMN	P.LAM	PLASTIC LAMINATE
CONC.	CONCRETE	PL	PLATE
CONC. BLK	CONCRETE BLOCK	PLYWD.	PLYWOOD
CONST.	CONSTRUCTION	PNL	PANEL
CONT.	CONTINUOUS	PROD	PRODUCE
CT	CERAMIC TILE	KG/SQM	KILOGRAMS PER SQUARE METER
DB	DECK BEARING	KG/SQCM	KILOGRAMS PER SQUARE CENTIMETER
DIM.	DIMENSION	QTY	QUANTITY
DR	DOOR	R	RISER
DTL	DETAIL	R	RADIUS
DWG	DRAWING	RD	ROOF DRAIN
EA	EACH	REFRIG	REFRIGERATION
E.B.	EXPANSION BOLT	REINF	REINFORCING
EF	EXHAUST FAN	REQD	REQUIRED
E.I.F.S.	EXTERIOR INSULATION AND FINISH SYSTEM	ROOM	ROOM
EJ	EXPANSION JOINT	RPP	RACK POST PROTECTOR
ELEC.	ELECTRICAL	SC	SOLID CORE
ELEV.	ELEVATION	SCHED.	SCHEDULE
EQ	EQUAL	SECT.	SECTION
EQUIP.	EQUIPMENT	SHT.	SHEET
EW	EACH WAY	SIM.	SIMILAR
EWC	ELECTRIC WATER COOLER	SPECS	SPECIFICATIONS
EXIST.	EXISTING	SMFE	SURFACE MOUNTED FEC
EXP	EXPANSION	SRFE	SEMI-RECESSED FEC
EXT.	EXTERIOR	S	SEWER
F	FEMALE	SS	SANITARY SEWER
FD	FLOOR DRAIN	S.S.	STAINLESS STEEL
FE	FIRE EXTINGUISHER	SSC	STAINLESS STEEL CLOSURE
FEC	FIRE EXTINGUISHER CABINET	SST	STAINLESS STEEL THRESHOLD
F.F.E.	FINISH FLOOR ELEVATION	STB	STAFF TRAINING BUILDING
FIN.	FINISH	STL	STEEL
FLR	FLOOR	STO.	STORAGE
FND	FOUNDATION	STRUCT.	STRUCTURAL
F.O.C.	FACE OF CONCRETE	SYM.	SYMBOL
FRP	FIBERGLASS REINFORCED PANEL	T	TREAD
FTG	FOOTING	T & B	TOP AND BOTTOM
GA	GAGE	THK	THICK
GALV	GALVANIZED	THRESH.	THRESHOLD
GR	GUARD RAIL	TJ	TOOLED JOINT
GP	GUARD POST	TO	TOP OF
GYP	GYPSUM	T.O.S.	TOP OF STEEL
GYP.BD.	GYPSUM BOARD	T.O.P.	TOP OF PANEL
H	HIGH	TS	TUBE STEEL
HD	HANDICAP	TYP	TYPICAL
HC	HOLLOW CORE	T.O.M.	TOP OF MASONRY
HDW	HARDWARE	U.N.O.	UNLESS NOTED OTHERWISE
HM	HOLLOW METAL	VCT	VINYL COMPOSITION TILE
HORIZ.	HORIZONTAL	VERT.	VERTICAL
HP	HORSEPOWER	VEST.	VESTIBULE
HT	HEIGHT	V.I.F.	VERIFY IN FIELD
INFO.	INFORMATION	W	WIDE
INSUL.	INSULATION	W/	WITH
INT	INTERIOR	WC	WATER CLOSET
JAN	JANITOR.	WD	WOOD
JT	JOINT	WDW	WINDOW
JST	JOIST	WG	WALL GUARD
KCJ	KEYED CONTROL JOINT	W/O	WITHOUT
LAV.	LAVATORY	WP	WATERPROOFING
		WT	WEIGHT
		WWF	WELDED WIRE FABRIC

INDEX OF DRAWINGS

SHEET NUMBER	SHEET NAME	ISSUE DATE	REVISION DATE
GENERAL INFORMATION			
G-001	TITLE SHEET	09-23-2024	
G-002	INDEX, SYMBOLS & ABBREV.	09-23-2024	11-15-2024
LIFE SAFETY			
GI001	LIFE SAFETY CODE ANALYSIS	09-23-2024	
GI101	LIFE SAFETY FLOOR PLAN	09-23-2024	
CIVIL			
VF101	SITE SURVEY	09-23-2024	
C-001	CIVIL NOTES	09-23-2024	
CS100	CIVIL SITE PLAN	09-23-2024	11-15-2024
CS101	CIVIL SITE PLAN	09-23-2024	11-15-2024
CS102	CIVIL SITE PLAN	09-23-2024	11-05-2024
CG100	SITE GRADING AND DRAINAGE PLAN	09-23-2024	
CG101	SITE GRADING AND DRAINAGE PLAN	09-23-2024	
CG102	SITE GRADING AND DRAINAGE PLAN	09-23-2024	11-05-2024
CU100	SITE UTILITY PLAN	09-23-2024	
CU101	SITE UTILITY PLAN	09-23-2024	10-09-2024
C-501	CIVIL DETAILS	09-23-2024	
C-502	CIVIL DETAILS	09-23-2024	11-15-2024
C-503	CIVIL DETAILS	09-23-2024	
C-504	CIVIL DETAILS	09-23-2024	
CE100	OVERALL SITE EROSION PLAN AND SEDIMENTATION CONTROL PLAN	09-23-2024	
CE101	SITE EROSION PLAN AND SEDIMENTATION CONTROL PLAN	09-23-2024	
CE102	SITE EROSION PLAN AND SEDIMENTATION CONTROL PLAN	09-23-2024	
CE501	SITE EROSION PLAN AND SEDIMENTATION CONTROL DETAILS	09-23-2024	
STRUCTURAL			
S-001	STRUCTURAL DESIGN CRITERIA AND GENERAL NOTES	09-23-2024	11-05-2024
S-101	TRUCK WASH FOUNDATION AND FRAMING PLANS	09-23-2024	
S-301	TYPICAL FOUNDATION DETAILS	09-23-2024	
S-302	FOUNDATION DETAILS	09-23-2024	
ARCHITECTURAL			
AS101	ARCHITECTURAL SITE PLAN	09-23-2024	11-05-2024
AS102	ARCHITECTURAL SITE PLAN- ENLARGED	09-23-2024	11-05-2024
A-101	PLANS - WASH BAY	09-23-2024	11-15-2024
A-102	PLANS- SHOOTING RANGE	09-23-2024	11-05-2024
A-301	BUILDING SECTIONS	09-23-2024	
A-310	WALL SECTIONS	09-23-2024	
A-501	DETAILS	09-23-2024	
A-540	ROOF DETAILS	09-23-2024	10-09-2024
A-620	DOOR SCHEDULE	09-23-2024	
PLUMBING			
P-001	PLUMBING LEGEND AND NOTES	09-23-2024	
P-101	WASH BAY FLOOR PLAN - PLUMBING	09-23-2024	11-05-2024
P-601	PLUMBING SCHEDULES AND DETAILS	09-23-2024	11-05-2024
P-901	PLUMBING RISER DIAGRAM	09-23-2024	11-05-2024
MECHANICAL			
M-101	MECHANICAL PLAN - WASH BAY	09-23-2024	10-09-2024
ELECTRICAL			
E-001	ELECTRICAL LEGEND	09-23-2024	
E-101	OVERALL SITE PLAN, SHOOTING RANGE AND WASH BAY ELECTRICAL PLAN	09-23-2024	11-05-2024
E-501	ELECTRICAL DETAILS	09-23-2024	10-09-2024
E-601	ELECTRICAL SCHEDULES & SINGLE-LINE DIAIGRAM	09-23-2024	11-05-2024

NOTES

GENERAL CONSTRUCTION REQUIREMENTS:

- ALL WORK SHALL BE DONE IN A SAFE AND WORKMANLIKE MANNER AND IN STRICT ACCORDANCE WITH THE IBC, GOVERNING BUILDING CODES, NATIONAL ELECTRIC CODE, AND ALL APPLICABLE REGULATIONS AND ORDINANCES HAVING JURISDICTION.
- THE CONTRACTOR IS TO UNDERSTAND ALL DRAWINGS AND SPECIFICATIONS COMPLETELY. EACH ASPECT OF THE WORK MAY BE INDICATED IN ONE DISCIPLINE OR INDICATED IN MULTIPLE DISCIPLINES. REVIEW ALL INFORMATION FROM ALL DISCIPLINES AND COMPLETELY FIELD VERIFY ALL CONDITIONS BEFORE IMPACTING EXISTING CONDITIONS OR PROVIDING NEW WORK.
- EACH SUBCONTRACTOR IS RESPONSIBLE FOR HAVING A THOROUGH KNOWLEDGE OF ALL DRAWINGS AND SPECIFICATIONS IN THEIR RELATED FIELD. THE FAILURE TO DO SO DOES NOT RELIEVE ANY RESPONSIBILITY FOR PERFORMING THIS WORK PROPERLY. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED BECAUSE OF CONDITIONS THAT OCCUR DUE TO FAILURE TO FAMILIARIZE WORKERS WITH THIS KNOWLEDGE.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN THE FIELD PRIOR TO FABRICATION OF ALL ITEMS, AND IF ANY DISCREPANCIES ARE FOUND BETWEEN WHAT IS SHOWN ON THE PLANS AND WHAT EXISTS IN THE FIELD, CONTACT THE ARCHITECT TO DETERMINE THE PROPER COURSE OF ACTION. THE CONTRACTOR'S APPROVAL FOR FABRICATION INDICATES THE ACCEPTANCE OF EXISTING CONDITIONS.
- THE CONTRACTOR SHALL KEEP THE CONSTRUCTION AREA FREE AND CLEAR OF DEBRIS. REMOVE TRASH AND DEBRIS FROM CONSTRUCTION AREA AND DO NOT ALLOW TO ACCUMULATE. PROVIDE EXTINGUISHERS AS REQUIRED BY LOCAL AND STATE AUTHORITIES, UL LISTED 2A-20BC DRY CHEMICAL FIRE EXTINGUISHERS, ACCESSIBLE AT ALL TIMES WITHIN ALL CONSTRUCTION AREAS.
- THE CONTRACTOR SHALL MAINTAIN THE REQUIRED NUMBER OF EXITS FROM THE FACILITY. MAINTAIN EXITS, EXIT SIGNS AND EMERGENCY LIGHTING AT ALL TIMES AS REQUIRED BY THE GOVERNING AUTHORITIES.
- REPAIR, RE-ROUTE AND EXTEND ALL SERVICES, PIPING, CONDUIT OF EXISTING ITEMS AND EQUIPMENT AS REQUIRED DURING THE CONSTRUCTION PROCESS FOR THE COMPLETE INSTALLATION AND OPERATIONS OF NEW EQUIPMENT. THIS INCLUDES ALL ITEMS SHOWN OR NOT SHOWN ON THE DRAWINGS. RESET EXISTING EQUIPMENT OR RELATED ITEMS AS REQUIRED FOR PROPER OPERATION.
- ALL QUESTIONS RELATING TO THE CONSTRUCTION OF THIS PROJECT SHALL BE DONE IN WRITTEN FORM USING THE "REQUEST FOR INFORMATION" FORM, INCLUDED IN THE SPECIFICATIONS, THROUGH THE GENERAL CONTRACTOR ONLY. FOLLOW INSTRUCTIONS WHEN COMPLETING AND SENDING THIS FORM.


GENERAL SITE VERIFICATION REQUIREMENTS:

- EXISTING CONDITIONS SHOWN IN THESE PLANS ARE BASED ON LIMITED FIELD OBSERVATIONS BY THE ARCHITECT AND ORIGINAL DESIGN DRAWINGS. ALL EXISTING MATERIAL, DIMENSIONS, ELEVATIONS, AND GENERAL CONDITIONS OF THE BUILDING SHALL BE VERIFIED BEFORE PURCHASE OF MATERIAL AND CONSTRUCTION. NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BETWEEN PLANS AND FIELD CONDITIONS IMMEDIATELY.
- ALL UTILITY LOCATIONS SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL FIELD VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES (WHETHER SHOWN OR NOT) PRIOR TO THE SUBMISSION OF HIS BID OR THE COMMENCEMENT OF CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE ARCHITECT OF THE DISCOVERY OF EXISTING UTILITIES NOT SHOWN OR NOTED ON DRAWINGS. THE CONTRACTOR SHALL VERIFY EXACT LOCATIONS AND DEPTHS OF UNDERGROUND UTILITY SERVICES PRIOR TO ANY EXCAVATION.


GENERAL FLOOR PLAN NOTES:

- REFER TO ARCH PLAN SHEETS (A-101-102)
- ALL DIMENSIONS ARE TO FACE OF CMU OR STUD UNLESS NOTED OTHERWISE.

SYMBOLS LEGEND



SECTION INDICATIONS



Project

SHERWOOD
 SHERWOOD PUBLIC WORKS
 TWO PINES & LANDERS ROAD
 SHERWOOD, AR 72117

Design Phase

CONSTRUCTION DOCUMENTS

Revisions

No.	Date	Description
1	10-09-2024	ADD 001
2	11-05-2024	ADD 002
3	11-15-2024	ADD 003

Stamp

Notes

- CROMWELL ARCHITECTS ENGINEERS, INC. ALL RIGHTS RESERVED
- THIS SHEET DESIGNED FOR COLOR PRINTING. CRITICAL INFORMATION MAY BE LOST WITH BLACK AND WHITE PRINTING.

Project Number **2023-249**
 Issue Date **09-23-2024**
 Sheet Title **INDEX, SYMBOLS & ABBREV.**
 Sheet Number **G-002**