ADDENDUM NO. 4 - Issued 04-24-2025

to the Project Manual and Drawings for

ADMINISTRATION BUILDING - HVAC IMPROVEMENTS PULASKI COUNTY SPECIAL SCHOOL DISTRICT LITTLE ROCK, ARKANSAS WDD JOB NO. 24-078

WITTENBERG, DELONY & DAVIDSON, INC. 5050 NORTHSHORE LANE NORTH LITTLE ROCK, ARKANSAS 72118 (501)376-6681

This addendum forms a part of the contract documents and modifies or interprets the Project Manual and/or Drawings as noted herein.

REFER TO THE DRAWINGS:

Sheet E-1:

1. Refer to clouded revisions for additional scope of work for temporary emergency standby generator provisions for IT Server Room equipment and IT Server Room mechanical equipment.

Sheet E-2:

1. Refer to clouded revisions for additional scope of work for temporary emergency standby generator provisions for I.T. Server Room equipment and I.T. Server Room mechanical equipment. Additional scope added for existing Panel "MP".

Sheet E-3:

1. Refer to clouded revisions for additional scope of work for existing Panel "MP".

All Sheets:

1. The scope of work for this project includes demolition and installation of electrical main service switchgear including normal power service from pad mount transformer and emergency standby service from standby generator. The overall project scope of work time period (mechanical and electrical) shall be no more than one (1) working week, which can include two weekends for a total of 9 days starting on a Friday afternoon until Monday morning. The awarded contractor will be required to coordinate the exact date of this work with the Architect, Engineer and owner well in advance of the expected power shut-down and will be required to provide temporary power for IT server room equipment racks and IT server room HVAC equipment.

PCSSD Admin HVAC: #24-078 Page 1 of 2

REVISED DRAWINGS:

Sheets E-1, E-2 and E-3 of original issue date 03-28-2025 and revised 04-24-2025 are attached to this addendum and are made a part of the Bid Documents.

END OF ADDENDUM NO. 4

PCSSD Admin HVAC: #24-078 Page 2 of 2